

## ADDENDUM NO. 1 INVITATION TO BID 15-060 MARSH CREEK WATERSHED IMPROVEMENT PROJECT

COMPLETE THIS ADDENDUM, SIGN and SUBMIT with the ITB.
City of Sandy Springs – Purchasing Division
Sandy Springs City Hall
7840 Roswell Road Bldg. 500
Sandy Springs, GA 30350

\*NEW DUE DATE: MAY 7, 2015; 2:00 P.M.

## **QUESTIONS/RESPONSES**

- 1. Can the CAD file be made available for estimating purposes? We can sign a release and understand that only the actual plans are part of the bid.
  - a. Unfortunately we are not in a position to release the CAD files.
- 2. Please clarify/ confirm that rock excavation is to be included in Grading Complete and that the quantity encountered is the Contractor's risk.
  - a. Answer is Rock excavation is to be included in Grading Complete per Special Provision Section 210 Grading Complete.
- 3. Note to be added to sheet C-04, General Grading Notes: 9. The pond level will be required to be brought to full pool to verify retention of bentonite layer, planting of littoral shelf and for placement and operation of fountain prior to final project acceptance.
- 4. Sheet L-02, the 36" Chestnut Oak located near the end of the existing asphalt drive at the maintenance access is to be removed and the cut out area sodded. The tree fence, shown on C-13, will be relocated along the common property line with 80 Johnson Ferry Road to the length shown.
- 5. Sheet C-03, the 6' chain link fence along the back parking lot of 124 Johnson Ferry Road has been changed to a 6' decorative fence per the attached exhibit "A". The proposed length of 6' decorative fence is 190 feet and is shown on the revised bid tab. The length of the 6' chain link fence has been reduced on the bid tab by 190' from 731' to 541'.
- 6. Sheet C-03, the entrance at 124 Johnson ferry Road will be revised to accommodate two way traffic. The entrance at 126 Johnson ferry Road will be abandoned and 24" curb and gutter and 6' sidewalk will be installed. The area between the new sidewalk and the asphalt driveway cut will be sodded. Refer to the attached exhibit "A" for details. The Bid Tab quantities and line items have been adjusted to accommodate these changes.
- 7. Sheet C-03, Offsite Storm Sewer Pipe Installation add Note 12. The contractor will repair or replace irrigation system components on 124 and 126 Johnson Ferry Road removed or damaged during the installation of the offsite storm drain system.
- 8. The contractor shall provide a 2 year warranty and maintenance agreement on all plantings for the project.

9. A 30"X48" aluminum access door will be provided on the Double Wing Catch Basin above pipe 5 for trash removal and sump access in lieu of the manhole ring and cover. The Aluminum access door is to have a stainless steel hold open arm, stainless steel hinges and attaching hardware, aluminum frame, padlock bar, recessed lifting handle and be single leaf construction with minimum 300 lbs. per sq. ft. load rating meeting Halliday Products Series S1R3048 or approved equal.

I hereby acknowledge receipt of Addendum 1 for ITB #15-060 MARSH CREEK WATERSHED IMPROVEMENT PROJECT and have incorporated the changes into my response for the abovementioned Invitation to Bid.


COMPANY NAME:	CONTACT PERSON:				
ADDRESS:		CITY:	STATE:	ZIP:	
PHONE:	FAX:	EMAIL ADI	ORESS:		
SIGNATURE:		DATE	E:		

PHASE	GA. DOT PAY ITEM DESCRIPTION ITEM NO.		UNIT	QUANTITY	COST	TOTAL COST
Construct Wet Pond						
	210-0100	GRADING COMPLETE	LS	1		
	163-0001	EROSION CONTROL COMPLETE	LS	1		
	550-1482	48" RCP TYPE IV	LF	16		
	550-1360	36" RCP TYPE III	LF	10		
	550-1300	30" RCP TYPE III	LF	43		
	550-1240	24" RCP TYPE III	LF	26		
	550-4248	48" HEADWALL STD 1125	EA	1		
	550-4236	36" HEADWALL STD 1125	EA	1		
	550-4230 550-4224	30" HEADWALL STD 1125 24" HEADWALL STD 1125	EA EA	1		
	668-1100	1034D CATCH BASIN	EA EA	1		
	668-2100	1019-A PEDESTAL INLET	EA EA	2		
	603-2180	RIP RAP TP3 - 12"	SY	190		
	003-2160	POND RISER COMPLETE	EA	190		
		TRASH SCREEN	EA	1		+
		36 FTB SNOUT	EA EA	1		
		30" x 48" ACCESS DOOR	EA EA	1		
		STRUCTURAL POND WALL COMPLETE	LS	1		
		GRAVITY RETAINING WALL COMPLETE	LS	1		
		POND WALL/RISER VENEER	SF	1460		
		SUMP PUMP COMPLETE	EA	1460		
		UNDERDRAIN SYSTEM COMPLETE	LS	1		
		BENTONITE LINER	TN	83		
Install Fountain	+	DENTONITE LINEK	IIV	63		
msidii Fuunidin		FOUNTAIN COMPLETE	LS	1		
Install Bioretention		FOUNTAIN COWFLETE	LS	1		
IIISIAII DIOTELETILIOTI	550-1360	36" RCP TYPE III	LF	55		_
	550-4236	36" HEADWALL STD 1125	EA	1		
	668-2100	1019-A PEDESTAL INLET	EA EA	1		
	000-2100	UNDERDRAIN SYSTEM COMPLETE	LS	1		_
	+	ENGINEERED SOIL	CY	1300		_
	+	ROUNDED RIVER ROCK (RIP RAP PAD)	EA	3		
Plant Native Vegetation		ROUNDED RIVER ROCK (RIP RAP PAD)	EA	3		
Piani Nalive vegetation		PLANT BIO RETENTION POND	LS	1		
Cita Landacana	+	PLANT BIO RETENTION POND	LS	l I		
Site Landscape	441-6012	6"X24" CONCRETE C AND G	LF	218		
	441-0018	CONCRETE APRON STD A1 - 8"	EA	1		
	441-0104	SIDEWALKS	SY	1042		
	441-0104	PERMEABLE PAVER COMPLETE	LS	1042		
		CHAIN LINK FENCE-6'	LF	541		
		METAL DECORATIVE FENCE-4'	LF	1162		
			LF LF			
		METAL DECORATIVE FENCE-6' DECORATIVE COLUMNS	EA	190 6		
				_		
		BENCHES	EA EA	3		
	+	TRASH RECEPTICAL SECURITY LIGHT COMPLETE		1		_
	+		EA EA	3		_
		BIKE RACK				
	-	PICNIC TABLES WOOD OBSERVATION DECK	EΑ	3		
	+		EA	1		
		DOG WASTE STATION	EA	1		
		WATER SERVICE COMPLETE	LS	1		
		IRRIGATION SYSTEM COMPLETE	LS	1		
		SHADE STRUCTURE	EA	1		
		HC SIGN/MARKING	LS	1		
Officita Otomic	1	SITE PLANTING/LANDSCAPE	LS	1		
Offsite Storm	444 4000	OALWOUT CONCEPTE		60.00		
	444-1000	SAWCUT CONCRETE	LF	80.00		
	150-0001	TRAFFIC CONTROL	LS	1.00		
	550-1540	54" RCP TYPE III	LF	386.00		
	550-4254	54" HEADWALL STD 1001B	EA	1.00		
	668-4300	STORM SEWER MH	EA	4.00		
	610-2700	CONCRETE REMOVAL	SY	245.00		
	441-0104	SIDEWALK 4"	SY	130.00		
	441-0018	DRIVEWAY CONCRETE 8"	SY	32.00		
	441-6012	6"X24" CONCRETE C AND G	LF	45.00		
	441-0018	CONCRETE APRON STD A1 - 8"	EA	1.00		
	700-9300	SOD	SF	4000.00		
		REPLACE IRRIGATION HEADS/PIPE	LS	1.00		
		REPLACEMENT TREES	EA	4.00		
	1	TOTAL BID PRICE				1

## SERIES S1R ACCESS DOOR

## STANDARD FEATURES:

- AUTO-LOCK T-316 STAINLESS STEEL HOLD OPEN ARM WITH RELEASE HANDLE
- T-316 STAINLESS STEEL HINGES AND ATTACHING HARDWARE
- NON-CORROSIVE PADLOCK BAR
- SINGLE LEAF CONSTRUCTION
- 300 LBS. PER SQ. FT. LOAD RATING (1464 KG. PER SQ. METER LOAD RATING)
- EXTRUDED ALUMINUM FRAME
- RECESSED LIFTING HANDLE
- LIFETIME GUARANTEE





www.HallidayProducts.com Phone 800-298-1027 Fax 407-298-4534 Sales@HallidayProducts.com

	STANDARD SIZES					
QTY.	MODEL NO.	A DIM. INCHES (MM)	C DIM. INCHES (MM)	UNIT WT. LBS. (KG.)		
	S1R2424	24 (610)	24 (610)	37 (17)		
	S1R2430	24 (610)	30 (762)	42 (19)		
	S1R2436	24 (610)	36 (914)	48 (22)		
	S1R2442	24 (610)	42 (1067)	55 (25)		
	S1R2448	24 (610)	48 (1219)	61 (28)		
	\$1R3030	30 (762)	30 (762)	49 (22)		
	S1R3036	30 (762)	36 (914)	57 (26)		
	S1R3042	30 (762)	42 (1067)	64 (29)		
<b>V</b>	\$1R3048	30 (762)	48 (1219)	71 (32)		
	S1R3054	30 (762)	54 (1372)	79 (36)		
	S1R3060	30 (762)	60 (1524)	87 (39)		
	S1R3636	36 (914)	36 (914)	65 (25)		
	S1R3642	36 (914)	42 (1067)	79 (36)		
	S1R3648	36 (914)	48 (1219)	85 (39)		
	S1R3654	36 (914)	54 (1372)	91 (41)		
	S1R3660	36 (914)	60 (1524)	100 (45)		
	S1R3666	36 (914)	66 (1676)	109 (49)		
	S1R3672	36 (914)	72 (1829)	116 (53)		
	S1R4242	42 (1067)	42 (1067)	93 (42)		

