

# SCOPE OF WORK

Commissioning Authority Services

Airport Traffic Control Tower (ATCT) and  
Administrative Base Building

Palm Springs International Airport

Palm Springs, California

March 15, 2012



U.S. Department of Transportation  
**Federal Aviation Administration**

**Federal Aviation Administration**

**“Expect Excellence”**

## TABLE OF CONTENTS

<b>1. INTRODUCTION</b>	<b>2</b>
<b>2. SCOPE</b>	<b>2</b>
<b>3. BACKGROUND INFORMATION AND GENERAL REQUIREMENTS</b>	<b>4</b>
<b>4. CONTACT INFORMATION</b>	<b>7</b>
<b>5. PROJECT SPECIFIC INFORMATION</b>	<b>7</b>

## 1. INTRODUCTION

The Federal Aviation Administration (FAA) awarded a construction contract in March 2010 to Swinerton Builders headquartered in San Francisco California. The project is over 90% complete.

The FAA has a requirement for a Commissioning Authority who will direct the commissioning process detailed in the attached project specification sections 15995.

## 2. SCOPE

The firms interested in this contract will be required to submit a proposal including the following information:

1. Company history with commissioning projects. The FAA is looking for a minimum of 10 years experience with similar projects.
2. Names and resumes of personnel ready to begin work on the Palm Springs ATCT construction site immediately after contract award. Estimated contract award is March 30, 2012.
3. List of any previous experience working with Swinerton Builders and/or the FAA including references.
4. Project Cost estimate

Items 1-3 will be used to evaluate technical acceptability. 10 years or more company experience will score 1 and less than 10 years will score 0. Qualified personnel available to start work immediately, with 5 years experience will score 1 pt with a maximum of 5 pts. No qualified personnel available immediately or less than 5 years experience will score 0. Previous experience with Swinerton and/or FAA including references will score 1 point per project with a maximum of 3 points. No experience with the FAA or Swinerton will score 0 points. Each firm scoring at least 1 point in each category will be deemed technically acceptable.

The contract will be awarded to the lowest priced technically acceptable vendor. If two technically acceptable firms have equal cost estimates, the technical score will determine the successful bid.

All personnel expected to work on the construction site must meet access requirements for the Airport Operations Area. Personnel must have a valid driver's license and must be escorted by FAA or Swinerton personnel authorized by the Palm Springs Airport Authority to provide escort services. Contract personnel are not permitted to drive on the airport operations area without an escort **and** an Airport Authority issued permit. The FAA will not compensate the contractor for any expenses incurred due to employees who do not meet access requirements or do not coordinate appropriate escort / vehicle permit requirements in advance of their arrival on site. Contractor employees acknowledge that parking within the Airport Operations Area may not be available and employees will need to find public parking on nearby streets. Employees will need to contact the COTR to arrange escort from the gate on Camino Bombero (between Signature Flight Services and the fire station) to the job site.

After contract award, the FAA Contracting Officer will issue a Notice-to-Proceed (NTP). Immediately upon receipt of the NTP, the selected firm shall contact the FAA COTR and coordinate a start date and time. Normal working hours will be established by the COTR and normal working days are Monday thru Friday. Night or weekend work may be required and the successful bidder will accommodate as required.

All work under this contract shall be performed in accordance with this SOW and technical input from the FAA. The successful bidder shall furnish sufficient skilled technical, supervisory, and administrative personnel to ensure the expeditious completion of the work specified herein.

Only the FAA Contracting Officer can make contract modifications. To facilitate the progress of this effort, coordination of change issues may be initiated with the COTR; however, all contract changes shall be issued by written modification from the FAA Contracting Officer.

The final deliverables under this contract are specified in the attached specification sections. Electronic deliverables shall include a pdf copy of the entire document as well as separate word/excel or other native copies of all files.

This SOW will require 10+ years experience and expertise. It is the government position that no work under this contract shall be subcontracted.

At the conclusion of the contract, all documents shall become the property of the FAA.

### 3. BACKGROUND INFORMATION AND GENERAL REQUIREMENTS

The Google Earth photos below show the nearby surface streets (El Cielo and Camino Bombero aka Airport Tower Road) and the close proximity to the airport taxiway. The second photo shows a closer view of the construction site and the existing Airport Traffic Control Tower (ATCT).





Project Commitment: It is assumed that the successful firm will devote the level of effort, skilled manpower, and other resources necessary to complete this work in compliance with the performance time of this contract.

Project Schedule: The firm shall develop a schedule based on the requirements in the attached specifications. The schedule shall assume contract award and NTP both occur April 2, 2012 and the schedule shall be submitted with the firm's proposal. The schedule shall be updated with the actual start date and any necessary revisions within one week after the contract NTP, and submitted to the FAA COTR.



Performance Time, Deliverables, and Submittals: The firm shall complete all aspects of the work outlined in this SOW within the defined performance time. All change orders, revisions, or modifications to this SOW must be approved by the FAA Contracting Officer and may result in an adjustment of the performance time; however, the firm will need to show the impacts to the project schedule, specifically the critical path, to justify additional time.



#### **4. CONTACT INFORMATION**

Daniel Dean (COTR)  
PSP ATCT Resident Engineer  
280 N El Cielo Rd.  
Palm Springs CA 92262  
(404) 539-7149

Scott Earl  
Engineering Services AJW-W11C  
Terminal Engineering Center, Los Angeles, CA  
15000 Aviation Blvd  
Hawthorne, California 90250  
(310) 725-6599

#### **5. PROJECT SPECIFIC INFORMATION**


**See Attached Drawings and Specifications**

## MECHANICAL SYMBOLS

[illegible]

## STANDARD ABBREVIATIONS

## REFERENCE



## FIRE RATED PARTITIONS



1 = HOUR  
 2 = HOUR  
 3 = HOUR  
 4 = HOUR

AC	ALTERNATING CURRENT	CONT	CONTINUOUS OR CONTINUOUS	FP	FIREPROOFING
A/C	AIR CONDITIONING	CONTR	CONTRACTOR	FT	FIRE TESTED
AD	AREA DRAIN	CSDR	CORRIDOR	FT	FIRE TRIM
ADJ	ADJUNCT OR ADJUSTABLE	CRAC	COMPUTER ROOM A/C CENTER	FIC	FIRE SILE CABINET
ADR	ACCESS DOOR	CSH	CABINET UNIT HEATER	<b>G</b>	GAGE
AF	ABOVE FIRST FLOOR	CLDR	CLIMATE CONTROL	GAU	GALVANIZED
AHF	AIR HANDLING UNIT	CHS	CHILLED WATER SUPPLY	GN	GENERATOR
AL	ALUMINUM	CHW	CHILLED WATER RETURN	GN	GALVANIZED
ALT	ALTERNATE	<b>D</b>		GM	GALLONS PER MIN.
APPROX	APPROXIMATELY	DF	DIFFUSER	GR	GRADE
ARCH	ARCHITECT[URE]	DIL	DRAIN DOUBLE	DWB	GYPSUM WALLBOARD
ASPH	ASPHALT	DSP	DEPRESSED	<b>H</b>	
AT	AIR TERMINAL, BOX	DET	DETAIL	HB	HOSE BIBB
ATD	AIR TRANSFER DUCT	DF	DRIVING FLOWING	H	HEATING COIL
ATU	AIR TERMINAL, UNIT	DA	DIAMETER	HOP	HANGING (PYS)
AUX	AUXILIARY	DI	DOWN, IRON PIPE	HORZ	HORIZONTAL
AZ	AZIMUTH	DN	DOWN	HP	HIGH POWER
<b>B</b>		DS	DOWNSPOUT	HPT	HIGH POINT
BE	BOTTOM ELEVATION	DW	DRAINING	HR	HOUR
BL	BUILDING LINE	DWP	DOMESTIC WATER PUMP	HS	HIGH STRENGTH
BLDG	BUILDING	<b>E</b>		HT	HEIGHT
BTU	BRITISH THERMAL UNIT	EA	EACH	HTG	HEATING
<b>C</b>		ED	EXHAUST FAN	HTR	HEATER
CB	CEMENT PIPE	EL	ELEVATION	HAC	HEATING/VENTILATION
CP	CABINET	ELEC	ELECTRIC (AL)		CONDITIONING
CR	CATCH BREAKER OR CATCH BASIN	ELEV	ELEVATOR	HZ	HERTZ
CC	COOLING COIL	EQ	EQUAL	HW	DOMESTIC HOT WATER
C/C	CENTER TO CENTER	EQUIP	EQUIPMENT	HMS	HEATING HOT WATER
CD	CONDENSING UNIT	EW	ELECTRIC WATER COOLER	HNS	HEATING HOT WATER
CE	CENTER ELEVATION	EW	ELECTRIC WATER HEATER		COOLING HOT WATER
CEM	CEMENT	EXH	EXHAUST	<b>I</b>	
CFM	CUBIC FEET PER MINUTE	EXIST	EXISTING	I	INCH
CFS	CUBIC FEET PER SECOND	EXP	EXPOSED	IE	INCHES DIAMETER
CH	CHILLER	EXT	EXTERIOR	IF	INCHES FACE
CP	CONTROL PUMP	<b>F</b>		IN	INCH
CU	CULVERT, JOINT	FA	FIRE ALARM	IN	INCH
CL	CENTER LINE	FCU	FAN COIL UNIT	INGA	INCHES
CLD	CEILING	FD	FLOOR DRAIN OR FIRE DAMPER	INT	INTERIOR
CLR	CLEAR	FE	FIRE EXTINGUISHER	<b>J</b>	
CMP	CORRUGATED METAL PIPE	FEC	FIRE EXTINGUISHER CABINET	JAN	JANITOR
CO	COOLANT	FIC	FIRE HYDRANT	JN	JUNCTION BOX
COL	COLUMN	FIC	FIRE HOSE CABINET	JST	JOIST
COMB	COMBINATION OR COMBINE	FIN	FINISH	JT	JOINT
CONC	CONCRETE	FL	FUTURE	<b>K</b>	
CONN	CONNECTION	FL	FLOOR	K	KITCHEN
CONST	CONSTRUCTION	FM	FIRE MAIN		

**L**  
LAW LAUNDRY  
LBS POUNDS  
LF LINEAR FEET  
LN LINEAR  
LVL LEVEL

**M**  
MAINT MAINTENANCE  
MAT MATERIAL  
MBB MASONRY  
MECH MECHANICAL  
MFR METAL  
MFG MANUFACTURE  
MG MOTOR GENERATOR  
MI MANHOLE  
MIN MINIMUM  
MTC MOUNTING OR MOUNTED

**N**  
NAC NATIONAL ELECTRICAL CODE  
NO NUMBER  
NOM NOMINAL  
NIC NOT IN CONTACT  
NTS NOT TO SCALE

**O**  
OA OUTSIDE AIR  
OC ON CENTER  
OD OUTSIDE DIAMETER  
OF OUTSIDE FACE  
OPMG OPENING

**OPP** OPPOSITE  
O/S OFFSET  
OD OUNCE

**P**  
P PUMP  
PART PART  
PMT PAYMENT  
PCF POUNDS PER CUBIC FOOT  
PDRP PERFORATED  
PF PREHEAT COIL  
PHAC PLUMBING, HEATING, VENTILATING AND AIR CONDITIONING  
PI POINT OF INTERSECTION  
PIV PRESS INDOOR VALVE  
FWS PAINTING  
PL PROPERTY LINE OR PLATE

FLAS FLASK  
FLUG PLUMBING  
FUG FOUNCES FOR LINEAR FLOT  
FNL PANEL  
FR FAN  
FRUG PROTECTION  
FRV PRESSURE REGULATING VALVE  
FSF POUNDS PER SQUARE FOOT  
FSO POUNDS PER SQUARE INCH  
FT POINT OF TANGENCY  
FVC POINT OF VERTICAL CURVATURE  
FVC POLYVINYL CHLORIDE  
FV POINT OF VERTICAL INTERSECTION  
PV POINT OF VERTICAL TANGENCY

**R**

R RADIUS  
REG REGISTER  
RA RETURN AIR  
RCP REINFORCED CONCRETE PIPE  
RD ROP DRAWN  
REF REFERENCE  
REFL REFLECTED  
REFN REFLECTING  
REQD REQUIRED  
REV REVERSE  
RF RETURN FAN  
RGS ROD GALVANIZED STEEL  
RH RISK ROOM  
RHC REHEAT COIL  
RM ROOM

**S**

S SANITARY SEWER  
SA SUPPLY AIR OR SOUND ATTENUATION  
SAN SANITARY  
SCH SCHEDULE  
SC SECTION  
SCF SCUM FLOT  
SHT SHEET  
SM SMLAB  
SK SINK  
SLP SLUMP PUMP  
SPEC SPECIFICATIONS  
SQ SQUARE  
SS STORM SEWER  
SSO STORM SEWER OVERFLOW  
SSTL STAINLESS STEEL  
STA STATION

STE STANDARD TAPERED END  
STF STIFFENER  
STR STRIP  
STL STEEL  
STOR STORAGE  
STR STRUCTURAL  
SUP SUSPENDED  
SW SWITCH  
SWCR SWITCHGEAR  
SYM SYMMETRICAL

**T**

T&B TOP AND BOTTOM  
TE TOP EDGE  
TEMP TEMPERATURE  
TOL TOLU  
TOPO TOPOGRAPHY  
TOS TOP OF STEEL  
TOW TOP OF WALL  
TP TOP OF FRAGMENT  
TRANS TRANSVERSE  
TYP TYPICAL

**U**

UG UNDERGROUND  
UH UNIT HEATER  
UV UNIT VENTILATOR  
UR URINAL

**V**

V VOLT  
VC VITRIFIED CLAY PIPE  
VERT VERTICAL  
VEST VESTIBULE  
VTD VARIABLE FREQUENCY DRIVE  
VTR VENT THROUGH ROOF


**W**


W WATT  
W/ WITH  
WC WATER CLOSET OR WALL COVERING  
WH WATER HEATER  
W/O WITHOUT  
WP WEATH-EXPROOF  
WRF WATERPROOF  
WS WATER STOP  
WT WEIGHT  
WWF WELDED WIRE FABRIC

**Y**


YD YARD  
YH YARD HYDRANT

[illegible]










SECTION  
M103 SCALE: 1/4" = 1'-0"

Room Schedule	
Room Number	Room Name
<b>LEVEL 5</b>	
502	SERVICE STAIR
503	EXIT STAIR
504	CABLE CHASE
505	PIPE CHASE
<b>LEVEL 5+</b>	
501+	ELEVATOR LOBBY
502+	SERVICE STAIR
503+	EXIT STAIR
<b>LEVEL 6</b>	
601	SPF ROOM
602	SERVICE STAIR
603	EXIT STAIR
604	CABLE CHASE
605	PIPE CHASE
<b>LEVEL 6+</b>	
602+	SERVICE STAIR
603+	EXIT STAIR

[illegible]



**LEO DAILY**  
PLANNING  
ARCHITECTURE  
ENGINEERING  
1000  
1000

8600 Indian Hills Drive  
Omaha, NE 68114-4039  
Tel 402.391.8111  
Fax 402.391.8564

1400 N. 300 1000-000

**DEPARTMENT OF TRANSPORTATION  
FEDERAL AVIATION ADMINISTRATION  
WESTERN SERVICE AREA LOS ANGELES, CA**

**REPLACE AIRPORT TRAFFIC CONTROL TOWER AND  
ESTABLISH BASE BUILDING**


**TOWER LEVELS 7 AND 8  
HVAC PLANS**

PALM SPRINGS PALM SPRINGS INTERNATIONAL AIRPORT (PSP) CALIFORNIA

REVIEWED BY: [Signature] SUBMITTED BY: [Signature] APPROVED BY: [Signature]

DESIGNED: CDR DATE: October 5, 2009  
DRAWN: PEH  
CHECKED: MPH

APPROVED'S TITLE: [Signature]  
DATE: October 5, 2009  
JCN  
DRAWING NO: PSP-D-ATCT- M104







1. ALL DUCTWORK SHALL HAVE 1" ACOUSTICAL DUCT LINER UNLESS NOTED OTHERWISE. DUCT DIMENSIONS ARE CLEAR INSIDE DIMENSIONS.


4' 0 4'


SCALE: 1/8"=1'-0"



The diagram illustrates a vertical air filtration system. At the top, a circular inlet labeled "1" leads down through a series of horizontal pleated filters labeled "H-2". Below the filters is a rectangular box containing three triangular mesh screens. A label points to this section: "96\"x60\" DUCT FROM H-2 TO FILTER BOX". Below the screen box are two larger rectangular filter units. A label points to them: "96\"x60\"x24\" FILTER BOX, W/ FULL AREA FILTERS ON BOTTOM AND 24\" TALL FILTERS ALL AROUND SIDES". To the right, a small rectangular component labeled "FID-1" is shown with a dimension of "3/4\" CWG/2\". Arrows indicate the downward flow of air from the inlet, through the filters, and out from the bottom of the filter box.

SECTION  
SCALE: 1/4" = 1'-0"

LEO A DAILY									
PLANNING ANALYST/DESIGNER INVESTIGATOR									
DATE REV									
REV	DATE	DESCRIPTION	JOIN	ISSUE DATE	APPROV				
<p align="center"><b>DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION</b></p> <p><b>WESTERN SERVICE AREA</b> <span style="float:right"><b>LOS ANGELES, CA</b></span></p> <p align="center"><b>REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING</b></p> <p align="center"><b>GROUND LEVEL HVAC PLAN</b></p>									
<p>8600 Mills Hill Drive Orem, UT 84057-1400 Tel 402-391-8111 Fax 402-391-8564</p> <p>LEAD NO: 202 1096-208</p>									
									
PALM SPRINGS		PALM SPRINGS INTERNATIONAL AIRPORT (PSP)			CALIFORNIA				
REVIEWED BY	SUBMITTED BY	APPROVED BY							
	<i>[Signature]</i>	<i>[Signature]</i>							
SUBMITTEE'S TITLE		APPROVER'S TITLE							
DESIGNED: CDR		ISSUED BY: ENGINEERING SERVICES			DATE: October 5, 2009		JOIN		
DRAWN: PEH		TERRAINING: - LOS ANGELES			DRAWING NO:				
CHECKED: MPH					PSP-D-ATCT- M111		REV		




Room Schedule	
Room Number	Room Name
GROUND LEVEL	
1	VESTIBULE
2	RECEPTION AREA
3	CORRIDOR A
4	CORRIDOR B
5	VESTIBULE B
6	CORRIDOR C
7	VESTIBULE C
11	SSC ADMIN COORD
12	SSC MANAGER
21	OPEN AREA/ADMIN ASSIST
22	AT MANAGER
23	OPS SUP
24	TAPE PLAYBACK
31	COPY/PRINTER
32	JANITOR
33	JOH
34	CONFERENCE
35	BREAK ROOM
36	FOOD PREP AREA
41	COPY/ADMIN STOR
51	LOCKER ROOM
52	WOMEN
53	SHOWER
54	MEN
55	SHOWER
61	TECH OPS WORK AREA
62	ENVIRONMENTAL SHOP
63	TECH STORAGE
64	WORKSPACE
71	MECHANICAL
72	EQUIPMENT
73	TECH LIBRARY
74	E SWITCH GEAR ROOM
75	SWITCH GEAR ROOM
76	WFO ROOM
91	TOWER VESTIBULE
92	EXIT PASSAGEWAY
93	PUMP ROOM

<b>LEO A DAILY</b> PLANNING ARCHITECTURE INTERIORS 2600 Indian Hills Drive Omaha, NE 68114-4039 Tel 402-391-8111 Fax 402-391-8564 CAD 101 100 1000 1000		DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION WESTERN SERVICE AREA LOS ANGELES, CA REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING <b>GROUND LEVEL          HVAC PIPING PLAN</b>	
SUBMITTED BY DESIGNED CDR DRAWN PEH CHECKED MPH	REVIEWED BY DATE OCT 5 2009	APPROVED BY DATE OCT 5 2009	PSM 21106 PSM-D-ATCT- M211



SCALE: NONE


LEO A DAILY							
TELEPHONE							
FAX NUMBER							
ADDRESS							
CITY							
STATE							
ZIP							
REV	DATE	DESCRIPTION	JCN	ISSUE	DATE	APPROVED	
<p align="center"><b>DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION</b></p> <p><b>WESTERN SERVICE AREA</b> <span style="float: right;"><b>LOS ANGELES, CA</b></span></p> <p align="center"><b>REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING</b></p> <p align="center"><b>CHILLED WATER SCHEMATIC DIAGRAM</b></p>							
<p>8600 Indian Hills Drive Oxnard, NE 681 14-0079 Tel 402-391-8111 Fax 402-391-8364</p>							
<p>LAO NCR 300 10096-208</p>							
		<p><b>PALM SPRINGS</b> <span style="float: right;"><b>PALM SPRINGS INTERNATIONAL AIRPORT (PSP)</b></span></p> <p>REVIEWED BY <i>[Signature]</i> <span style="float: right;">APPROVED BY <i>[Signature]</i></span></p> <p>SUBMITTER'S TITLE <i>[Signature]</i> <span style="float: right;">APPROVED'S TITLE <i>[Signature]</i></span></p> <p>DESIGNED <i>[Signature]</i> <span style="float: right;">DATE October 8, 2009</span> <span style="float: right;">JCN</span></p> <p>DRAWN <i>[Signature]</i> <span style="float: right;">ISSUED BY</span> <span style="float: right;">ENGINEERING SERVICES</span></p> <p>CHECKED <i>[Signature]</i> <span style="float: right;">TOWNAL - LOS ANGELES</span> <span style="float: right;">DRAWING NO.</span></p> <p>MEPH <span style="float: right;">PSP-D-ATCT- M301</span></p>					







- 

[illegible]


											
6620 Indian Hills Drive Oranthe, NE 68114-4039 Tel 402-391-8111 Fax 402-391-8564		REV		DATE		DESCRIPTION		JCN		RESUME DATE	
		DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION WESTERN SERVICE AREA									
		LOS ANGELES, CA REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING									
		DETAILS									
LAD 102- 200 1006-208		PALM SPRINGS INTERNATIONAL AIRPORT (PSP) CALIFORNIA									
		PALM SPRINGS REVIEWED BY		SUBMITTED BY 		APPROVED BY 					
		SUBMITTER'S TITLE		DESIGNED: CNR		ISSUED BY ENGINEERING SERVICES		APPROXIMATE DATE October 5, 2009		JCN	
		DRAWN: MEH		CHECKED: MEH		DOWNING NO.		P5D-A-ATCT- M401		REV	




1 AIR TRANSFER DUCT  
M402 SCALE: NONE




2 RETURN GRILLE  
M402 SCALE: NONE




3 DIFFUSER CONNECTION  
M402 SCALE: NONE




4 EXTERIOR PIPE TRENCH SUPPORT DETAIL  
M402 SCALE: NONE




5 VAV BOX DETAIL  
M402 SCALE: NONE




6 AIR ELIMINATOR  
M402 SCALE: NONE




7 ELECTRIC STEAM HUMIDIFIER  
M402 SCALE: NONE



8 FIRE/SMOKE DAMPER AT RATED WALLS  
M402 SCALE: NONE




9 FIRE DAMPER DETAIL  
M402 SCALE: NONE




10 LOUVER DETAIL  
M402 SCALE: NONE

<b>LEO DAILY</b> <small>ILLUSTRATION ARCHITECTURAL INTERIOR MECHANICAL ELECTRICAL PLUMBING PAINTING GENERAL</small> 8402 Indian Mills Drive Omaha, NE 68114-4039 Tel 402-391-8111 Fax 402-391-8564 LEO DAILY 100 YEARS OF SERVICE No. 1033005 REG. 6-30-71 MECHANICAL STATE OF CALIFORNIA		<table border="1"> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> <th>JOH</th> <th>REL</th> <th>DATE</th> <th>APV</th> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </table>		REV	DATE	DESCRIPTION	JOH	REL	DATE	APV							
REV	DATE	DESCRIPTION	JOH	REL	DATE	APV											
DEPARTMENT OF TRANSPORTATION <b>FEDERAL AVIATION ADMINISTRATION</b> WESTERN SERVICE AREA LOS ANGELES, CA REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING <b>DETAILS</b>		PALM SPRINGS PALM SPRINGS INTERNATIONAL AIRPORT (PSP) CALIFORNIA REVIEWED BY: <i>[Signature]</i> SUBMITTER'S TITLE: <i>[Signature]</i> DESIGNED: CDR DRAWN: PEH CHECKED: MPH ISSUED BY: ENGINEERING SERVICES TERMINAL - LOS ANGELES DATE: October 5, 2008 APPROVED BY: <i>[Signature]</i> APPROVER'S TITLE: <i>[Signature]</i> PSP-D-ATCT- M402															












1 TRANSVERSE CABLE BRACE FOR DUCTWORK  
SCALE: NONE




2 TRANSVERSE & LONGITUDINAL CABLE BRACE FOR DUCTWORK  
SCALE: NONE



3 TRANSVERSE SINGLE ARM BRACE FOR DUCTWORK  
SCALE: NONE




4 SINGLE ARM BRACE FOR DUCTWORK TRANSVERSE & LONGITUDINAL  
SCALE: NONE




NOTE: FOR ATTACHMENT OF CABLES, SEE INSTALLATION DETAIL DRAWING ENTITLED "TYPICAL CABLE ATTACHMENT TO STRUCTURE".

5 TYPICAL INSTALLATION OF INLINE PUMP  
SCALE: NONE




6 ROOF INTAKE HOOD CURB DETAIL  
SCALE: NONE

<b>LEO A DAILY</b> 8400 Indian Hills Drive Omaha, NE 68114-4039 Tel 402-391-8111 Fax 402-391-6564		REV DATE DESCRIPTION JOB REVISIONS APPROVED	
LEO NO. 001 1004 000		DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION WESTERN SERVICE AREA LOS ANGELES, CA REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING <b>DETAILS</b>	
PALM SPRINGS PALM SPRINGS INTERNATIONAL AIRPORT (PSP) CALIFORNIA		SUBMITTED BY [Signature] APPROVED BY [Signature]	
DESIGNED CDR	ISSUED BY	DATE October 5, 2009	LCN
DRAWN PEH	ENGINEERING SERVICES	DRAWING NO	
CHECKED MPH	TERMINAL - LOS ANGELES	PSP-D-ATCT- M404	REV




<b>LEO DAILY</b> PUBLISHED EVERY DAY EXCEPT SUNDAY 800 391-8111		REV DATE DESCRIPTION JOB REVISIONS APPROVED	
8620 Indian Hills Drive Omaha, NE 68114-4039 Tel 402-391-8111 Fax 402-391-8164		DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION WESTERN SERVICE AREA LOS ANGELES, CA REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING <b>DETAILS</b>	
LAD NO. 001 1006-000		PALM SPRINGS PALM SPRINGS INTERNATIONAL AIRPORT (PSP) CALIFORNIA	
SUBMITTED BY DESIGNED CDR DRAWN PEH CHECKED MPH	REVIEWED BY APPROVED BY DATE October 5, 2008 DRAWING NO. PSP-D-ATCT- M405	APPROVED BY DATE DRAWING NO.	









1 AHU-1, RF-1, ERU-1, H-1 CONTROL DIAGRAM  
M501 SCALE NONE

SYSTEM, APPARATUS, OR AREA DESCRIPTION	INPUTS				OUTPUTS				ALARMS	NOTES
	ANALOG	BINARY	BINARY	ANALOG	ANALOG	BINARY	ANALOG	ANALOG		
SUPPLY FAN										
VAR. FREQ. DRIVE (SUPPLY FAN)										1
SUPPLY AIR										
RETURN AIR										
MIXED AIR										
STATIC PRESSURE (REMOTE IN DUCT)										
STATIC PRESSURE (AT UNIT IN DUCT)										
STATIC PRESSURE (RETURN AIR DUCT)										
COOLING COIL CONTROL VALVE										
HEATING COIL										
FILTERS (EACH)										
RELIEF AIR DAMPER										
RETURN AIR DAMPER										
OUTSIDE AIR DAMPER (ECONOMIZER)										
OUTSIDE AIR DAMPER (MINIMUM)										
EXHAUST AIR DAMPER										
SMOKE DETECTOR										
OUTSIDE AIR										
RETURN FAN										
VAR. FREQ. DRIVE (RETURN FAN)										1
HUMIDIFIER (H-1)										
HUMIDIFIER HIGH LIMIT										
STATIC PRESSURE (BUILDING)										
EXHAUST AIR (UPSTREAM OF ERU-1)										
EXHAUST AIR (DOWNSTREAM OF ERU-1)										
CONDITIONED OUTSIDE AIR										
ENERGY RECOVERY UNIT										
ENERGY GENERATOR										

NOTES:  
1 SEE VFD SPECIFICATION FOR ADDITIONAL POINTS TO MONITOR & CONTROL BY BMCS.

#### SEQUENCE OF OPERATION

- GENERAL: UNIT IS A VARIABLE AIR VOLUME (VAV) AIR HANDLING UNIT (AHU) SUPPORTED BY A STATIC PLATE PACK ENERGY RECOVERY UNIT (ERU-1) PROVIDING COOLING, HEATING & VENTILATION FOR AREAS SHOWN ON THE DRAWINGS.
- OPERATION: UPON A CALL FROM THE BMCS TO OPERATE THE RETURN AIR DAMPER SHALL OPEN, THE MINIMUM OUTSIDE AIR DAMPER SHALL OPEN, AND THE EXHAUST AIR DAMPER SHALL OPEN. THE ERU-1 EXHAUST AND OUTSIDE AIR FANS SHALL START AND AHU-1 SUPPLY AND RETURN FANS SHALL START AND RUN CONTINUOUSLY. THE ERU-1 EXHAUST FAN SHALL RUN CONTINUOUSLY DURING OCCUPIED PERIODS. THE ERU-1 OUTSIDE AIR FAN SHALL ALSO OPERATE DURING OCCUPIED PERIODS, EXCEPT DURING PERIODS WHEN AHU-1 IS IN ECONOMIZER MODE AND THE ELECTRIC HEATING COIL IS NOT OPERATING. DURING THESE PERIODS OF "FREE COOLING" THE ERU-1 OUTSIDE AIR FAN SHALL NOT OPERATE AND THE MINIMUM OUTSIDE AIR DAMPER SHALL BE CLOSED. ALARM BMCS OPERATOR IF FANS DO NOT "PROVE" START OR STOPS AFTER CALLED TO OPERATE. ALARM SHALL BE THROUGH CURRENT SENSING RELAY.
- SUPPLY FAN SPEED CONTROL: THE AHU SUPPLY FAN SHALL BE EQUIPPED WITH A VARIABLE FREQUENCY DRIVE WHICH WILL RESPOND TO MAINTAIN THE REMOTE SUPPLY AIR DUCT STATIC PRESSURE SETPOINT OF 1 INCH W.G. (A.G.). REMOTE DUCT STATIC PRESSURE SHALL BE MONITORED BY THE BMCS AND SHALL SIGNAL AN ALARM TO THE BMCS SHOULD PRESSURE RISE ABOVE OR FALL BELOW PREDETERMINED SETPOINTS (A.G.).
- RETURN FAN SPEED CONTROL: THE RETURN FAN SHALL BE EQUIPPED WITH A VARIABLE FREQUENCY DRIVE WHICH WILL RESPOND TO MAINTAIN A NEGATIVE PRESSURE OF 0.25 IN. W.G. (A.G.) DOWNSTREAM OF THE RETURN AIR DAMPER. ALARM BMCS SHOULD PRESSURE RISE ABOVE OR FALL BELOW PREDETERMINED SETPOINTS (A.G.).
- TEMPERATURE CONTROL:
  - ECONOMIZER/HEATING: WHEN THE OUTSIDE AIR TEMPERATURE IS BELOW THE RETURN AIR TEMPERATURE BY A MINIMUM OF 5°F (A.G.), THE RELIEF AIR AND THE ECONOMIZER OUTSIDE AIR DAMPER SHALL MODULATE OPEN IN CONJUNCTION WITH THE RETURN AIR DAMPER MODULATING CLOSED TO PROVIDE THE LOWEST POSSIBLE MIXED AIR TEMPERATURE DOWN TO A MINIMUM OF 55 DEGREES F (A.G.). IF MIXED AIR TEMPERATURE FALLS BELOW 50 DEGREES F SETPOINT AND THE RETURN AIR DAMPER IS FULLY OPEN, THE BMCS SHALL STAGE THE ELECTRIC HEATING COIL TO MAINTAIN 55.00 (A.G.) LEAVING AIR TEMPERATURE.
  - COOLING: WHEN THE ECONOMIZER OPERATION CANNOT MAINTAIN A SUPPLY AIR TEMPERATURE OF 55 DEGREES F (A.G.) THE BMCS SHALL MODULATE COOLING COIL CONTROL VALVE OPEN TO THE COIL TO MAINTAIN SUPPLY AIR SETPOINT. IF SUPPLY AIR TEMPERATURE RISES MORE THAN 3 DEGREES F (A.G.) ABOVE SETPOINT FOR 5 MINUTES (A.G.) SIGNAL ALARM TO OPERATOR.
- SUPPLY AIR TEMPERATURE RESET: WHEN ALL VAV BOXES ARE CALLING FOR HEAT AND ALL (A.G.) ARE IN MINIMUM SA POSITION, THE SUPPLY AIR TEMPERATURE OF AHU-1 SHALL BE RAISED IN 2°F (A.G.) INCREMENTS UNTIL ONE VAV BOX RESETS TO AN "ABOVE MINIMUM" POSITION FOR (3) MINUTES (A.G.). RESET "INCREMENTS" SHALL BE NO SOONER THAN 5 MINUTES (A.G.) BEFORE THE NEXT 2 DEGREE INCREMENT IS INITIATED. SUPPLY AIR TEMPERATURE SHALL BE RESET "UP" UNTIL TWO (A.G.) VAV BOXES ARE AT MAXIMUM COOLING SETTING FOR 5 MINUTES (A.G.) AFTER WHICH SA SHALL RESET "DOWN" IN TWO DEGREE F (A.G.) INCREMENTS UNTIL SA TEMPERATURE REACHES 50 DEGREE F (A.G.).
- HUMIDIFICATION: RETURN AIR HUMIDITY SENSOR SHALL MONITOR RELATIVE HUMIDITY (RH) IF RH IS BELOW 30% (A.G.), BMCS SHALL ENABLE HUMIDIFIER AND THE HUMIDIFIER PACKAGED CONTROLS SHALL MODULATE TO MAINTAIN RETURN AIR RH SETPOINT. IF THE HIGH LIMIT SENSOR DETECTS DRY AIR ABOVE 80% RH (A.G.), BMCS SHALL DISABLE HUMIDIFIER & SHALL ALARM BMCS OPERATOR.
- BUILDING PRESSURIZATION: THE RELIEF AIR DAMPER SHALL MODULATE TO MAINTAIN THE BUILDING POSITIVE STATIC PRESSURE BETWEEN 0.03 IN. W.G. TO 0.10 IN. W.G. (A.G.).
- FILTER STATUS: DIFFERENTIAL PRESSURE SWITCH SHALL ALARM THE BMCS TO SIGNAL FILTER MAINTENANCE SHOULD THE DIFFERENTIAL PRESSURE ACROSS THE FILTER BANK(S) RISE ABOVE PREDETERMINED SETPOINTS. SETPOINT FOR FILTER ALARM SHALL BE DETERMINED DURING BALANCING BY SIMULATING A DIRTY FILTER USING CARIBGARD OR OTHER DEVICE TO BLOCK AIR HANDLING UNIT FILTER SECTION FREE AREA BY 30%.
- FAN SHUTDOWN STATIC PRESSURE: AT UNIT DUCT STATIC PRESSURE SHALL BE MONITORED BY THE BMCS AND SHALL SIGNAL AN ALARM TO THE BMCS SHOULD PRESSURE RISE ABOVE PREDETERMINED SETPOINT OF 3.0 INCHES W.G. (A.G.). UPON ALARM, BMCS SHALL SHUTDOWN SUPPLY & RETURN FAN.
- SMOKE SHUTDOWN/FIRE ALARM: WHEN SMOKE DETECTOR ALARMS OR UPON A SIGNAL FROM THE FIRE ALARM SYSTEM, BMCS SHALL BE NOTIFIED & FIRE ALARM SHALL SHUTDOWN THE SUPPLY FAN, RETURN FAN, AND ERU-1 FANS.
- ENERGY RECOVERY: BMCS SHALL CALCULATE THE AMOUNT OF ENERGY RECOVERED BY ERU-1 THROUGH THE FOLLOWING FORMULA:  

$$BTUH \text{ RECOVERED} = (\text{ABSOLUTE VALUE}) \text{ CONDITIONED OUTSIDE AIR CFM} \times 1.08 \times (\text{OUTSIDE AIR TEMP } (T_1) - \text{CONDITIONED OUTSIDE AIR TEMP } (T_2))$$
- EMERGENCY GENERATOR OPERATION: IF THE EMERGENCY GENERATOR IS OPERATING, THEN THE ELECTRIC HEATING COIL AND THE HUMIDIFIER WILL BE LOCKED OUT.

SYSTEM, APPARATUS, OR AREA DESCRIPTION	INPUTS				OUTPUTS				ALARMS	NOTES
	ANALOG	BINARY	BINARY	ANALOG	ANALOG	BINARY	ANALOG	ANALOG		
SP-1 SERVING ELEVATOR PIT										2
DWSP-1										3
SPF-1										3
FUEL TANK MONITORING AND DETECTION										1
DWCP-1										4

#### NOTES:

- AN ALARM ISSUED BY THE FUEL MONITORING AND LEAK DETECTION SYSTEM SHALL ALSO BE SENT TO THE BMCS SYSTEM.
- BMCS TO MONITOR SP-1 CONTROL PANEL, HIGH WATER ALARM & SHALL ALARM OPERATOR UPON HIGH WATER CONDITION.
- BMCS SHALL MONITOR DWSP-1 CONTROL PANEL & SHALL SIGNAL ALARM TO OPERATOR FROM GENERAL DWSP-1 ALARMS.
- THE DOMESTIC HOT WATER CIRCULATING PUMP SHALL OPERATE DURING OCCUPIED PERIODS.
- BMCS TO MONITOR SPF-1 STATUS & SHALL ALARM OPERATOR WHEN SPF-1 IS CALLED TO OPERATE.

#### 2 MISCELLANEOUS BMCS POINT SCHEDULE

M-501 SCALE NONE

#### SYMBOL LEGEND


(APPLIES TO ALL CONTROL DIAGRAM SHEETS)

- ADJUSTABLE SETPOINT
- GRAVITY BACKDRIFT DAMPER
- SMOKE DETECTOR (FURNISHED BY ELECTRICAL)
- FAN
- AIR VALVE
- MOTOR STARTER
- MODULATING CONTROL VALVE (TWO WAY)
- MODULATING CONTROL VALVE (THREE WAY)
- WALL MOUNTED SENSOR
- DUCT MOUNTED SENSOR
- DAMPER END SWITCH
- INPUT TO BMCS (DIGITAL/ANALOG)
- OUTPUT FROM BMCS (DIGITAL/ANALOG)
- (N.C.) NORMALLY CLOSED (POSITION UPON LOSS OF POWER)
- (N.O.) NORMALLY OPEN (POSITION UPON LOSS OF POWER)
- DPS DIFFERENTIAL PRESSURE SWITCH
- T THERMOSTAT
- PS PRESSURE SENSOR
- TS TEMPERATURE SENSOR
- HL HIGH LIMIT
- HS HUMIDITY SENSOR
- RH RELATIVE HUMIDITY
- AV AIR VALVE
- ES END SWITCH
- CC- COOLING COIL
- EC- ELECTRIC HEATING COIL
- EDH- ELECTRIC DUCT HEATER
- PUMP
- VS VARIABLE FREQUENCY DRIVE CONTROLLER
- M/MOTORIZED DAMPER
- FD/SD COMBINATION FIRE/SMOKE DAMPER
- SD SMOKE DAMPER
- AMS AIR FLOW MEASURING STATION
- FAR FIRE ALARM RELAY (BY ELECTRICAL)
- CI INPUT TO/OUTPUT FROM FIRE ALARM CONTROL PANEL
- POWER WIRING (BY ELECTRICAL)
- CS CURRENT SENSOR
- FM FLOW METER
- TS SENSOR IN THERMOWELL
- EC ELECTRIC HEATING COIL CONTROLLER

<b>LEO DAILY</b> 8600 Indian Hills Drive Chula Vista, CA 92014-4039 Tel 619-591-8111 Fax 619-591-8564		REV DATE DESCRIPTION JCN RELN SAE AND	
DEPARTMENT OF TRANSPORTATION <b>FEDERAL AVIATION ADMINISTRATION</b> WESTERN SERVICE AREA LOS ANGELES, CA REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING		CONTROL DIAGRAMS	
PALM SPRINGS INTERNATIONAL AIRPORT (PSP) CALIFORNIA		SUBMITTER'S TITLE: DESIGNED GNR CHECKED MPH	
ISSUED BY: ENGINEERING SERVICES TERMINAL - LOS ANGELES		APPROVED BY: [Signature] DATE: October 5, 2008 JCN DRAWING NO: PSP-D-AI/CT-M501	








1 SPF-1 CONTROL DIAGRAM  
M503 SCALE: NONE

SEQUENCE OF OPERATION

- GENERAL: STARWELL PRESSURIZATION FAN PROVIDES STAR PRESSURIZATION FOR THE TOWER STAR AS SHOWN ON THE DRAWINGS. SYSTEM SHALL NOT BE CONNECTED TO THE BMCS. THE SYSTEM IS DESIGNED TO MAINTAIN POSITIVE STAR PRESSURIZATION WITH ONE DOOR BEING OPEN TO THE STAR. 2000 CFM ADDITIONAL IS PROVIDED TO COMPENSATE FOR AN OPEN DOOR.
- OPERATION: THE SYSTEM SHALL ACTIVATE AUTOMATICALLY THROUGH THE FIRE ALARM SYSTEM UPON A SIGNAL FROM THE FIRE ALARM SYSTEM (SEE FIRE ALARM MATRIX). THE OUTSIDE AIR DAMPER AND RELIEF AIR DAMPER SHALL FULLY OPEN AND THE STAR PRESSURIZATION FAN SHALL START AND RUN CONTINUOUSLY.




2 EQUIPMENT ROOM CONTROL DIAGRAM (CRAC-1,2,3)  
M503 SCALE: NONE

BMCS POINT SCHEDULE																		
SYSTEM APPARATUS, OR AREA DESCRIPTION	INPUTS					OUTPUTS				ALARMS		NOTES						
	ANALOG	BINARY			BINARY	ANALOG												
	TEMPERATURE	PRESSURE	STATUS ON / OFF	STATUS OPEN / CLOSED	EMERGENCY GENERATOR	OPEN / CLOSE	ENABLE / DISABLE	START / STOP	VALVE POSITION	SECT. POINT ADJUSTMENT	REGULATION		HI ANALOG	LO ANALOG	HI BINARY	LOW BINARY	REMOTE ALARM	SENSOR FAIL
SPACE	●	●								●		●						
PACKAGED UNIT CONTROLLER			●	●														
PACK. DUTY/STANDBY CONTROLLER						●	●											
WATER DETECTION															●	●		

SEQUENCE OF OPERATION


- GENERAL: UNITS PROVIDE HEATING, COOLING & HUMIDITY CONTROL FOR THE AREAS AS SHOWN ON THE DRAWINGS. TWO UNITS SHALL OPERATE AS LEAD UNIT & ONE UNIT SHALL OPERATE AS STANDBY (LAG). PACKAGED DUTY/STANDBY CONTROLLER SHALL ALTERNATE UNITS EVERY 7 DAYS TO PROVIDE EQUAL RUN TIME. THE CHILLED WATER SENSING VALVE ON THE STANDBY UNIT SHALL REMAIN CLOSED.
- OPERATION: BMCS SHALL ENABLE THE PACKAGED DUTY/STANDBY CONTROLLER WHICH SHALL OPEN SUPPLY AIR DAMPER AND THEN START & RUN THE LEAD UNIT(S). CONTINUOUSLY, CONTROL OF THE UNIT SHALL BE THROUGH THE PACKAGED UNIT MOUNTED CONTROLLER (SEE SPECIFICATIONS). DUTY/STANDBY CONTROLLER SHALL START & RUN LAG UNIT IF LEAD UNIT(S) CANNOT MAINTAIN SETPOINTS.
- TEMPERATURE CONTROL: UNIT MOUNTED CONTROLLER SHALL OPEN LEAD UNIT(S) SOLIDNO ISOLATION VALVE(S) AND SHALL MODULATE COOLING COIL CONTROL VALVE(S) OPEN TO COIL AND STAGE ELECTRIC HEATING COIL TO MAINTAIN RETURN AIR HEATING & COOLING SETPOINTS (A.G.). NOTE: THE TWO LEAD UNITS SHALL OPERATE IN PARALLEL.
- HUMIDITY CONTROL: UNIT MOUNTED CONTROLLER SHALL MODULATE COOLING COIL CONTROL VALVE, STAGE ELECTRIC HEATING COIL & MODULATE HUMIDIFIER TO MAINTAIN RETURN AIR RELATIVE HUMIDITY (A.G.). HIGH LIMIT HUMIDITY SENSOR SHALL SHUTOFF HUMIDIFIER WHEN DISCHARGE AIR HUMIDITY EXCEEDS SETPOINT (A.G.).
- BMCS SHALL BE ABLE TO ADJUST SPACE TEMPERATURE & RELATIVE HUMIDITY SETPOINTS THROUGH UNIT MOUNTED CONTROLLER.
- ALARMS:
  - BMCS SHALL ALARM OPERATOR & SHALL ENABLE LAG UNITS IF HEATING, COOLING OR RELATIVE HUMIDITY SETPOINTS ARE NOT MAINTAINED.
  - BMCS SHALL MONITOR GENERAL ALARMS OF PACKAGED UNIT CONTROLLER & PACKAGED DUTY/STANDBY CONTROLLER.
  - BMCS SHALL MONITOR WATER DETECTOR SUPPLIED WITH UNIT & SHALL ALARM OPERATOR UPON DETECTION.
  - BMCS SHALL MONITOR FILTER STATUS DIFFERENTIAL PRESSURE SWITCH AND SHALL ALARM THE BMCS TO SIGNAL FILTER MAINTENANCE SHOULD THE DIFFERENTIAL PRESSURE ACROSS THE FILTER BANK RISE ABOVE PREDETERMINED SETPOINTS (A.G.).
- EMERGENCY GENERATOR OPERATION: IF THE EMERGENCY GENERATOR IS OPERATING, THEN THE HUMIDIFIER AND ELECTRIC REHEAT ON THE UNITS SHALL BE LOCKED OUT.
- OCCUPIED/UNOCCUPIED MODES: IF SPACE TEMPERATURE SENSOR DETECTS SPACE TEMPERATURE ABOVE 80°F (A.G.) OR BELOW 50°F (A.G.) WHEN IN UNOCCUPIED MODE BMCS SHALL START LEAD UNIT & SHALL OPERATE HEATING/COOLING TO MAINTAIN 50°F-80°F.

<b>LEO DAILY</b> PLANNING ARCHITECTURE ENGINEERING & CONSTRUCTION 8000 Indian Wells Drive Omaha, NE 68114-4039 Tel 402-391-8111 Fax 402-391-8364 LEO DAILY 001 1094.000 		REV DATE DESCRIPTION JCN REUSE DATE AND DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION WESTERN SERVICE AREA LOS ANGELES, CA REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING <b>CONTROL                  DIAGRAMS</b> PALM SPRINGS PALM SPRINGS INTERNATIONAL AIRPORT (PSP) CALIFORNIA SUBMITTED BY: [Signature] APPROVED BY: [Signature] DESIGNED GNR ISSUED BY: [Signature] DATE: October 5, 2008 JCN DRAWN PEH TERMINAL - LOS ANGELES DRAWING NO: PSP-D-ATCT- M503 CHECKED MPH	
---	--	---	--

[illegible]


## SEQUENCE OF OPERATION

- 7) GENERAL: VAPOR AIR VOLUME) FROM SPACE SHALL PROVIDE HEATING, COOLING AND VENTILATION TO THE AIRKAS AS SHOWN ON THE DRAWINGS.
- 8) OPERATING: UPON A CALL FROM THE SPACE TEMPERATURE SENSOR, THE IMCS SHALL MODULATE THE VAV BOX AIR VOLUME OPEN WHEN TEMPERATURE IS ABOVE SETPOINT AND CLOSED TO MAINTAIN AIR VOLUME POSITION WHEN TEMPERATURE IS BELOW SETPOINT. IF THE SENSOR CONTINUES TO CALL FOR HEAT THE IMCS SHALL STAGE THE ELECTRIC HEATING COILS ON TO SATISFY SPACE TEMPERATURE SETPOINT.
- 9) HEATING: THE INTERVAL VAV BOX CONTROLLER SHALL INCLUDE MANAGERIAL VAV FLOW "PRIORITY" PRIOR TO THE ELECTRIC HEATING COILS.
- 10) VAV-72 PROVIDES CONTROL VOLUME AIR FLOW TO ROOM NO. 72 AS SHOWN ON DRAWINGS. LINT HEATING COIL SHALL STAGE TO MAINTAIN 72°F (A02) SUPPLY AIR TEMPERATURE TO ROOM NO. 72.
- 11) ALARM IMCS OPERATOR IF TEMPERATURE IS MORE THAN 2°F (A02) ABOVE OR BELOW SETPOINT FOR A CONTINUOUS PERIOD OF 5 MINUTES (A02).
- 12) IF THE EMERGENCY DRAINAGE IS OPERATING, LOCK OUT THE ELECTRIC HEATING COIL.
- 13) OCCUPANCY/UNOCCUPIED MODES: IF SPACE TEMPERATURE SENSOR DETECTS SPACE TEMPERATURE ABOVE 85°F (A02) OR BELOW 50°F (A02) WHEN IN UNOCCUPIED MODE, THE IMCS SHALL STAGE THE VAV BOX AIR VOLUME ACCORDING TO DRAWING 72T-301.

[illegible]

## SEQUENCE OF OPERATION

- 1) GENERAL: FANCOIL UNIT SHALL PROVIDE HEATING, COOLING, & VENTILATION TO THE AREA AS SHOWN ON THE DRAWINGS.
- 2) OPERATION:
  - A) GENERAL: WHEN SPACE IS OCCUPIED THE FANCOIL UNIT FAN SHALL RUN CONTINUOUSLY AND THE OUTSIDE AIR DAMPER SHALL BE OPEN.
  - B) UPON A CALL FOR COOLING BMS SHALL MODULATE COOLING COIL CONTROL VALVE OPEN TO COOL TO MAINTAIN SETPOINT.
  - C) UPON A CALL FOR HEATING BMS SHALL START HEATING COIL TO MAINTAIN SETPOINT.
  - D) ALARM BMS OPERATOR IF SPACE TEMPERATURE RISES ABOVE 80°F (AUL), OR FALLS BELOW 40°F (DUL), OR WHEN FAN FAILS WHEN CALLED TO OPERATE.
  - E) BMS SHALL MONITOR FILTER STATUS DIFFERENTIAL, PRESSURE SWITCH AND SHALL ALARM THE BMS TO SIGNAL FILTER MAINTENANCE SHOULD THE DIFFERENTIAL PRESSURE ACROSS THE FILTER BANK RISE ABOVE PREDEFINITION SETPOINTS (AUL).
  - F) INCLUDE MAINFAM AIR "THROWING" PRIOR TO ENGAGING THE ELECTRIC HEATING COIL.
- 3) IF THE EMERGENCY GENERATOR IS OPERATING, LOCK OUT THE ELECTRIC HEATING COIL.
- 4) OCCUPANCY/UNOCCUPANCY MODES IF SPACE TEMPERATURE SENSOR DETECTS SPACE TEMPERATURE ABOVE 85°F (AUL) OR BELOW 50°F (DUL) WHEN IN UNOCCUPANCY MODES, FANCOIL UNIT SHALL STOP FAN AND MODULATE COILS TO MAINTAIN SETPOINT.




2 FAN COIL UNIT (FCU-4, 5, & 8) CONTROL DIAGRAM  
W504 SCALE: NONE

BMCS POINT SCHEDULE																				
SYSTEM, APPARATUS, OR AREA DESCRIPTION	INPUTS							OUTPUTS				ALARMS				NOTES				
	ANALOG			BINARY				BINARY		ANALOG										
	TEMPERATURE			STATUS ON / OFF	FILTER STATUS	SMOKE	AIR FLOW	STATUS OPEN / CLOSED	OPEN / CLOSE	DONOR / DOABLE	STOP	VALVE POSITION	SET POINT ADJUSTMENT	STAGE						
	PRESSURE	RH													HI ANALOG		LOW ANALOG	HI BINARY	LOW BINARY	REMOTE ALARM
SPACE SENSOR	●																			
FAN				●						●										
COOLING COIL										●		●								
HEATING COIL												●		●						

## SEQUENCE OF OPERATION

- 1) GENERAL: FANCOIL UNIT SHALL PUMP HEATING & COOLING TO THE AREA AS SHOWN ON THE DRAWINGS.
- 2) OPERATION:
  - A) GENERAL: WHEN SPACE CALLS FOR EITHER HEATING OR COOLING THE FANCOIL UNIT FAN SHALL RUN CONTINUOUSLY.
  - B) UPON A CONTINUED CALL FOR COOLING IMCS SHALL MODULATE COOLING COIL, CONTROL VALVE OPEN TO COOL TO MAINTAIN SETPOINT.
  - C) UPON A CONTINUED CALL FOR HEATING IMCS SHALL START HEATING COIL TO MAINTAIN SETPOINT.
  - D) ALARM IMCS OPERATOR IF SPACE TEMPERATURE RISES ABOVE 80°F (26.7°C), OR FALLS BELOW 45°F (4.0°C), OR WHEN FAN FALLS WHEN CALLED TO OPERATE.
  - E) INCLUDE MANUWAL AIR "PROVING" PRIOR TO ENGAGING THE ELECTRIC HEATING COIL.
- 3) IF THE EMERGENCY GENERATOR IS OPERATING, LOCK OUT THE ELECTRIC HEATING COIL.




5 FAN COIL UNIT (FCU-7) CONTROL DIAGRAM

BMCS POINT SCHEDULE												NOTES
SYSTEM APPARATUS, OR AREA DESCRIPTION	INPUTS				OUTPUTS				ALARMS			
	ANALOG		BINARY		BINARY		ANALOG					
	TEMPERATURE	PRESSURE	STATUS ON / OFF	FILTER STATUS	ENABLE / DISABLE	STAGE ON	SET POINT ADJUSTMENT	ANALOG	LOW BINARY	HIGH BINARY		
SPACE SENSOR	●				OPEN / CLOSE							
FAN			●		ENABLE / DISABLE				●			
COOLING COIL					STAGE STOP						●	
					STATUS OPEN / CLOSED							
					VALVE POSITION							
					MODULATION							
					STAGE							
					ANALOG				●			
					LOW ANALOG				●			
					HI BINARY							
					LOW BINARY							
					REMOTE ALARM					●		
					SENSOR FAIL							

## SEQUENCE OF OPERATION

- 1) GENERAL: FANCOIL UNIT SHALL PROVIDE COOLING TO THE AREA AS SHOWN ON THE DRAWINGS.
- 2) OPERATOR:
  - A) GENERAL: WHEN SPACE CALLS COOLING THE FANCOIL UNIT FAN SHALL RUN CONTINUOUSLY.
  - B) UPON A CONTINUED CALL FOR COOLING BMS SHALL MODULATE COOLING COIL CONTROL VALVE OPEN TO COOL TO MAINTAIN SETPOINT.
  - C) ALARM BMS OPERATOR IF SPACE TEMPERATURE RISES ABOVE 80°F (A.O.), OR FALLS BELOW 45°F (A.O.), OR WHEN FAN FAILS WHEN CALLED TO OPERATE.

EQUIPMENT ROOM CONTROL DIAGRAM  
(CRAC -4 AND 5)[illegible]

## SEQUENCE OF OPERATION


- 1) GENERAL: UNITS PROVIDE HEATING/COOLING & HUMIDITY CONTROL FOR THE AREAS AS SHOWN ON THE DRAWINGS. ONE UNIT SHALL OPERATE AS LEAD UNIT & ONE UNIT SHALL OPERATE AS STANDBY (LAG). PACKAGED UNIT/STANDBY CONTROLLER SHALL ALTERNATE UNITS EVERY 2 DAYS TO PROVIDE EQUAL TIME. SOLIDNO VALVE ON STANDBY UNITS' CHILLED WATER COIL SHALL REMAIN CLOSED.
- 2) OPERATION: BMCS SHALL ENABLE THE PACKAGED UNIT/STANDBY CONTROLLER WHICH SHALL THEN START & RUN THE LEAD UNIT CONTINUOUSLY. CONTROL OF THE UNIT SHALL BE THROUGH THE DEDICATED UNIT MOUNTED CONTROLLER (SEE SPECIFICATIONS). STANDBY CONTROLLER SHALL START & RUN LAG UNIT IF LEAD UNIT CANNOT MAINTAIN SETPOINTS.
- 3) TEMPERATURE CONTROL: UNIT MOUNTED CONTROLLER SHALL OPEN LEAD UNIT SOLIDNO SOLIDNO VALVE AND SHALL MODULATE COOLING COIL CONTROL VALVE, AND STAGE ELECTRIC HEATING COIL TO MAINTAIN RETURN AIR HEATING & COOLING SETPOINTS (AQJ).
- 4) HUMIDITY CONTROL: UNIT MOUNTED CONTROLLER SHALL MODULATE COOLING COIL CONTROL VALVE, HEATING COIL CONTROL VALVE & HUMIDIFIER TO MAINTAIN RETURN AIR RELATIVE HUMIDITY (AQJ). HIGH LIMIT HUMIDITY SENSOR SHALL SHUT/OFF HUMIDIFIER WHEN DISCHARGE AIR HUMIDITY EXCEEDS SETPOINT (AQJ).
- 5) BMCS SHALL BE ABLE TO ADJUST SPACE TEMPERATURE & RELATIVE HUMIDITY SETPOINTS THROUGH UNIT MOUNTED CONTROLLER.
- 6) ALARMS:
  - A) BMCS SHALL ALARM OPERATION & SHALL ENLARG LAG UNITS IF HEATING, COOLING OR RELATIVE HUMIDITY SETPOINTS ARE NOT MAINTAINED.
  - B) BMCS SHALL MONITOR GENERAL ALARM OF PACKAGED UNIT CONTROLLER & PACKAGED UNIT/STANDBY CONTROLLER.
  - C) BMCS SHALL MONITOR WATER DETECTOR SUPPLIED WITH UNIT & SHALL ALARM OPERATION UPON DETECTION.
- 7) (B)CS SHALL MONITOR FILTER STATUS DIFFERENTIAL PRESSURE SWITCH & SHALL ALARM THE UNITS TO SIGNAL FILTER MAINTENANCE SHOULD THE DIFFERENTIAL PRESSURE ACROSS THE FILTER BANK RISE ABOVE PREDETERMINED SETPOINTS (AQJ).
- 7) IF THE EMERGENCY OPERATOR IS OPERATING, THEN THE HUMIDIFIER AND ELECTRIC REHEAT SHALL BE LOCKED OUT.
- 8) OCCUPIED/UNOCCUPIED WIDES IF SPACE TEMPERATURE SENSOR DETECTS SPACE TEMPERATURE ABOVE 80F (AQJ) OR BELOW 50F (AQJ) WHEN IN UNOCCUPIED MODE BMCS SHALL START LEAD UNIT & SHALL OPERATE HEATING/COOLING TO 70F-80F-50F-60F.

<b>LEO A DAILY</b>											
PLANS REVISED REVISIONS BY DATE											
REV		DATE		DESCRIPTION		JCN		SCALE		A	
<b>DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION</b>											
WESTERN SERVICE AREA				LOS ANGELES, CALIF.							
<b>REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING</b>											
<b>CONTROL DIAGRAMS</b>											
PALM SPRINGS				PALM SPRINGS INTERNATIONAL AIRPORT (PSP)				CALIFORNIA			
SUBMITTED BY		APPROVED BY									
DESIGNED		DRAWN		CHECKED		ISSUED BY		DATE		JCN	
ENGINEERING SERVICES		TERMINAL - LOS ANGELES		DRAWING NO.		PSP-D-AICT-M504					

LAO KOL 000 10096-000

*(Circular Stamp: OFFICIAL PROFESSIONAL SEAL OF THE STATE OF CALIFORNIA No. M 33005 Exp. 6-30-11 REGISTERED ELECTRICAL ENGINEER)*





1 CHILLED WATER (CWP-1, 2 & CH-1, 2) CONTROL DIAGRAM  
WSP / SCALE: NONE

BACS POINT SCHEDULE											
SYSTEM, APPARATUS, OR AREA DESCRIPTION	INPUTS				OUTPUTS				ALARMS		
	ANALOG	BINARY	ANALOG	BINARY	ANALOG	BINARY	ANALOG	BINARY	ANALOG	BINARY	ANALOG
CWS											
CHR											
CWP-1, 2 (EACH)											
OUTSIDE AIR											
CH-1, 2 (EACH)											
MODIFIED ISOLATION VALVE											

SEQUENCE OF OPERATION

- GENERAL: PUMPS CWP-1,2, AND CHILLERS CH-1,2 PROVIDE CHILLED WATER FOR COOLING OF THE FACILITY. THE CHILLERS AND PUMPS ARE REDUNDANT. ONLY ONE CHILLER AND PUMP WILL OPERATE AT ANY TIME. BACS SHALL ALTERNATE UNITS EVERY 7 DAYS TO PROVIDE EQUAL RUN TIME.  
THE SWITCHOVER OF CHILLERS SHALL OCCUR AS FOLLOWS:  
A. THE OPERATIONAL (LEAD) CHILLER SHALL BE DE-ENERGIZED, WITH FLOW CONTINUING THROUGH THE CHILLER.  
B. THE LAG CHILLER'S ISOLATION VALVE SHALL OPEN AFTER LAG CHILLER ISOLATION VALVE PROVES SOFT OPEN (AOI). THE LAG CHILLER'S ISOLATION VALVE SHALL BECOME TO CLOSE. THE CHILLER VALVES "OPENING AND CLOSING" SHALL BE ACCOMPLISHED IN LESS THAN 1 MINUTE.  
C. AFTER A 2 MINUTE (AOI) DELAY TO INSURE FULL ACTUATION OF THE ISOLATION VALVES, THE LAG CHILLER SHALL BE ENERGIZED.  
D. IF LAG UNIT FAILS AS DESCRIBED ABOVE, BACS SHALL THEN TRY TO RESTART LEAD UNIT.  
THE SWITCHOVER OF PUMPS SHALL OCCUR AS FOLLOWS:  
A. THE LAG PUMP ENERGIZING, THEN AFTER A 2 MINUTE PERIOD (AOI) OF BOTH PUMPS OPERATING TO INSURE THE LAG PUMP IS AT FULL SPEED, THE LEAD PUMP SHALL THEN SHUT DOWN.  
B. IF LAG PUMP FAILS AS DESCRIBED ABOVE, BACS SHALL THEN TRY TO RESTART LEAD PUMP.
- OPERATION:  
A. COOLING OPERATION: DURING OCCUPIED MODE, THE BACS SHALL OPEN THE LEAD CHILLER ISOLATION VALVE, SHALL ENABLE THE LEAD CHILLER, AND THE LEAD CHILLED WATER PUMP SHALL START AND RUN CONTINUOUSLY. THE PACKAGED CHILLER CONTROLS SHALL THEN MODULATE THE COMPRESSORS TO MAINTAIN 45 DEGREES F (AOI) LEAVING CHILLED WATER SUPPLY TEMPERATURE AT THE CHILLER. THE BACS SHALL ALTERNATE EVERY 7 DAYS THE LEAD CHILLER AND LEAD CHILLED WATER PUMP TO PROMOTE EQUAL RUN TIME.  
B. BACS SHALL INTERFERE WITH THE CHILLERS AND SHALL BE ABLE TO RESET THE CHILLED WATER SUPPLY TEMPERATURE THROUGH THE BACS AT THE PACKAGED CHILLER CONTROLS.
- ALARMS:  
A) IF LEAD CHILLED WATER PUMP FAILS TO START OR STOPS AFTER BEING CALLED TO OPERATE, BACS SHALL ALARM OPERATOR & SHALL START LAG PUMP. ALARM SHALL BE THROUGH CURRENT SENDING RELAY.  
B) IF BUILDING CWS TEMPERATURE RISES ABOVE PREDETERMINED SETPOINT BY MORE THAN 3 DEGREES F (AOI) FOR MORE THAN 5 MINUTES (AOI), BACS SHALL ALARM OPERATOR.  
C) BACS SHALL MONITOR GENERAL ALARM FROM PACKAGED CHILLER CONTROLS AND SHALL SIGNAL ALARM TO OPERATOR.  
D) IF LEAD CHILLER STOPS AFTER BEING ENABLED OR CANNOT MAINTAIN CWS SETPOINT AT CHILLER, BACS SHALL ALARM OPERATOR AND SHALL START LAG CHILLER.  
E) FREEZE PROTECTION:  
1) WHEN OUTSIDE AIR TEMPERATURE IS BELOW 32°F (AOI) THE BACS SHALL ALTERNATE EVERY 4 HOURS (AOI) THE LEAD CHILLER TO PROVIDE PERIODIC FLOW THROUGH EACH CHILLER TO PREVENT FREEZING.  
2) MANUAL OPERATION: CHILLERS, PUMPS, AND ISOLATION VALVES SHALL BE ABLE TO BE MANUALLY ACTIVATED AND ACTUATED IN CASE OF FAILURE OF DDC SYSTEM.

VAV BOX AND FANCOIL UNIT DDC SYSTEM GRAPHICAL INFORMATION INTERFACE											
MARK	TEMPERATURE (°F)			CFM			ELECTRIC HEATING COIL			STATUS (N)	ALARM (Y)
	SETPOINT	COOLING	HEATING	ACTUAL	DESIGN MAXIMUM	DESIGN MINIMUM	ACTUAL	ENABLED (X)	STEPS ON (S)		
VW-1	75	72		80	35						
VW-4	75	72		480	190						
VW-5	75	72		85	55						
VW-6	75	72		570	300						
VW-7	75	72		80	55						
VW-11	75	72		430	190						
VW-12	75	72		245	105						
VW-21	75	72		450	190						
VW-22	75	72		275	190						
VW-23	75	72		215	105						
VW-31	75	72		380	190						
VW-33	75	72		150	105						
VW-34	75	72		560	300						
VW-36	75	72		870	425						
VW-41	75	72		235	105						
VW-54	75	72		260	105						
VW-64	75	72		500	300						
VW-62	75	72		240	105						
VW-63	75	72		310	190						
VW-64	75	72		265	80						
VW-72	75	72		200	200						
VW-74	75	72		120	55						
VW-101	73	72		115	55						
FCU-1	80	40		N/A	N/A	N/A					
FCU-4	80	65		N/A	N/A	N/A					
FCU-5	75	72		N/A	N/A	N/A					
FCU-7	75	70		N/A	N/A	N/A					
FCU-8	80	85		N/A	N/A	N/A					
FCU-10	75	72		N/A	N/A	N/A					

- REMARKS:
- PROVIDE A GRAPHICAL INTERFACE SCREEN SIMILAR TO ABOVE FOR USE BY BACS OPERATOR AS DESCRIBED BELOW.
  - TEMPERATURE SETPOINT SHALL BE ADJUSTABLE THRU GRAPHIC INTERFACE.
  - PROVIDE FLOOR PLAN GRAPHIC DISPLAY/INTERFACE THAT SHOWS VAV BOX AND FANCOIL UNIT LOCATIONS AND ROOM SENSOR LOCATIONS. PLAN SHALL BE CLEARLY LABELED TO INDICATE VAV BOX NUMBER, FANCOIL UNIT NUMBER, SENSOR NUMBER, SETPOINT TEMPERATURE AND ACTUAL TEMPERATURE. UNITS THAT ARE COOLING SHALL BE BLUE IN COLOR, HEATING ORANGE IN COLOR & ALARM RED IN COLOR.
  - ENABLE = YES / NO
  - STEPS ON = 0 / 1 / 2 / 3
  - STATUS = OCCUPIED / UNOCCUPIED
  - ALARM = HIGH TEMP / LOW TEMP / SENSOR FAIL / FAN FAILURE

2 VAV BOX / FANCOIL UNIT GRAPHICAL INTERFACE  
WSP / SCALE: NONE

OCCUPIED / UNOCCUPIED SCHEDULE											
EQUIPMENT	WEEKDAY		WEEKEND		HOLIDAY		START	STOP	START	STOP	STATUS
	START	STOP	START	STOP	START	STOP					
CH-1/2	4:00AM	10:00PM	4:00AM	10:00PM	4:00AM	10:00PM					
CWP-1/2	4:00AM	10:00PM	4:00AM	10:00PM	4:00AM	10:00PM					
AKU-1 & RT-1	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
ERU-1	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
AKU-2/3	4:00AM	10:00PM	4:00AM	10:00PM	4:00AM	10:00PM					
H-1	4:00AM	10:00PM	4:00AM	10:00PM	4:00AM	10:00PM					
H-2	4:00AM	10:00PM	4:00AM	10:00PM	4:00AM	10:00PM					
ET-1	4:00AM	10:00PM	4:00AM	10:00PM	4:00AM	10:00PM					
DWP-1	4:00AM	10:00PM	4:00AM	10:00PM	4:00AM	10:00PM					
DWP-1	4:00AM	10:00PM	4:00AM	10:00PM	4:00AM	10:00PM					
FCU-1	12:00AM	12:00PM	12:00AM	12:00PM	12:00AM	12:00PM					
FCU-4	4:00AM	10:00PM	4:00AM	10:00PM	4:00AM	10:00PM					
FCU-5	12:00AM	12:00PM	12:00AM	12:00PM	12:00AM	12:00PM					
FCU-7	12:00AM	12:00PM	12:00AM	12:00PM	12:00AM	12:00PM					
FCU-8	12:00AM	12:00PM	12:00AM	12:00PM	12:00AM	12:00PM					
FCU-10	12:00AM	12:00PM	12:00AM	12:00PM	12:00AM	12:00PM					
CHAC-1,2,3	12:00AM	12:00PM	12:00AM	12:00PM	12:00AM	12:00PM					
CHAC-4,5	12:00AM	12:00PM	12:00AM	12:00PM	12:00AM	12:00PM					
VW-1	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-4	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-5	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-6	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-7	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-11	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-12	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-21	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-22	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-23	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-31	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-33	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-34	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-36	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-41	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-54	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-61	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-62	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-63	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-64	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-72	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-74	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					
VW-101	8:00AM	6:00PM	8:00AM	5:00PM	OFF	OFF					

- REMARKS:
- PROVIDE A OCCUPIED/UNOCCUPIED SCHEDULE SCREEN SIMILAR TO ABOVE FOR USE BY BACS OPERATOR AS DESCRIBED BELOW.
  - ALL TIMES SHALL BE ADJUSTABLE THRU GRAPHIC INTERFACE BY SELECTING INDIVIDUAL TIME. SELECTING SHALL BE BY HOUR AND 15 MINUTE INCREMENTS AND SHALL ALSO INCLUDE OFF.
  - BACS SHALL NOT ALLOW INVALID TIME SELECTIONS. BACS SHALL POST A LOCAL SCREEN ERROR INDICATING INVALID START/STOP TIMES.
  - TO DENOTE A TWENTY FOUR HOUR RUN TIME, SELECTION SHALL BE 12:00 PM (START)/12:00 PM (STOP).

3 OCCUPIED/UNOCCUPIED SCHEDULE  
WSP / SCALE: NONE

<b>LEO A DAILY</b> PLANNING ADMINISTRATION DIVISION 100 Indian Wells Drive Omaha, NE 68114-4039 Tel 402-391-8111 Fax 402-391-8364		DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION WESTERN SERVICE AREA LOS ANGELES, CA REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING <b>CONTROL DIAGRAMS</b> PALM SPRINGS PALM SPRINGS INTERNATIONAL AIRPORT (PSP) CALIFORNIA			
REV	DATE	DESCRIPTION	CHK	DATE	APP
SUBMITTER'S TITLE: _____ DESIGNED: GNR CHECKED: MPH ISSUED BY: _____ ENGINEERING SERVICES TERMINAL - LOS ANGELES DATE: October 5, 2008 DRAWING NO: PSP-D-ATCT- M505 APPROVED BY: _____ APPROVER'S TITLE: _____					





[illegible]

## REMARKS

- REMARKS:
1. UNIT TO BE LEAKED CHILLED WATER DOWN FLOW UNIT W/ INFRARED HUMIDIFIER, ELECTRIC REHEAT, AND 3 HP SUPPLY FAN.
  2. SEE DETAIL 2/MS-03 FOR SEQUENCE OF OPERATION.
  3. SEE DETAIL 3/MS-04 FOR SEQUENCE OF OPERATION.
  4. UNIT TO BE LEAKED CHILLED WATER UP FLOW UNIT W/ TOP DISCHARGE/PLUNION GRILLE, INFRARED HUMIDIFIER, ELECTRIC REHEAT, CONDENSATE PUMP, AND 2 HP SUPPLY FAN.
  5. UNIT TO BE SUPPLIED W/ REVERSE OSMOSIS WATER SUPPLY.
  6. UNIT TO BE SUPPLIED A RELAY TO ALLOW ELECTRIC HUMIDIFIER AND HUMIDIFIER TO BE LOCKED OUT WHEN EMERGENCY GENERATOR IS OPERATING.

WFCU		FAN COIL UNIT SCHEDULE																				REMARKS	
MARK	LOCATION	TYPE	CFM	COOL PRESS.		COOLING DATA								HEATING DATA				ELECTRICAL DATA		MANUF. AND MODEL NO.			
				IN		OUT		WAT	Y	WAT	Y	WAT	Y	WAT	Y	WAT	Y	WAT	Y				
				NO.	NO.	NO.	NO.															NO.	NO.
FCU-1	RM 76	HORIZ. COIL	175	---	---	85	82	4.5	4.5	1.0	43	34	10	35	1.5	1	0.53	685	208	1	60	TRANE UNITPANE SIZE 020	1
FCU-1	RM 806	HORIZ. COIL	415	---	---	85	82	11	11	1.5	45	32	10	35	2	2	0.67	895	208	1	60	TRANE UNITPANE SIZE 060	1
FCU-5	RM 92	HORIZ. CONCAVE	130	0.05	---	85	80	2.5	2.5	0.3	45	64	10	55	1	1	0.53	656	208	1	60	TRANE UNITPANE SIZE 020	3
FCU-7	RM 813	HORIZ. COIL	140	---	---	75	61	15.8	13.5	4.0	45	32	10	---	---	---	0.1	1023	208	1	60	TRANE UNITPANE SIZE 080	1
FCU-8	RM 93	HORIZ. COIL	560	---	---	85	62	21.2	21.2	5.7	45	30	18	55	3	2	0.13	1043	208	1	60	TRANE UNITPANE SIZE 080	1
FCU-10	RM 806	VERT. DUCTED	800	0.75	1.2	86	70	36.9	33.8	8.0	40	37	10	75	5.5	3	0.5	1417	208	1	60	TRANE BLOWER COIL BXC0336	1

## REMARKS

- |  |  |
|--|--|
| REMARKS:   |  |
| 1. PROVIDE FRONT GRILLE DISCHARGE AND BOTTOM STAMPED INLET.          |  |
| 2. PROVIDE FRONT TOE INLET, TOP GRILLE OUTLET AND CONDENSATE PUMP.   |  |
| 3. PROVIDE DUCT COLLAR OUTLET.                                       |  |
| 4. PROVIDE UNIT WITH INLET PLENUM WITH 1" FILTER AND CONDENSATE PUMP |  |

[illegible]

HUMIDIFIER SCHEDULE												
MARK	LOCATION	SERIES	TYPE	CFM	CAPACITY LBS./HR.	KW	ELECTRICAL DATA				MANUFACTURER AND MODEL NO.	REMARKS
							FLA	VOL	PH	HZ		
H-1	BASE BUILDING	AHU-1	ELECTRIC	4510	86.1	30	84	200	3	60	ARWINGTON HC-6500	1, 2, 4
H-2	TOWER MECH.	AHU-2,3	ELECTRIC	5560	13.2	8	23	200	3	60	ARWINGTON HC-6100	1, 3, 4

## REMARKS

- REMARKS:
1. PROVIDE PROPORTIONAL OUTPUT CONTROL, DOCS INTERFACE FOR ENABLE/DISABLE, SETPOINT (ADJUSTABLE), AND ALARM OUTPUT.
  2. DISPERSION GRID TO BE MOUNTED IN AHU.
  3. DISPERSION GRID TO BE MOUNTED IN SUPPLY AIR DUCTWORK (AHU-2 AND AHU-3 SHALL SHARE DISPERSION GRID).
  4. UNITS TO BE SUPPLIED W/ REVERSE OSMOSIS WATER SUPPLY.

WQ402		AIR COOLED CHILLER SCHEDULE																		
MARK	LOCATION	TYPE	AHS TRAMP T-DB	MIN CAP T-DB	CONDENSER WATER					CONDENSER SAE					CONDENSER		MANUFACTURER AND MODEL NO.	REMARKS		
					GPM	ENT S	LENT S	MAX P-FT	NO.	COND.	TOTAL	WOL	FIN	FL.	NO.	TOTAL STEPS			ONSE/STEP	
CH-1	SEE DWGS	AIR-COOLED SCROLL	115	66.1	185	54.6	45	15	6	PROPELLER	38.4	208	3	40	220	4	4	17.2/36.0/20.6/196.1	TRANE CG4080	1, 2, 3
CH-2	SEE DWGS	AIR-COOLED SCROLL	115	66.1	185	54.6	45	15	6	PROPELLER	38.4	208	3	40	220	4	4	17.2/36.0/20.6/196.1	TRANE CG4080	1, 2, 3

## REMARKS

- REMARKS:
1. PROVIDE COPPER TUBES AND COPPER FNS.
  2. PROVIDE UNIT W/ LOW AMBIENT OPERATION.
  3. CHILLER SHALL BE RATED TO OPERATE AT 125°F, PROVIDING 60.3 TONS OF CAPACITY AT THE SCHEDULED FLOWRATE AND A 55 DEGREE DWT.
  4. CHILLER TO HAVE DUAL PT POWER CONNECTION. FLA SHOWN ARE FOR EACH POWER CONNECTION.

[illegible]

## SYNOPSIS

- REMARKS:
1. PROVIDE FAN W/ GRAVITY BACKDRIFT DAMPER.
  2. RETURN FAN SHALL BE CONTROLLED BY VARIABLE FREQUENCY DRIVE.

[illegible]

## REMARKS

- REMARKS:
1. UNIT SHALL INCLUDE THE FOLLOWING MODULES: FILTER MODULE W/ 2" (30% EFFICIENT) PLEATED MEDIA AND 12" (85% EFFICIENT) CARTRIDGE, ELECTRIC HEATING COIL, ACCESS, COOLING COIL AND SUPPLY FAN.
  2. AIR HANDLERS SHALL BE STACKED WITHOUT REQUIRING SUPPLEMENTAL STRUCTURAL SUPPORTS OR BRACING, INCLUDING SEISMIC REQUIREMENTS OTHER THAN MFR. BASE RAILS.
  3. UNIT SHALL INCLUDE THE FOLLOWING MODULES: AIR MIXING MODULE W/ 2" (30% EFFICIENT) PLEATED MEDIA FILTER, ACCESS, ELECTRIC HEATING COIL, HUMIDIFICATION MODULE, ACCESS, COOLING COIL, AND SUPPLY FAN WITH TOP DISCHARGE.
  4. UNIT SUPPLY FAN SHALL BE CONTROLLED BY VARIABLE FREQUENCY DRIVE.

MARK		CHILLED WATER COOLING COIL SCHEDULE															
MARK	SERIES	CFM	MAX FACE VEL FPM	TWT °F				CHILLED WATER				GPM	CHILLED WATER		MANUFACTURER AND MODEL NO.	REMARKS	
				DB	WB	DB	WB	DB	WB	DB	WB		DB	WB			
CC-1	AHU-1	6950	489	80.6	66.5	50.2	53.3	0.47	271.8	271.8	54.2	45	35	6.0	4	TOONE TO FIT AHU-1	
CC-1	AHU-2	5560	452	80.6	66.5	50.2	54.1	0.42	194.6	178.3	35.5	45	35	6.0	4	TOONE TO FIT AHU-2	
CC-3	AHU-3	5560	452	80.3	66.8	50.9	54.1	0.42	194.6	178.3	35.5	45	35	6.0	4	TOONE TO FIT AHU-3	

## REMARKS:

WSE#		ELECTRIC HEATING COIL SCHEDULE												MANUFACTURER AND MODEL NO.		REMARKS
WARK	SERIES	TYPE	CFM	WAT FTH	WAT FTH	MAX AIR FTH	MAX AIR FTH	VOLTS	PH	Hz	STEPS					
DHC-1	AWU-1	ELECTRIC	1500	43	0.16	209	3	60	24.3	SCR	TRANE TO FIT AWU-1		1			
DHC-2	AWU-2	ELECTRIC	5500	1500	68.3	0.14	209	3	60	41.3	SCR	TRANE TO FIT AWU-2	1			
DHC-3	AWU-3	ELECTRIC	1500	68.3	0.14	209	3	60	41.3	SCR	TRANE TO FIT AWU-3		1			
DHC-4	AWU-4	ELECTRIC	1500	68.3	0.14	209	3	60	41.3	SCR	TRANE TO FIT AWU-4					

## REMARKS


- REMARKS  
1. FN-TUBULAR TYPE. PROVIDE AIRFLOW INTERLOCK SWITCH AND DISCONNECT INTEGRAL TO CONTROL PANEL ACCESS DOOR

ENERGY RECOVERY UNIT SCHEDULE																	
MARK		SERIES	TYPE	CFM D.A.	CFM E.A.	MAX AVG S.P.	HEATING				COOLING				MANUFACTURER AND MODEL NO.	REMARKS	
NO.	NO.						1	2	3	4	5	6	7	8			9
ERU-1	ANU-1	STATIC PLATE	2080	1400	0.50	31	52.5	75	50	112	73	84.0	68.7	75	45	REMARK: HEIZ	1

## REMARKS:

- REMARKS:  
1. PROVIDE W/ INTERNAL 2HP OUTSIDE AIR FAN AND 2HP EXHAUST FAN

[illegible]

LEO A DAILY																																															
PLANS EXHIBITS INSTRUCTIONS																																															
ID																																															
REV		DATE		DESCRIPTION		JCN		RESUME		APV																																					
<p align="center"><b>DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION</b></p> <p><b>WESTERN SERVICE AREA</b> <span style="float: right;"><b>LOS ANGELES, CA</b></span></p> <p align="center"><b>REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING</b></p> <p align="center"><b>SCHEDULES</b></p>																																															
<p>LAD NO. 900 10096-008</p>																																															
																																															
<p><b>PALM SPRINGS</b> <span style="margin-left: 100px;"><b>PALM SPRINGS INTERNATIONAL AIRPORT (PSP)</b></span> <span style="float: right;"><b>CALIFORNIA</b></span></p> <table border="1" style="width: 100%;"> <tr> <td colspan="2">                 REVIEWED BY: <i>[Signature]</i> </td> <td colspan="2">                 SUBMITTED BY: <i>[Signature]</i> </td> <td colspan="2">                 APPROVED BY: <i>[Signature]</i> </td> </tr> <tr> <td colspan="2">                 SUBMITTER'S TITLE:             </td> <td colspan="2">                 ISSUED BY:             </td> <td colspan="2">                 APPROVED'S TITLE:             </td> </tr> <tr> <td colspan="2">                 DESIGNED: <b>QAR</b> </td> <td colspan="2">                 FOR: <b>ENGINEERING SERVICES</b> </td> <td colspan="2">                 DATE: <b>October 5, 2009</b> </td> </tr> <tr> <td colspan="2">                 DRAWN: <b>PEH</b> </td> <td colspan="2">                 FOR: <b>LOS ANGELES</b> </td> <td colspan="2">                 JCN:             </td> </tr> <tr> <td colspan="2">                 CHECKED: <b>MPH</b> </td> <td colspan="2">                 FOR: <b>LOS ANGELES</b> </td> <td colspan="2">                 DRAWING NO:             </td> </tr> <tr> <td colspan="6"> <p align="right"><b>PSP-D-ATCT- M601</b></p> </td> </tr> </table>												REVIEWED BY: <i>[Signature]</i>		SUBMITTED BY: <i>[Signature]</i>		APPROVED BY: <i>[Signature]</i>		SUBMITTER'S TITLE:		ISSUED BY:		APPROVED'S TITLE:		DESIGNED: <b>QAR</b>		FOR: <b>ENGINEERING SERVICES</b>		DATE: <b>October 5, 2009</b>		DRAWN: <b>PEH</b>		FOR: <b>LOS ANGELES</b>		JCN:		CHECKED: <b>MPH</b>		FOR: <b>LOS ANGELES</b>		DRAWING NO:		<p align="right"><b>PSP-D-ATCT- M601</b></p>					
REVIEWED BY: <i>[Signature]</i>		SUBMITTED BY: <i>[Signature]</i>		APPROVED BY: <i>[Signature]</i>																																											
SUBMITTER'S TITLE:		ISSUED BY:		APPROVED'S TITLE:																																											
DESIGNED: <b>QAR</b>		FOR: <b>ENGINEERING SERVICES</b>		DATE: <b>October 5, 2009</b>																																											
DRAWN: <b>PEH</b>		FOR: <b>LOS ANGELES</b>		JCN:																																											
CHECKED: <b>MPH</b>		FOR: <b>LOS ANGELES</b>		DRAWING NO:																																											
<p align="right"><b>PSP-D-ATCT- M601</b></p>																																															

### DIFFUSER, REGISTER AND GRILLE SCHEDULE

MARK	SERIES	TYPE	NECK SIZE	FINISH	MAX PG INCH WS	MAX K/LC	MANUFACTURER AND MODEL NO.	REMARKS
D-1	SEE PLANS	SQUARE SUPPLY DIFFUSER	SEE PLAN	WHITE	0.10	38	TITUS TDC	1
LD-1	SEE PLANS	LINER DIFFUSER	SEE PLAN	(NOTE 3)	0.08	38	TITUS TC-481 N/ BOARDER TYPE B11	2
R-1	SEE PLANS	SUPPLY BLACK REGISTER	SEE PLAN	WHITE	0.10	38	TITUS 300 RL	
R-2	SEE PLANS	RETURN/EXHAUST BLACK REGISTER	SEE PLAN	WHITE	0.10	38	TITUS 350 RL	
G-1	SEE PLANS	RETURN PERFORATED GRILLE 24"x24" FACE	SEE PLAN	WHITE	0.06	36	TITUS PAR	
G-2	SEE PLANS	RETURN PERFORATED GRILLE 24"x12" FACE	SEE PLAN	WHITE	0.06	36	TITUS PAR	

## REMARKS

1. 12"x12" W/ 24"x24" EXTENDED PANEL.
2. DIFFUSER TO HAVE 15° DIRECTIONAL BLADES, DIRECT DIFFUSER TO BLOW AIR "OUT" TOWARDS CAB GLASS.
3. PROVIDE ANODIZED FINISH TO MATCH CAB GLASS FRAME.

### AIR TERMINAL UNIT SCHEDULE

MARK	TYPE	CFW		MAX SIZE INCH	P/O MAX CFW INCH	INC. IN MAX. SIZE		ELEC. TESTING CODE		MANUFACTURER AND MODEL NO.	REMARKS
		MIN	MAX			IN/OUT	IN/OUT	IN	IN/OUT		
VW-1	VW W/ ELECTRIC REHAID	80	55	4	0.25	22	22	0.3	2008	1 60 1	TITUS DESIG 4
VW-4	VW W/ ELECTRIC REHAID	480	190	8	0.25	22	22	2.5	2008	1 60 3	TITUS DESIG 8
VW-5	VW W/ ELECTRIC REHAID	85	55	4	0.25	22	22	0.5	2008	1 60 1	TITUS DESIG 4
VW-6	VW W/ ELECTRIC REHAID	370	300	10	0.25	22	22	2.5	2008	1 60 3	TITUS DESIG 10
VW-7	VW W/ ELECTRIC REHAID	80	55	4	0.25	22	22	0.5	2008	1 60 1	TITUS DESIG 4
VW-11	VW W/ ELECTRIC REHAID	430	190	8	0.25	22	22	1.5	2008	1 60 3	TITUS DESIG 8
VW-12	VW W/ ELECTRIC REHAID	245	105	6	0.25	22	22	1.0	2008	1 60 2	TITUS DESIG 6
VW-21	VW W/ ELECTRIC REHAID	450	180	8	0.25	22	22	1.5	2008	1 60 3	TITUS DESIG 8
VW-22	VW W/ ELECTRIC REHAID	360	160	8	0.25	22	22	1.0	2008	1 60 2	TITUS DESIG 8
VW-23	VW W/ ELECTRIC REHAID	215	105	6	0.25	22	22	1.0	2008	1 60 2	TITUS DESIG 6
VW-31	VW W/ ELECTRIC REHAID	360	160	8	0.25	22	22	1.0	2008	1 60 2	TITUS DESIG 8
VW-33	VW W/ ELECTRIC REHAID	150	105	6	0.25	22	22	0.5	2008	1 60 1	TITUS DESIG 6
VW-34	VW W/ ELECTRIC REHAID	560	300	10	0.25	22	22	1.5	2008	1 60 3	TITUS DESIG 10
VW-36	VW W/ ELECTRIC REHAID	870	425	12	0.25	22	22	3.0	2008	1 60 3	TITUS DESIG 12
VW-41	VW W/ ELECTRIC REHAID	235	105	8	0.25	22	22	0.5	2008	1 60 1	TITUS DESIG 8
VW-54	VW W/ ELECTRIC REHAID	260	105	6	0.25	22	22	0.5	2008	1 60 1	TITUS DESIG 6
VW-61	VW W/ ELECTRIC REHAID	500	300	10	0.25	22	22	1.5	2008	1 60 3	TITUS DESIG 10
VW-62	VW W/ ELECTRIC REHAID	240	105	6	0.25	22	22	0.5	2008	1 60 1	TITUS DESIG 6
VW-63	VW W/ ELECTRIC REHAID	310	190	8	0.25	22	22	1.0	2008	1 60 3	TITUS DESIG 8
VW-64	VW W/ ELECTRIC REHAID	205	80	6	0.25	22	22	1.5	2008	1 60 3	TITUS DESIG 6
VW-72	VW W/ ELECTRIC REHAID	200	200	6	0.25	22	22	0.5	2008	1 60 1	TITUS DESIG 6
VW-74	VW W/ ELECTRIC REHAID	120	55	4	0.25	22	22	0.5	2008	1 60 1	TITUS DESIG 4
VW-101	VW W/ ELECTRIC REHAID	115	55	4	0.25	22	22	1.0	2008	1 60 2	TITUS DESIG 4

THE MANUSCRIPT

1. UNIT TO BE CONSTANT VOLUME UNIT TO PROVIDE VENTILATION AIR TO EQUIPMENT ROOM NO. 72 AS SHOWN ON THE DRAWINGS.

## OUTSIDE AIR INTAKE OR RELIEF SCHEDULE

[illegible]

## REMARKS

1. PROVIDE 30% EFFICIENT "ROUGHING" FILTER.
2. PROVIDE WITH 12" ROOF CURB.

## MECHANICAL EQUIPMENT SCHEDULE

MARK	FUNCTION	SPECIFICATION	MANUFACTURER AND MODEL NO.	REMARKS
CWT-1	CHILLED WATER BUFFER TANK	210 GALLON INSUL. WELDED STEEL w/ (125 PSI) A.S.W.E. STAMP	LAWS CWT-30-07T w/FLUOD 3" I/O CONNECTIONS	1
AS-1	AIR SEPARATOR (CHILLED WATER)	144 GPM MAX. FLOW RATE 3" CONNECTIONS	TACO ACS	

## REMARKS:

1. PROVIDE INTERNAL BAFFLES TO INSURE ANTI-STRATIFICATION/BLENDING THRU TANK AND 1-1/2" EXTERIOR FIBERGLASS INSULATION.

### EXPANSION TANK SCHEDULE

MARK	LOCATION	SERVIS	SIZE DIA X L INCH	MIN. ACCUPANCE GALLONS	MIN. TOTAL CAPACITY GALLONS	MANUFACTURER AND MODEL NO.	REMARKS
ET-1	MECH. RM	CHILLED WATER LOOP	18"X642-3/4"	11.3	33.6	AMTROL SX-60 (VERTICAL)	

### CONTROL VALVE SCHEDULE

[illegible]

LEO A DAY															
ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED DATE 01-11-2001 BY 60322 (U)		REV		DATE		DESCRIPTION		JCN		RESUME DATE		JCN		JCN	
0600 Indian Hills Drive Omaha, NE 68131-4079 Tel 402-391-8111 Fax 402-391-0564		DEPARTMENT OF TRANSPORTATION FEDERAL AVIATION ADMINISTRATION WESTERN SERVICE AREA LOS ANGELES, CA REPLACE AIRPORT TRAFFIC CONTROL TOWER AND ESTABLISH BASE BUILDING SCHEDULES													
LAD NO. 002 10096 000															
		PALM SPRINGS PALM SPRINGS INTERNATIONAL AIRPORT (PSP) CALIFORNIA SUBMITTED BY <i>[Signature]</i> APPROVED BY <i>[Signature]</i> SUBMITTER'S TITLE: _____ DESIGNED: CHS DATE October 5, 2009 JCN DRAWN: PEH CHECKED: MPH ISSUED BY: LOS ANGELES TERMINAL: _____ DRAWING NO. _____ PSP-D-ATCT- M602													

SECTION 15950 - HVAC TESTING/ADJUSTING/BALANCING

PART 1 - GENERAL

1.1 RELATED REQUIREMENTS

- A. Section 15995, COMMISSIONING OF HVAC SYSTEMS.

1.2 DESCRIPTION OF WORK

- A. The work includes test, adjust, and balance (TAB) of new heating, ventilating, and cooling (HVAC) air and water distribution systems including equipment, ducts, and piping which are located within, on, under, between, and adjacent to buildings.
- B. Air Distribution Systems. Systems shall be tested, adjusted, and balanced (TAB'd) in compliance with this section. Obtain Contracting Officer's written approval before applying insulation to exterior of air distribution systems under Section 15080 THERMAL INSULATION FOR MECHANICAL SYSTEMS.
- C. Water Distribution Systems. Systems shall be TAB'd in compliance with this section. Obtain Contracting Officer's written approval before applying insulation to water distribution systems under Section 15080 THERMAL INSULATION FOR MECHANICAL SYSTEMS. At Contractor's option and with Contracting Officer's written approval, the piping systems may be insulated before systems are TAB'd. Piping insulation shall terminate immediately adjacent to each flow control valve, automatic control valve, or device. The ends of pipe insulation and the space between ends of pipe insulation and piping shall be sealed with waterproof vapor barrier coating. After completion of work under this section, the flow control valves and devices shall be insulated under Section 15080 THERMAL INSULATION FOR MECHANICAL SYSTEMS.
- D. Phasing of Work. This Specification Section is structured as though the HVAC construction, and thereby the TAB work, is going to be completed in a single phase. All elements of the TAB work are addressed on this premise. When a contract is to be completed in construction phases, including the TAB work, the TAB work shall be planned for, completed and approved by the Contracting Officer with each phase. An example of this case would be one contract that requires the rehabilitation of the HVAC in each of several separated buildings. At the completion of the final phase, all approved reports shall be compiled and submitted as one document.

1.3 DEFINITIONS

- A. TAB team supervisor: TAB team engineer.
- B. TAB team technician: TAB team assistant.
- C. TAB'd: HVAC Testing/Adjusting/Balancing procedures performed.
- D. Field check group: One or more systems of the same basic type; the subgroup of a "field check group" is a "system". An example of a "system" is a supply air handler with its duct system, which is its supply, return, and outside air ducts.
- E. Out-of-tolerance data: Pertains only to field checking of Certified TAB report. When applied to TAB work this phrase means "a measurement taken during TAB field checking which does not fall within the range of plus 5 to minus 5 percent of the original measurement reported on the certified TAB Report for a specific parameter."
- F. Season of maximum heating load: Time of year when outdoor ambient temperature at equipment installation site remains within following range throughout the period of data recording for TAB work. Indicated winter outdoor design dry bulb temperature plus 30 to minus 30 degrees Fahrenheit.
- G. Season of maximum cooling load: Time of year when outdoor ambient temperature at equipment installation site remains within following range throughout the period of data recording for TAB work. Indicated summer outdoor design dry bulb temperature plus 15, minus 5 degrees Fahrenheit.



1.4 SUBMITTALS

- A. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES.
- B. Test Reports
  - 1. Certified TAB report
  - 2. Submit certified reports in the specified format including the above data.
- C. Certificates
  - 1. Independent TAB agency personnel qualifications; G
  - 2. TAB Submittal and Work Schedule; G
  - 3. Design review report; G
  - 4. Pre-field TAB engineering report; G
  - 5. Advanced notice for TAB field work; G

1.5 TAB SUBMITTAL AND WORK SCHEDULE

- A. Submit this schedule, adapted for this particular contract, to the Contracting Officer for review and approval. Include with the submittal the planned calendar dates for each submittal or work item. Resubmit an updated version for CO approval every 90 calendar days. Compliance with the following schedule is the Contractor's responsibility.
- B. Qualify TAB Personnel. Within 45 calendar days after date of contract award, submit TAB agency and personnel qualifications.
- C. Pre-TAB Meeting. Within 30 calendar days after the date of approval of the TAB agency and personnel, meet with the Contracting Officer's TAB representative.
- D. Design Review Report. Within 60 calendar days after the date of the TAB agency personnel qualifications approval, submit design review report.
- E. Pre-Field TAB Engineering Report. Within 21 calendar days after approval of the TAB agency Personnel Qualifications, submit the Pre-Field TAB Engineering Report.
- F. Prerequisite HVAC Work Check Out List and Advanced Notice For TAB Field Work. At a minimum of 120 calendar days prior to CCD, submit prerequisite HVAC work check out list certified as complete, and submit advance notice of commencement of TAB field work.
- G. TAB Field Work. At a minimum of 90 calendar days prior to CCD, and when the ambient temperature is within limits, accomplish TAB field work.
- H. Submit TAB Report. Within 15 calendar days after completion of TAB field work, submit certified TAB report.
- I. TAB Field Check. 30 calendar days after certified TAB report is approved by the Contracting Officer, conduct field check.
- J. Complete TAB Work. Prior to CCD, complete all TAB work.
- K. TAB Field Work. At a minimum of 90 calendar days prior to CCD, accomplish TAB field work; submit certified TAB report; and conduct field check.
- L. Complete TAB Work. Prior to CCD, complete all TAB work.

1.6 QUALITY ASSURANCE

- A. Modifications of References. Accomplish work in accordance with referenced publications of AABC or NEBB except as modified by this section. In the references referred to herein, consider the advisory or recommended provisions to be mandatory, as though the word "shall" had been substituted for the words "should" or "could" or "may" wherever they appear. Interpret reference to the "authority having jurisdiction," the "Administrative Authority," the "Owner," or the "Design Engineer" to mean the "Contracting Officer."

B. Certificates.

1. Independent TAB Agency Personnel Qualifications
  - a. For agency proposed for approval, submit information certifying that the TAB agency is a first tier subcontractor who is not affiliated with any other company participating in work on this contract , including design, furnishing equipment, or construction.
  - b. Submit the following, for the agency, to Contracting Officer for approval in compliance with paragraph entitled "TAB Personnel Qualification Requirements."
    - 1) Independent AABC or NEBB certified TAB agency:
    - 2) TAB agency: AABC registration number and expiration date of current certification; or NEBB certification number and expiration date of current certification.
    - 3) TAB team supervisor: Name and copy of AABC or NEBB TAB supervisor certificate and expiration date of current certification.
    - 4) TAB team field leader: Name and documented evidence that the team field leader shall have satisfactorily performed full-time supervision of TAB work in the field for not less than 3 years immediately preceding this contract's bid opening date.
    - 5) TAB team field technicians: Names and documented evidence that each field technician shall have satisfactorily assisted a TAB team field leader in performance of TAB work in the field for not less than one year immediately preceding this contract's bid opening date.
    - 6) Current certificates: Registrations and certifications shall be current, and valid for the duration of this contract. Certifications which expire prior to completion of the TAB work, shall be renewed in a timely manner so that there is no lapse in registration or certification. TAB agency or TAB team personnel without a current registration or current certification shall not perform TAB work on this contract.
    - 7) TAB Team Members: TAB team approved to accomplish work on this contract shall be full-time employees of the TAB agency. No other personnel shall do TAB work on this contract.
    - 8) Replacement of TAB team members: Replacement of members may occur if each new member complies with the applicable personnel qualifications and each is approved by the Contracting Officer.
2. Design Review Report. Submit typed report describing omissions and deficiencies in the HVAC system's design that would preclude the TAB team from accomplishing the duct leakage testing work and the TAB work requirements of this section. Provide a complete explanation including supporting documentation detailing the design deficiency. State that no deficiencies are evident if that is the case.
3. Pre-Field TAB Engineering Report. Submit report containing the following information:
  - a. Step-by-step TAB procedure:
    - 1) Strategy: Describe the method of approach to the TAB field work from start to finish. Include in this description a complete methodology for accomplishing each seasonal TAB field work session.
    - 2) Procedural steps: Delineate fully the intended procedural steps to be taken by the TAB field team to accomplish the required TAB work of each air distribution system and each water distribution system. Include intended procedural steps for TAB work for subsystems and system components.
  - b. Pre-field data: Submit AABC or NEBB or SMACNA HVACTAB data report forms with the following pre-field information filled in:
    - 1) Design data obtained from system drawings, specifications, and approved submittals.
    - 2) Notations detailing additional data to be obtained from the contract site by the TAB field team.
    - 3) Designate the actual data to be measured in the TAB field work.
    - 4) Provide a list of the types of instruments, and the measuring range of each, which are anticipated to be used for measuring in the TAB field work. By means of a keying scheme, specify on each TAB data report form submitted, which instruments will be used for measuring each item of TAB data. If the selection of which instrument to use, is to be made in the field, specify from which instruments the choice will be made. The instrument key number shall be placed in the blank space where the measured data would be entered.
  - c. Prerequisite HVAC work checkout list: Provide a list of inspections and work items which are to be completed by the Contractor. This list shall be acted upon and completed by the Contractor and then submitted and approved by the Contracting Officer prior to the TAB team coming to the contract site. At a minimum, a list of the applicable inspections and work items listed in the NEBB TABES, Section III, "Preliminary TAB Procedures" under paragraphs titled, "Air Distribution System Inspection" and "Hydronic Distribution System Inspection" shall be provided for each separate system to be TAB'd.



- C. Responsibilities. The Contractor shall be responsible for ensuring compliance with the requirements of this section. The following delineation of specific work responsibilities is specified to facilitate execution of the various work efforts by personnel from separate organizations. This breakdown of specific duties is specified to facilitate adherence to the schedule listed in paragraph entitled "TAB Submittal and Work Schedule".
1. Contractor.
    - a. TAB personnel: Ensure that the TAB work is accomplished by a group meeting the requirements specified in paragraph entitled "TAB Personnel Qualification Requirements".
    - b. Pre-TAB meeting: Attend the meeting with the TAB Supervisor, and ensure that a representative is present for the sheet metal contractor, mechanical contractor, electrical contractor, and automatic temperature controls contractor.
    - c. HVAC documentation: Furnish one complete set of the following HVAC-related documentation to the TAB agency:
      - 1) Contract drawings and specifications
      - 2) Approved submittal data for equipment
      - 3) Construction work schedule
      - 4) Up-to-date revisions and change orders for the previously listed items
    - d. Submittal and work schedules: Ensure that the schedule for submittals and work required by this section and specified in paragraph entitled "TAB Submittal and Work Schedule," is met.
    - e. Coordination of supporting personnel:
      - 1) Provide the technical personnel, such as factory representatives or HVAC controls installer required by the TAB field team to support the TAB field measurement work.
      - 2) Provide equipment mechanics to operate HVAC equipment and ductwork mechanics to provide the field designated test ports to enable TAB field team to accomplish the TAB field measurement work. Ensure these support personnel are present at the times required by the TAB team, and cause no delay in the TAB field work.
      - 3) Conversely, ensure that the HVAC controls installer has required support from the TAB team field leader to complete the controls check out.
    - f. Deficiencies: Ensure that the TAB Agency supervisor submits all Design/Construction deficiency notifications directly to the Contracting officer within 3 days after the deficiency is encountered. Further, the Contractor shall ensure that all such notification submittals are complete with explanation, including documentation, detailing deficiencies.
    - g. Prerequisite HVAC work: Complete check out and debugging of HVAC equipment, ducts, and controls prior to the TAB engineer arriving at the project site to begin the TAB work. Debugging includes searching for and eliminating malfunctioning elements in the HVAC system installations, and verifying all adjustable devices are functioning as designed. Include as prerequisite work items, the deficiencies pointed out by the TAB team supervisor in the design review report.
    - h. Prior to the TAB field team's arrival, ensure completion of the applicable inspections and work items listed in the TAB team supervisor's pre-field engineering report. Do not allow the TAB team to commence TAB field work until all of the following are completed.
      - 1) HVAC system installations are fully complete.
      - 2) HVAC prerequisite checkout work lists specified in the paragraph "Pre-Field TAB Engineering Report" have been completed, submitted, and approved. Ensure that the TAB Agency gets a copy of the approved prerequisite HVAC work checklist.
      - 3) HVAC system filters are clean for both Season 1 and Season 2 TAB field work.
    - i. Advance notice: Furnish to the Contracting Officer with advance written notice for the commencement of the TAB field work.
  2. TAB Agency. Provide the services of a TAB team which complies with the requirements of paragraph entitled "Independent TAB Agency Personnel Qualifications". The work to be performed by the TAB agency shall be limited to testing, adjusting, and balancing of HVAC air and water systems to satisfy the requirements of this specification section.
  3. TAB Team Supervisor
    - a. Overall management: Supervise and manage the overall TAB team work effort, including preliminary and technical TAB procedures and TAB team field work.
    - b. Pre-TAB meeting: Attend meeting with Contractor.
    - c. Design review report: Review project specifications and accompanying drawings to verify that the air systems and water systems are designed in such a way that the TAB engineer can accomplish the work in compliance with the requirements of this section. Verify the presence and location of permanently installed test ports and other devices needed, including gauge cocks, thermometer wells, flow control devices, circuit setters, balancing valves, and manual volume dampers.
    - d. Support required: Specify the technical support personnel required from the Contractor other than the TAB agency; such as factory representatives for temperature controls or for complex equipment. Inform the Contractor in writing of the support personnel needed and when they are needed. Furnish

- the notice as soon as the need is anticipated, either with the design review report, or the pre-field engineering report, during the TAB field work.
- e. Pre-field engineering report: Utilizing the following HVAC-related documentation; contract drawings and specifications, approved submittal data for equipment, up-to-date revisions and change orders; prepare this report.
  - f. Prerequisite HVAC work checklist: Ensure the Contractor gets a copy of this checklist at the same time as the pre-field engineering report is submitted.
  - g. Technical Assistance for TAB Work: Provide immediate technical assistance to the TAB field team for the TAB work.
  - h. Certified TAB report: Certify the TAB report. This certification includes the following work:
    - 1) Review: Review the TAB field data report. From this field report, prepare the certified TAB report.
    - 2) Verification: Verify adherence, by the TAB field team, to the TAB plan prescribed by the pre-field engineering report and verify adherence to the procedures specified in this section.
  - i. Design/Construction deficiencies: Within 3 working days after the TAB Agency has encountered any design or construction deficiencies, the TAB Supervisor shall submit written notification directly to the Contracting Officer, with a separate copy to the Contractor, of all such deficiencies. Provide in this submittal a complete explanation, including supporting documentation, detailing deficiencies. Where deficiencies are encountered that are believed to adversely impact successful completion of TAB, the TAB Agency shall issue notice and request direction in the notification submittal.
  - j. TAB Field Check: The TAB team supervisor shall attend and supervise TAB field check.
4. TAB Team Field Leader
- a. Field manager: Manage, in the field, the accomplishment of the work specified in Part 3, "Execution."
  - b. Full time: Be present at the contract site when TAB field work is being performed by the TAB team; ensure day-to-day TAB team work accomplishments are in compliance with this section.
  - c. Prerequisite HVAC work: Do not bring the TAB team to the contract site until a copy of the prerequisite HVAC Checklist, with all work items certified by the Contractor to be working as designed, reaches the office of the TAB Agency.

D. Test Reports

- 1. Certified TAB Reports. Submit Certified TAB Report for Season 1 and Certified TAB Report for Season 2 in the following manner:
  - a. Report format: Submit the completed pre-field data forms approved in the pre-field TAB Engineering Report completed by TAB field team, reviewed and certified by the TAB supervisor. Bind the report with a waterproof front and back cover. Include a table of contents identifying by page number the location of each report. Report forms and report data shall be typewritten. Handwritten report forms or report data are not acceptable.
  - b. Temperatures: On each TAB report form reporting TAB work accomplished on HVAC thermal energy transfer equipment, include the indoor and outdoor dry bulb temperature range and indoor and outdoor wet bulb temperature range within which the TAB data was recorded.
    - 1) Data shall be measured/recorded only after the HVAC systems installations are complete, the systems fully balanced and the HVAC systems controls operating in fully automatic mode.
    - 2) Data may be compiled using direct digital controls trend logging where available. Otherwise, the Contractor shall temporarily install calibrated time versus temperature/humidity recorders for this purpose. The HVAC systems and controls shall have been fully operational a minimum of 24 hours in advance of commencing data compilation. The specified data shall be included in the TAB Report.
  - c. Static Pressure Profiles: Report static pressure data for all supply, return, relief, exhaust and outside air ducts for the systems listed. The static pressure report data shall include, in addition to NEBB/AABC required data, the following:
    - 1) Report supply fan, return fan, relief fan, and exhaust fan inlet and discharge static pressures.
    - 2) Report static pressure drop across chilled water coils, hot water coils, and electric resistance heating coils installed in unit cabinetry or the system ductwork.
    - 3) Report static pressure drop across outside air, return air, and supply air automatic control dampers, both proportional and two-position, installed in unit cabinetry, or in the system ductwork.
    - 4) Report static pressure drop across air filters, acoustic silencers, air flow measuring stations or other pressure drop producing specialty items installed in unit cabinetry, or in the system ductwork. Examples of these specialty items are smoke detectors, white sound generators, RF shielding, wave guides, security bars, blast valves, small pipes passing through ductwork, and duct mounted humidifiers.

- 5) Do not report static pressure drop across duct fittings provided for the sole purpose of conveying air, such as elbows, transitions, offsets, plenums, manual dampers, and branch takes-offs.
- 6) Report static pressure drop across outside air and relief/exhaust air louvers.
- 7) Report supply, return, exhaust/relief, outside air duct static pressure readings, including the following locations:
  - a) Main Duct: Take readings at four locations along the full length of the main duct. Locations shall be at 25 percent, 50 percent, 75 percent, and 100 percent of the total duct length.
  - b) Floor Branch Mains: Take readings at floor branch mains served by a main duct vertical riser.
  - c) Branch Main Ducts: Take readings at branch main ducts.
  - d) VAV Terminals: Take readings at inlet static pressure at VAV terminal box primary air branch ducts.
  - e) VAV Terminals, Fan Powered: Take readings at fan discharge and inlet static pressures for series and parallel fan powered VAV terminal boxes.
- d. Duct Transverses: Report duct traverses for main and branch main supply, return, exhaust, relief and outside air ducts. This shall include all ducts, including those which lack 7 1/2 duct diameters upstream and 2 1/2 duct diameters downstream of straight duct unobstructed by duct fittings/offsets/elbows. The TAB Agency shall evaluate and report findings on the duct traverses taken. Evaluate the suitability of the duct traverse measurement based on satisfying the qualifications for a pitot traverse plane as defined by AMCA 203, "Field Measurements", Section 8, paragraph 8.3, "Location of Traverse Plane".
- e. Instruments: List the types of instruments actually used to measure the tab data. Include in the listing each instrument's unique identification number, calibration date, and calibration expiration date. Instrumentation, used for taking wet bulb temperature readings shall provide accuracy of plus or minus 5 percent at the measured face velocities. Submit instrument manufacturer's literature to document instrument accuracy performance is in compliance with that specified.
- f. Certification: Include the typed name of the TAB supervisor and the dated signature of the TAB supervisor.
- g. Performance Curves: The TAB Supervisor shall include, in the Certified TAB Reports, factory pump curves and fan curves for pumps and fans TAB'd on the job.
- h. Calibration Curves: The TAB Supervisor shall include, in the Certified TAB Reports, a factory calibration curve for installed flow control balancing valves, flow venturis and flow orifices TAB'd on the job.

#### 1.7 PRE-TAB MEETING

- A. Meet with the Contracting Officer's TAB representative to develop a mutual understanding relative to the details of the TAB work requirements. Ensure that the TAB supervisor is present at this meeting. Requirements to be discussed include required submittals, work schedule, and field quality control.

#### PART 2 - PRODUCTS – NOT USED

#### PART 3 - EXECUTION

##### 3.1 TAB PROCEDURES

- A. TAB Field Work
  1. Test, adjust, and balance the listed HVAC systems to the state of operation indicated on and specified in the contract design documents. Conduct TAB work, including maintenance and calibration of instruments, measurement accuracy, and sound measurement work in conformance with the AABC MN-1 and AABC MN-4, or NEBB TABES, and NEBB MASV, except as supplemented and modified by this section. Provide instruments and consumables required to accomplish the TAB work.
  2. Air systems and water systems shall be proportionately balanced and reported in the certified TAB report.
- B. Preliminary Procedures. Use the approved pre-field engineering report as instructions and procedures for accomplishing TAB field work. Test ports required for testing by the TAB engineer shall be located in the field by the TAB engineer during TAB field work. It shall be the responsibility of the sheet metal contractor to provide and install test ports as required by the TAB engineer.



- C. TAB Air Distribution Systems
1. Air Handling Units. Air handling unit systems including fans (air handling unit fans, exhaust fans and winter ventilation fans), coils, ducts, plenums, mixing boxes, terminal units, variable air volume boxes, and air distribution devices for supply air, return air, outside air, mixed air relief air, and makeup air.
  2. Fan Coils. Fan coil unit systems including fans, coils, ducts, plenums, and air distribution devices for supply air, return air, and outside air.
  3. Return Air Fans. Return air fan system including fan ducts, plenums, registers, diffusers, grilles, and louvers for supply air, return air, outside air, and mixed air.
  4. Heating and Ventilating Units. Heating and ventilating unit systems including fans, coils, ducts, plenums, roof vents, registers, diffusers, grilles, and louvers for supply air, return air, outside air, and mixed air.
  5. Exhaust Fans. Exhaust fan systems including fans, ducts, plenums, grilles, and hoods for exhaust air.
  6. Cooling Units.
- D. TAB Water Distribution Systems
1. Chilled Water. Chilled water systems including chillers, pumps, coils, system balance valves and flow measuring devices.
- E. TAB Work on Performance Tests Without Seasonal Limitations
1. Performance Tests. In addition to the TAB proportionate balancing work on the air distribution systems and the water distribution systems, accomplish TAB work on the HVAC systems which directly transfer thermal energy. TAB the operational performance of the heating systems and cooling systems.
  2. Ambient Temperatures. On each tab report form used for recording data, record the outdoor and indoor ambient dry bulb temperature range and the outdoor and indoor ambient wet bulb temperature range within which the report form's data was recorded. That is, record these temperatures at beginning and at the end of data taking.
  3. Water Chillers. For water chillers, data as required by NEBB Form TAB 15-83, NEBB TABES shall be reported, including refrigeration operational data.
  4. Coils. Heating and cooling performance capacity tests shall be reported for heating and chilled water coils for the purpose of verifying that the coils meet the indicated design capacity. Submit the following data and calculations with the coil test reports:
    - a. For Central station air handlers with capacities greater than 7.5 tons (90,000 Btu) cooling, such as factory manufactured units, central built-up units and rooftop units, capacity tests shall be conducted in accordance with AABC MN-4, procedure 3.5, "Coil Capacity Testing".
      - 1) Entering and leaving wet and dry bulb temperatures shall not be determined by single point measurement, but shall be the average of multiple readings in compliance with paragraph 3.5-5, "Procedures", (in subparagraph d.) of AABC MN-4, Procedure 3.5, "Coil Capacity Testing".
      - 2) Submit part-load coil performance data from the coil manufacturer converting test conditions to design conditions; the data shall be used for the purpose of verifying that the coils meet the indicated design capacity in compliance with AABC MN-4, Procedure 3.5, "Coil Capacity Testing", paragraph 3.5.7, "Actual Capacity Vs. Design Capacity" (in subparagraph c.).
    - b. For units with capacities of 7.5 tons (90,000 Btu) or less, such as fan coil units, duct mounted reheat coils associated with VAV terminal units, and unitary units. The apparent coil capacity shall be determined by calculations using single point measurement of entering and leaving wet and dry bulb temperatures; the calculations shall be submitted with the coil reports.
- F. TAB Work on Performance Tests With Seasonal Limitations
1. Performance Tests. Accomplish proportionate balancing TAB work on the air distribution systems and water distribution systems, in other words, accomplish adjusting and balancing of the air flows and water flows, any time during the duration of this contract, subject to the limitations specified elsewhere in this section. However, accomplish, within the following seasonal limitations, TAB work on HVAC systems which directly transfer thermal energy.
  2. Season of Maximum Load. Visit the contract site for at least two TAB work sessions for TAB field measurements. Visit the contract site during the season of maximum heating load and visit the contract site during the season of maximum cooling load, the goal being to TAB the operational performance of the heating systems and cooling systems under their respective maximum outdoor environment-caused loading. During the seasonal limitations, TAB the operational performance of the heating systems and cooling systems.
  3. Ambient Temperatures. On each tab report form used for recording data, record the outdoor and indoor ambient dry bulb temperature range and the outdoor and indoor ambient wet bulb temperature range within which the report form's data was recorded. That is, record these temperatures at beginning and at the end of data taking.

4. Air Cooled Chillers. For air cooled chillers, data as required by NEBB Form TAB 15-83, NEBB TABES shall be reported, including refrigeration operational data.
5. Coils. Heating and cooling performance capacity tests shall be reported for heating and chilled water coils for the purpose of verifying that the coils meet the indicated design capacity. Submit the following data and calculations with the coil test reports:
  - a. For Central station air handlers with capacities greater than 7.5 tons (90,000 Btu) cooling, such as factory manufactured units, central built-up units and rooftop units, capacity tests shall be conducted in accordance with AABC MN-4, procedure 3.5, "Coil Capacity Testing".
    - 1) Entering and leaving wet and dry bulb temperatures shall not be determined by single point measurement, but shall be the average of multiple readings in compliance with paragraph 3.5-5, "Procedures", (in subparagraph d.) of AABC MN-4, Procedure 3.5, "Coil Capacity Testing".
    - 2) Submit part-load coil performance data from the coil manufacturer converting test conditions to design conditions; the data shall be used for the purpose of verifying that the coils meet the indicated design capacity in compliance with AABC MN-4, Procedure 3.5, "Coil Capacity Testing," paragraph 3.5.7, "Actual Capacity Vs. Design Capacity" (in subparagraph c.).
  - b. For units with capacities of 7.5 tons (90,000 Btu) or less, such as fan coil units, duct mounted reheat coils associated with VAV terminal units, and unitary units, such as through-the-wall heat pumps:
    - 1) The apparent coil capacity shall be determined by calculations using single point measurement of entering and leaving wet and dry bulb temperatures; the calculations shall be submitted with the coil reports.
- G. Workmanship. Conduct TAB work on specified HVAC systems until measured parameters are within plus or minus 10 percent of the design values, that is, the values specified or indicated on the contract documents.
- H. Deficiencies.
  1. Strive to meet the intent of this section to maximize the performance of the equipment as designed and installed. However, if deficiencies in equipment design or installation prevent TAB work from being accomplished within the range of design values specified in the paragraph entitled "Workmanship", provide written notice as soon as possible to the Contractor and the Contracting Officer describing the deficiency and recommended correction.
  2. Responsibility for correction of installation deficiencies is the Contractor's. If a deficiency is in equipment design, call the TAB team supervisor for technical assistance. Responsibility for reporting design deficiencies to Contractor is the TAB team supervisor's.
- I. Data From TAB Field Work
  1. After completion of the TAB field work, prepare the TAB field data for TAB supervisor's review and certification, using the reporting forms approved in the pre-field engineering report. Data required by those approved data report forms shall be furnished by the TAB team. Except as approved otherwise in writing by the Contracting Officer, the TAB work and thereby the TAB report shall be considered incomplete until the TAB work is accomplished to within the accuracy range specified in the paragraph entitled "Workmanship".
  2. After completion of the TAB work, prepare a pre-final TAB report using the reporting forms approved in the pre-field engineering report. Data required by those approved data report forms shall be furnished by the TAB team. Except as approved otherwise in writing by the Contracting Officer, the TAB work and the TAB report shall be considered incomplete until the TAB work is accomplished to within the accuracy range specified in the paragraph entitled "Workmanship" of this Section.
  3. Prepare the report neatly and legibly; the pre-final TAB report shall be the final TAB report minus the TAB supervisor's review and certification. Obtain, at the contract site, the TAB supervisor's review and certification of the TAB report.
  4. Verbally notify the Contracting Officer's TAB representative that the field check of the Certified TAB report data can commence; give this verbal notice 48 hours in advance of when the field checking shall commence. Do not schedule field check of the Certified TAB report until the specified workmanship requirements have been met or written approval of the deviations from the requirements have been received from the Contracting Officer.
- J. Quality Assurance - Contracting Officer TAB Field Checks
  1. Field Check.
    - a. During field check, the Contractor shall check, in the presence of the Contracting Officer's TAB representative, random selections of data (water, air quantities, air motion, sound level readings) recorded in the Certified TAB Report. Points and areas of field checks shall be selected by the

Contracting Officer's TAB representative. Measurement and test procedures shall be the same as approved for TAB work for the Certified TAB Report.

- b. Selections for recheck will not exceed 25 percent of the total number of reported data entries tabulated in the report.
- 2. Additional Field Checks
  - a. If any of the data checked for a given HVAC field check group are determined to be out-of-tolerance, data checking for all affected data for that group shall be terminated and the affected TAB report data for the given group shall be disapproved. The Contractor shall make the necessary corrections and prepare a revised Certified TAB Report. A field check of the revised report data shall then be rescheduled with the Contracting Officer's TAB representative.
  - b. Further, if any data on the Certified TAB Report for a given field check group is out-of-tolerance, then data for one additional field check group shall be field checked as specified herein. This increase field check work shall continue until out-of-tolerance data ceases to be found. This additional field checking is up and above the original 25 percent of the reported data entries to be field checked.
  - c. If there are no more of the similar field check group, additional field checking from another, but different, type of field check group shall be checked.
- 3. Prerequisite for Approval. Compliance with the field checking requirements of this section is a prerequisite for the final Contracting Officer approval of the certified TAB report submitted.

### 3.2 MARKING OF SETTINGS

- A. Upon the final TAB work approval, permanently mark the settings of HVAC adjustment devices including valves, splitters, and dampers so that adjustment can be restored if disturbed at any time. The permanent markings shall indicate the settings on the adjustment devices which result in the data reported on the submitted certified TAB report.

### 3.3 MARKING OF TEST PORTS

- A. The TAB team shall permanently and legibly mark and identify the location points of the duct test ports. If the ducts have exterior insulation, these markings shall be made on the exterior side of the duct insulation. The location of test ports shall be shown on the as-built mechanical drawings with dimensions given where the test port is covered by exterior insulation.

END OF SECTION 15950



This page is intended to be blank.

## SECTION 15995 - COMMISSIONING OF HVAC SYSTEMS

### PART 1 - GENERAL

#### 1.1 SUBMITTALS

- A. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES.
- B. Product Data
  - 1. Commissioning Team. List of team members who will represent the Contractor in the pre-commissioning checks and functional performance testing, at least 2 weeks prior to the start of pre-commissioning checks. Proposed revision to the list, prior to the start of the impacted work.
  - 2. Tests. Detailed procedures for pre-commissioning checks and functional performance tests, at least 4 weeks prior to the start of pre-commissioning checks.
  - 3. Pre-Commissioning Checks. Schedule for pre-commissioning checks and functional performance tests, at least 2 weeks prior to the start of pre-commissioning checks.
- C. Test Reports. Completed pre-commissioning checklists and functional performance test checklists organized by system and by subsystem and submitted as one package. The results of failed tests shall be included along with a description of the corrective action taken.

#### 1.2 SEQUENCING AND SCHEDULING

- A. The work described in this Section shall begin only after all work required in related Sections, including Section 15910 DIRECT DIGITAL CONTROL SYSTEMS and Section 15950 TESTING/ADJUSTING/BALANCING, has been successfully completed, and all test and inspection reports and operation and maintenance manuals required in these Sections have been submitted and approved.

### PART 2 - PRODUCTS – NOT USED

### PART 3 - EXECUTION

#### 3.1 COMMISSIONING TEAM AND CHECKLISTS

- A. The Contractor shall designate team members to participate in the pre-commissioning checks and the functional performance testing specified herein. In addition, the Government will be represented by a representative of the Contracting Officer, the Design Agent's Representative, and the Using Agency. The team members shall be as follows:

Designation	Function
Q	Contractor's Chief Quality Control Representative
M	Contractor's Mechanical Representative
E	Contractor's Electrical Representative
T	Contractor's Testing, Adjusting, and Balancing Representative
C	Contractor's Controls Representative
D	Design Agent's Representative
O	Resident Engineer/Project Engineer
U	Using Agency's Representative

- B. Appendices A and B are provided as a general checklist and have been prepared to best match the various equipment selected during the design of this project. Each checklist shown in Appendices A and B shall be reviewed and modified as necessary to reflect equipment actually installed during construction of the project. The commissioning team shall review the accuracy and applicability of each item in the checklist and revise as needed. Equipment shown in the checklist but not installed for the project shall be annotated as "NA". Likewise, equipment installed but not listed in the checklist shall be added or revised accordingly. A note as to why it was added or revised shall be inserted with the reviewer's initial. The commissioning team shall also add or modify to any of the equipment checklist items as required and/or specified by the equipment manufacturer. Acceptance by each commissioning team member of each pre-commissioning checklist item shall be indicated by initials and date, unless an "X" is

shown indicating that participation by that individual is not required. Acceptance by each commissioning team member of each functional performance test checklist shall be indicated by signature and date.

### 3.2 TESTS

- A. The pre-commissioning checks and functional performance tests shall be performed in a manner which essentially duplicates the checking, testing, and inspection methods established in the related Sections. Where checking, testing, and inspection methods are not specified in other Sections, methods shall be established which will provide the information required. Testing and verification required by this section shall be performed during the Commissioning phase. Requirements in related Sections are independent from the requirements of this Section and shall not be used to satisfy any of the requirements specified in this Section. The Contractor shall provide all materials, services, and labor required to perform the pre-commissioning checks and functional performance tests. A pre-commissioning check or functional performance test shall be aborted if any system deficiency prevents the successful completion of the test or if any participating non-Government commissioning team member of which participation is specified is not present for the test. The Contractor shall reimburse the Government for all costs associated with effort lost due to tests that are aborted. These costs shall include salary, travel costs and per diem (where applicable) for Government commissioning team members. The Contractor shall submit Test Reports as specified in the Submittals paragraph.
- B. Pre-Commissioning Checks. Pre-commissioning checks shall be performed for the items indicated on the checklists in Appendix A. Deficiencies discovered during these checks shall be corrected and retested in accordance with the applicable contract requirements.
- C. Functional Performance Tests. Functional performance tests shall be performed for the items indicated on the checklists in Appendix B. Functional performance tests shall begin only after all pre-commissioning checks have been successfully completed. Tests shall prove all modes of the sequences of operation, and shall verify all other relevant contract requirements. Tests shall begin with equipment or components and shall progress through subsystems to complete systems. Upon failure of any functional performance test checklist item, the Contractor shall correct all deficiencies in accordance with the applicable contract requirements. The checklist shall then be repeated until it has been completed with no errors.



APPENDIX A

PRE-COMMISSIONING CHECKLISTS

Pre-commissioning checklist - Piping

For [\_\_\_\_\_] Piping System

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Piping complete.	___	___	X	___	X	___	___	___
b. As-built shop drawings submitted.	___	___	X	___	X	___	___	___
c. Piping flushed and cleaned.	___	___	X	___	X	___	___	___
d. Strainers cleaned.	___	___	X	___	X	___	___	___
e. Valves installed as required.	___	___	X	___	X	___	___	___
f. Piping insulated as required.	___	___	X	___	X	___	___	___
g. Thermometers and gauges installed as required.	___	___	X	___	X	___	___	___
h. Verify operation of valves.	___	___	X	___	___	___	___	___
i. Air vents installed as specified.	___	___	X	X	X	___	___	___
j. Flexible connectors installed as specified	___	___	X	X	X	___	___	___
k. Verify that piping has been labeled and valves identified as specified.	___	___	X	___	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. Hydrostatic test complete.	___	___	X	___	X	___	___	___
b. TAB operation complete.	___	___	X	___	___	___	___	___

Pre-commissioning Checklist - Ductwork

For Air Handler: [\_\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Ductwork complete.	___	___	X	___	X	___	___	___
b. As-built shop drawings submitted.	___	___	X	___	X	___	___	___
c. Ductwork leak test complete.	___	___	X	___	X	___	___	___
d. Fire dampers, smoke dampers, and access doors installed as required with installation of each verified by the specified team members initialing each location on a copy of the as-built drawings.	___	___	X	___	X	___	___	___
e. Ductwork insulated as required.	___	___	X	___	X	___	___	___
f. Thermometers and gauges installed as required.	___	___	___	___	___	___	___	___
g. Verify open/closed status of dampers.	___	___	X	___	X	___	___	___
h. Verify smoke and fire damper operation.	___	___	X	___	___	___	___	___
i. Flexible connectors installed as specified	___	___	X	___	X	___	___	___
j. Seismic Restraints Installed.	___	___	X	___	___	X	___	___
Testing, Adjusting, and Balancing (TAB)								
a. TAB operation complete.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Variable Volume Air Handling Unit

For Air Handling Unit: [\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Vibration isolation devices installed.	___	___	X	X	X	___	___	___
b. Inspection and access doors are operable and sealed.	___	___	X	___	X	___	___	___
c. Casing undamaged.	___	___	X	X	X	___	___	___
d. Insulation undamaged.	___	___	X	X	X	___	___	___
e. Condensate drainage is unobstructed. (Visually verify drainage by pouring a cup of water into drain pan.)	___	___	X	X	X	___	___	___
f. Fan belt adjusted.	___	___	X	___	X	___	___	___
g. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to unit disconnect.	___	___	___	X	X	___	___	___
b. Power available to unit control panel.	___	___	___	X	___	___	___	___
c. Proper motor rotation verified.	___	___	___	___	X	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
e. Power available to electric heating coil.	___	___	___	X	X	___	___	___
Coils								
a. Chilled water piping properly connected.	___	___	X	X	X	___	___	___
b. Chilled water piping pressure tested.	___	___	X	X	X	___	___	___
d. Air vents installed on water coils with shutoff valves as specified.	___	___	X	X	X	___	___	___
e. Any damage to coil fins has been repaired.	___	___	X	___	X	___	___	___

Controls

a. Automatic control valves/actuators properly installed.	___	___	X	___	___	___	___	___
b. Automatic control valves/actuators operable.	___	___	X	___	___	___	___	___
c. Dampers/actuators properly installed.	___	___	X	___	___	___	___	___
d. Dampers/actuators operable.	___	___	X	___	___	___	___	___
e. Verify proper location, installation and calibration of duct static pressure sensor.	___	___	X	___	___	___	___	___
f. Fan air volume controller operable.	___	___	X	___	___	___	___	___
g. Air handler controls system operational.	___	___	X	___	___	___	___	___

Testing, Adjusting, and Balancing (TAB)

a. Construction filters removed and replaced.	___	___	X	___	___	___	___	___
b. TAB report submitted.	___	___	X	___	X	___	___	___
c. TAB results within limits specified in Section 15950								
d. TAB results for outside air intake within limits specified in Section 15950	___	___	X	___	X	___	___	___



Pre-commissioning Checklist - VAV Terminal

For VAV Terminal: [\_\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. VAV terminal in place.	___	___	X	X	X	___	___	___
b. VAV terminal ducted.	___	___	X	X	X	___	___	___
c. VAV terminal connected to controls.	___	___	X	X	___	___	___	___
e. Electric reheat coil connected to local disconnect.	___	___	___	___	X	___	___	___
f. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
Controls								
a. Cooling only VAV terminal controls set.	___	___	X	X	___	___	___	___
b. Cooling only VAV controls verified.	___	___	X	X	___	___	___	___
c. Reheat VAV terminal controls set.	___	___	X	X	___	___	___	___
d. Reheat terminal/coil controls verified.	___	___	X	X	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. Verify terminal maximum air flow set.	___	___	X	___	___	___	___	___
b. Verify terminal minimum air flow set.	___	___	X	___	___	___	___	___
c. TAB operation complete.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Pumps

For Pump: [\_\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Pumps grouted in place.	___	___	X	X	X	___	___	___
b. Pump vibration isolation devices functional.	___	___	X	X	X	___	___	___
c. Pump/motor coupling alignment verified.	___	___	X	X	X	___	___	___
d. Piping system installed.	___	___	X	X	X	___	___	___
e. Piping system pressure tested.	___	___	X	X	X	___	___	___
f. Pump not leaking.	___	___	X	X	X	___	___	___
g. Field assembled couplings aligned to meet manufacturer's prescribed tolerances.	___	___	X	X	X	___	___	___
Electrical								
a. Power available to pump disconnect.	___	___	___	X	X	___	___	___
b. Pump rotation verified.	___	___	___	X	X	___	___	___
c. Control system interlocks functional.	___	___	___	X	___	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. Pressure/temperature gauges installed.	___	___	X	___	X	___	___	___
b. Piping system cleaned.	___	___	X	X	X	___	___	___
c. Chemical water treatment complete.	___	___	X	X	X	___	___	___
d. Water balance complete.	___	___	X	___	X	___	___	___
e. Water balance with design maximum flow.	___	___	X	___	X	___	___	___
f. TAB Report submitted.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Packaged Air Cooled Chiller

For Chiller: [\_\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
<b>Installation</b>								
a. Chiller properly piped.	___	___	X	___	___	___	___	___
b. Chilled water pipe leak tested.	___	___	X	X	X	___	___	___
c. Verify that refrigerant used complies with specified requirements.	___	___	X	X	X	___	___	___
d. Any damage to coil fins has been repaired.	___	___	X	___	X	___	___	___
e. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
f. Low ambient kit installed.	___	___	X	X	X	___	___	___
g. Copper tubes and copper fins installed.	___	___	X	X	X	___	___	___
<b>Electrical</b>								
a. Power available to unit disconnect.	___	___	___	X	___	___	___	___
b. Power available to unit control panel.	___	___	___	X	___	___	___	___
c. Separate power is supplied to electric heating tape.	___	___	___	X	___	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
<b>Controls</b>								
a. Factory startup and checkout complete.	___	___	X	X	___	___	___	___
b. Chiller safety/protection devices tested.	___	___	X	X	___	___	___	___
c. Chilled water flow switch installed.	___	___	X	X	___	___	___	___
d. Chilled water flow switch tested.	___	___	X	X	___	___	___	___
e. Chilled water pump interlock installed.	___	___	X	X	X	___	___	___
f. Chilled water pump interlock tested.	___	___	___	X	___	___	___	___

Pre-commissioning Checklist - Fan Coil Unit

For Fan Coil Unit: [\_\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
<b>Installation</b>								
a. Vibration isolation devices installed.	___	___	X	X	X	___	___	___
b. Access doors/removable panels are operable and sealed.	___	___	X	___	X	___	___	___
c. Casing undamaged.	___	___	X	X	X	___	___	___
d. Insulation undamaged.	___	___	X	X	X	___	___	___
e. Condensate drainage is unobstructed.	___	___	X	X	X	___	___	___
f. Fan belt adjusted.	___	___	X	___	X	___	___	___
g. Any damage to coil fins has been repaired.	___	___	X	___	X	___	___	___
h. Manufacturer's required maintenance clearance provided.	___	___	X	X	X	___	___	___
<b>Electrical</b>								
a. Power available to unit disconnect.	___	___	___	X	___	___	___	___
b. Power available to unit control panel.	___	___	___	X	___	___	___	___
c. Proper motor rotation verified.	___	___	___	___	X	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
e. Power available to electric heating coil.	___	___	___	X	X	___	___	___
<b>Coils</b>								
a. Chilled water piping properly connected.	___	___	X	X	X	___	___	___
b. Chilled water piping pressure tested.	___	___	X	X	X	___	___	___
<b>Controls</b>								
a. Control valves/actuators properly installed.	___	___	X	___	___	___	___	___
b. Control valves/actuators operable.	___	___	X	X	___	___	___	___
c. Verify proper location and installation of thermostat.	___	___	X	___	___	___	___	___



Testing, Adjusting, and Balancing (TAB)

- a. Construction filters removed and replaced. ☐ ☐ ☒ ☐ ☐ ☐ ☐ ☐
- b. TAB results within limits specified in  
Section 15990A
- c. TAB Report submitted. ☐ ☐ ☒ ☐ ☒ ☐ ☐ ☐

Pre-commissioning Checklist - Exhaust Fan

For Exhaust Fan: [\_\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Fan belt adjusted.	___	___	X	___	X	___	___	___
Electrical								
a. Power available to fan disconnect.	___	___	___	X	___	___	___	___
b. Proper motor rotation verified.	___	___	___	___	X	___	___	___
c. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
Controls								
a. Control interlocks properly installed.	___	___	___	X	___	___	___	___
b. Control interlocks operable.	___	___	___	X	___	___	___	___
c. Dampers/actuators properly installed.	___	___	X	___	___	___	___	___
d. Dampers/actuators operable.	___	___	X	___	___	___	___	___
e. Verify proper location and installation of thermostat.	___	___	X	___	___	___	___	___
Testing, Adjusting, and Balancing (TAB)								
a. TAB results within limits specified in Section 15990A	___	___	X	___	X	___	___	___
b. TAB Report submitted.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Computer Room Unit

For Computer Room Unit: [\_\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Unit properly supported.	___	___	X	X	X	___	___	___
b. Access doors are operable and sealed.	___	___	X	___	X	___	___	___
c. Casing undamaged.	___	___	X	X	X	___	___	___
d. Insulation undamaged.	___	___	X	X	X	___	___	___
e. Condensate drainage is unobstructed and routed to floor drain.	___	___	X	X	X	___	___	___
f. Fan belt adjusted.	___	___	X	___	X	___	___	___
g. Manufacturer's required maintenance operational clearance provided.	___	___	X	X	X	___	___	___
h. Drain pipe installed.	___	___	X	X	X	___	___	___

Electrical

a. Power available to unit disconnect.	___	___	___	X	X	___	___	___
b. Proper motor rotation verified.	___	___	___	___	X	___	___	___
c. Proper motor rotation verified.	___	___	___	___	X	___	___	___
d. Verify that power disconnect is located within sight of the unit it controls.	___	___	___	X	___	___	___	___
e. Power available to reheat coils.	___	___	___	___	X	___	___	___

Coils/Humidifier

a. Chilled water piping properly connected.	___	___	X	___	___	___	___	___
b. Chilled water piping pressure tested.	___	___	X	X	X	___	___	___
c. Humidifier makeup water connected.	___	___	X	X	X	___	___	___

Controls

a. Control valves operable.	___	___	X	X	___	___	___	___
b. Unit control system operable and verified.	___	___	___	X	___	___	___	___

c. Verify proper location and installation of  
thermostat and humidistat.      ☐ ☐ X ☐ ☐ ☐ ☐ ☐

Testing, Adjusting, and Balancing (TAB)

a. Construction filters removed and replaced. ☐ ☐ X ☐ X ☐ ☐ ☐

b. TAB results within limits specified in  
Section 15950      ☐ ☐ X ☐ X ☐ ☐ ☐

c. TAB Report submitted.      ☐ ☐ X ☐ X ☐ ☐ ☐



Pre-commissioning Checklist - HVAC System Controls

For HVAC System: [\_\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. As-built shop drawings submitted.	___	___	X	X	___	___	___	___
b. Layout of control panel matches drawings.	___	___	X	X	___	___	___	___
c. Framed instructions mounted in or near control panel.	___	___	X	X	___	___	___	___
d. Components properly labeled (on inside and outside of panel).	___	___	X	X	___	___	___	___
e. Control components piped and/or wired to each labeled terminal strip.	___	___	X	X	___	___	___	___
f. EMCS connection made to each labeled terminal strip as shown.	___	___	X	X	___	___	___	___
g. Control wiring and tubing labeled at all terminations, splices, and junctions.	___	___	X	X	___	___	___	___
h. Shielded wiring used on electronic sensors.	___	___	X	X	___	___	___	___
Main Power and Control Air								
a. 110 volt AC power available to panel.	___	___	___	X	___	___	___	___
Testing, Commissioning, and Balancing								
a. Testing, Commissioning, and Balancing Report submitted.	___	___	X	___	___	___	___	___

Pre-commissioning Checklist - Single Zone Air Handling Unit

For Air Handling Unit: [\_\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
Installation								
a. Vibration isolation devices installed.	__	__	X	X	X	__	__	__
b. Inspection and access doors are operable and sealed.	__	__	X	__	X	__	__	__
c. Casing undamaged.	__	__	X	X	X	__	__	__
d. Insulation undamaged.	__	__	X	X	X	__	__	__
e. Condensate drainage is unobstructed.	__	__	X	X	X	__	__	__
f. Fan belt adjusted.	__	__	X	__	X	__	__	__
g. Any damage to coil fins has been repaired.	__	__	X	__	X	__	__	__
h. Manufacturer's required maintenance clearance provided.	__	__	X	X	X	__	__	__
i. Seismic restraints installed.	__	__	X	X	X	__	__	__

Electrical

a. Power available to unit disconnect.	__	__	__	X	X	__	__	__
b. Power available to unit control panel.	__	__	__	X	__	__	__	__
c. Proper motor rotation verified.	__	__	__	__	X	__	__	__
d. Verify that power disconnect is located within sight of the unit it controls.	__	__	__	X	__	__	__	__
e. Power available to electric heating coil.	__	__	__	X	__	__	__	__

Coils

a. Chilled water piping properly connected.	__	__	X	__	__	__	__	__
b. Chilled water piping pressure tested.	__	__	X	X	X	__	__	__
e. Air vents installed on water coils [with shutoff valves] as specified.	__	__	X	X	X	__	__	__
f. Any damage to coil fins has been repaired.	__	__	X	__	__	__	__	__

Controls

a. Control valves/actuators properly installed.	___	___	X	___	___	___	___	___
b. Control valves/actuators operable.	___	___	X	___	___	___	___	___
c. Dampers/actuators properly installed.	___	___	X	___	___	___	___	___
d. Dampers/actuators operable.	___	___	X	___	___	___	___	___
e. Verify proper location and installation of thermostat.	___	___	X	___	___	___	___	___

Testing, Adjusting, and Balancing (TAB)

a. Construction filters removed and replaced.	___	___	X	___	X	___	___	___
b. TAB results within limits specified in Section 15950	___	___	X	___	X	___	___	___
c. TAB Report submitted.	___	___	X	___	X	___	___	___

Pre-commissioning Checklist - Energy Recovery Unit

For Energy Recovery Unit: [\_\_\_\_\_]

Checklist Item	Q	M	E	T	C	D	O	U
<b>Installation</b>								
a. Seismic restraints installed.	__	__	X	X	X	__	__	__
b. Inspection and access doors are operable and sealed.	__	__	X	__	X	__	__	__
c. Casing undamaged.	__	__	X	X	X	__	__	__
d. Insulation undamaged.	__	__	X	X	X	__	__	__
e. Condensate drainage is unobstructed.	__	__	X	X	X	__	__	__
f. Fan belts adjusted.	__	__	X	__	X	__	__	__
g. No damage to heat exchanger plates.	__	__	X	__	X	__	__	__
h. Manufacturer's required maintenance clearance provided.	__	__	X	X	X	__	__	__
<b>Electrical</b>								
a. Power available to unit disconnect.	__	__	__	X	X	__	__	__
b. Power available to unit control panel.	__	__	__	X	__	__	__	__
c. Proper motor rotation verified.	__	__	__	__	X	__	__	__
d. Verify that power disconnect is located within sight of the unit it controls.	__	__	__	X	__	__	__	__
e. Power available to outside air fan.	__	__	__	X	__	__	__	__
f. Power available to exhaust fan.	__	__	__	X	__	__	__	__
<b>Controls</b>								
a. Dampers/actuators properly installed.	__	__	X	__	__	__	__	__
b. Dampers/actuators operable.	__	__	X	__	__	__	__	__
<b>Testing, Adjusting, and Balancing (TAB)</b>								
a. Construction filters removed and replaced.	__	__	X	__	X	__	__	__
b. TAB results within limits specified in Section 15950	__	__	X	__	X	__	__	__
c. TAB Report submitted.	__	__	X	__	X	__	__	__



APPENDIX B

FUNCTIONAL PERFORMANCE TESTS CHECKLISTS

Functional Performance Test Checklist - Pumps

For Pump: [\_\_\_\_\_]

Prior to performing this checklist, ensure that for closed loop systems, system is pressurized and the make-up water system is operational or, for open loop systems, that the sumps are filled to the proper level.

1. Activate pump start using control system commands (all possible combination, on/auto, etc.). ON \_\_\_\_\_ AUTO \_\_\_\_\_ OFF \_\_\_\_\_

a. Verify pressure drop across strainer:

Strainer inlet pressure \_\_\_\_\_ psig  
Strainer outlet pressure \_\_\_\_\_ psig

b. Verify pump inlet/outlet pressure reading, compare to Testing, Adjusting, and Balancing (TAB) Report, pump design conditions, and pump manufacturer's performance.

	DESIGN	SYSTEM TEST	ACTUAL
Pump inlet pressure (psig)	_____	_____	_____
Pump outlet pressure (psig)	_____	_____	_____

c. Operate pump at shutoff and at 100 percent of designed flow when all components are in full flow. Plot test readings on pump curve and compare results against readings taken from flow measuring devices.

	SHUTOFF	100 percent	INCHES
Pump inlet pressure (psig)	_____	_____	
Pump outlet pressure	_____	_____	
Pump flow rate (gpm)	_____	_____	
Pump impeller (size)			_____

d. Operate pump at shutoff and at minimum flow or when all components are in full by-pass. Plot test readings on pump curve and compare results against readings taken from flow measuring devices.

	SHUTOFF	100 percent
Pump inlet pressure (psig)	_____	_____
Pump outlet pressure	_____	_____
Pump flow rate (gpm)	_____	_____

2. Verify motor amperage each phase and voltage phase to phase and phase to ground for both the full flow and the minimum flow conditions.

a. Full flow:

	PHASE 1	PHASE 2	PHASE 3
Amperage	_____	_____	_____
Voltage	_____	_____	_____
Voltage	_____	_____	_____
Voltage to ground	_____	_____	_____

b. Minimum flow:

	PHASE 1	PHASE 2	PHASE 3
Amperage	_____	_____	_____
Voltage	_____	_____	_____
Voltage	_____	_____	_____
Voltage to ground	_____	_____	_____

3. Unusual vibration, noise, etc.

\_\_\_\_\_

\_\_\_\_\_

4. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

\_\_\_\_\_

Contractor's Mechanical Representative

\_\_\_\_\_

Contractor's Electrical Representative

\_\_\_\_\_

Contractor's Testing, Adjusting and Balancing Representative

\_\_\_\_\_

Contractor's Controls Representative

\_\_\_\_\_

Resident Engineer

\_\_\_\_\_

Using Agency's Representative

\_\_\_\_\_

Functional Performance Test Checklist - VAV Terminals

The Contracting officer will select VAV terminals to be spot-checked during the functional performance test. The number of terminals shall not exceed [2] [10] [10 percent].

1. Functional Performance Test: Contractor shall demonstrate operation of selected VAV boxes as per specifications including the following:

a. Cooling only VAV boxes:

(1) Verify VAV box response to room temperature set point adjustment. Turn thermostat to 5 degrees F above ambient and measure maximum air flow. Turn thermostat to 5 degrees F below ambient and measure minimum air flow.

Maximum flow [\_\_\_\_\_] cfm  
Minimum flow [\_\_\_\_\_] cfm

(2) Check damper maximum/minimum flow settings.

Maximum flow setting [\_\_\_\_\_] cfm  
Minimum flow setting [\_\_\_\_\_] cfm

b. Cooling with reheat VAV boxes:

(1) Verify VAV box response to room temperature set point adjustment. Turn thermostat to 5 degrees F above ambient and measure maximum air flow. Turn thermostat to 5 degrees F below ambient and measure minimum air flow.

Maximum flow [\_\_\_\_\_] cfm  
Minimum flow [\_\_\_\_\_] cfm

(2) Check damper maximum/minimum flow settings.

Maximum flow setting [\_\_\_\_\_] cfm  
Minimum flow setting [\_\_\_\_\_] cfm

Reheat coil operation range (full open to full closed) \_\_\_\_\_

c. Fan powered VAV boxes:

(1) Verify VAV box response to sensor call for heating via set point adjustment. Changes to be cooling setpoint to heating set point and return to cooling set point. \_\_\_\_\_ Verify cooling damper closes to minimum position, blower fan energizes according to sequence of operation, and upon further drop in space temperature, heating coil activation and deactivation.  
\_\_\_\_\_

(2) Check primary air damper maximum/minimum flow settings.

Maximum flow setting [\_\_\_\_\_] cfm  
Minimum flow setting [\_\_\_\_\_] cfm

(3) Check blower fan flow. [\_\_\_\_\_] cfm

(4) Verify free operation of fan backdraft damper (insure no primary air is being discharged through the recirculated air register).  
\_\_\_\_\_

(5) Verify that no recirculated air is being induced when box is in full cooling. \_\_\_\_\_

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

---

Contractor's Mechanical Representative

---

Contractor's Electrical Representative

---

Contractor's Testing, Adjusting and Balancing Representative

---

Contractor's Controls Representative

---

Resident Engineer

---

Using Agency's Representative

---



Functional Performance Test Checklist - Variable Volume Air Handling Unit

For Air Handling Unit: [\_\_\_\_\_]

Ensure that a slight negative pressure exists on inboard side of the outside air dampers throughout the operation of the dampers. Modulate OA, RA, and EA dampers from fully open to fully closed positions.

1. Functional Performance Test: Contractor shall verify operation of air handling unit as per specification including the following:

a. The following shall be verified when the [supply fan operating] [supply and return fans operating] mode is initiated:

(1) All dampers in normal position [and fan inlet vanes modulate to maintain the required static pressure]. \_\_\_\_\_

(2) All valves in normal position. \_\_\_\_\_

(3) System safeties allow start if safety conditions are met. \_\_\_\_\_

(4) VAV fan controller shall "soft-start" fan. \_\_\_\_\_

(5) Modulate all VAV boxes to minimum air flow and verify that the static pressure does not exceed the design static pressure Class shown.

---

b. Occupied mode of operation - economizer de-energized.

(1) Outside air damper at minimum position. \_\_\_\_\_

(2) Return air damper open. \_\_\_\_\_

(3) Relief air damper [at minimum position] [closed]. \_\_\_\_\_

(4) Chilled water control valve modulating to maintain leaving air temperature set point. \_\_\_\_\_

(5) Fan VAV controller receiving signal from duct static pressure sensor and modulating fan to maintain supply duct static pressure set point.

---

c. Occupied mode of operation - economizer energized.

(1) Outside air damper modulated to maintain mixed air temperature set point. \_\_\_\_\_

(2) Relief air damper modulates with outside air damper according to sequence of operation. \_\_\_\_\_

(3) Chilled water control valve modulating to maintain leaving air temperature set point. \_\_\_\_\_

(4) Fan VAV controller receiving signal from duct static pressure sensor and modulating fan to maintain supply duct static pressure set point.

---

d. Unoccupied mode of operation

(1) All dampers in normal position. \_\_\_\_\_

(2) Verify low limit space temperature is maintained as specified in sequence of operation. \_\_\_\_\_

e. The following shall be verified when the [supply fan off] [supply and return fans off] mode is initiated:

(1) All dampers in normal position. \_\_\_\_\_

(2) All valves in normal position. \_\_\_\_\_

(3) Fan de-energizes. \_\_\_\_\_

f. Verify the chilled water coil control valve operation by setting all VAV's to maximum and minimum cooling.

	Max cooling	Min cooling
Supply air volume _____ cfm)	_____	_____
Supply air temp. (_____ degrees F)	_____	_____

g. Verify safety shut down initiated by smoke detectors. \_\_\_\_\_

h. Verify safety shut down initiated by low temperature protection thermostat. \_\_\_\_\_

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative \_\_\_\_\_

Contractor's Mechanical Representative \_\_\_\_\_

Contractor's Electrical Representative \_\_\_\_\_

Contractor's Testing, Adjusting and Balancing Representative \_\_\_\_\_

Contractor's Controls Representative \_\_\_\_\_

Resident Engineer \_\_\_\_\_

Using Agency's Representative \_\_\_\_\_

Functional Performance Test Checklist - Single Zone Air Handling Unit

For Air Handling Unit: [\_\_\_\_\_]

1. Functional Performance Test: Contractor shall verify operation of air handling unit as per specification including the following:

a. The following shall be verified when the supply and return fan operating mode is initiated:

- (1) All dampers in normal position. \_\_\_\_\_
- (2) All valves in normal position. \_\_\_\_\_
- (3) System safeties allow start if safety conditions are met. \_\_\_\_\_

b. Occupied mode of operation - economizer de-energized.

- (1) Outside air damper at minimum position. \_\_\_\_\_
- (2) Return air damper open. \_\_\_\_\_
- (3) Relief air damper [at minimum position] [closed]. \_\_\_\_\_
- (4) Chilled water control valve modulating to maintain space cooling temperature set point. \_\_\_\_\_

c. Occupied mode of operation - economizer energized.

- (1) Outside air damper modulated to maintain mixed air temperature set point. \_\_\_\_\_
- (2) Relief air damper modulates with outside air damper according to sequence of operation. \_\_\_\_\_
- (3) Chilled water control valve modulating to maintain space cooling temperature set point. \_\_\_\_\_

d. Unoccupied mode of operation

- (1) All dampers in normal position. \_\_\_\_\_
- (2) Verify low limit space temperature is maintained as specified in sequence of operation. \_\_\_\_\_

e. The following shall be verified when the [supply fan off] [supply and return fans off] mode is initiated:

- (1) All dampers in normal position. \_\_\_\_\_
- (2) All valves in normal position. \_\_\_\_\_
- (3) Fan de-energizes. \_\_\_\_\_

f. Verify cooling coil and heating coil operation by varying thermostat set point from cooling set point to heating set point and returning to cooling set point. \_\_\_\_\_

g. Verify safety shut down initiated by smoke detectors. \_\_\_\_\_

h. Verify safety shut down initiated by low temperature protection  
thermostat. \_\_\_\_\_

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

\_\_\_\_\_

Contractor's Mechanical Representative

\_\_\_\_\_

Contractor's Electrical Representative

\_\_\_\_\_

Contractor's Testing, Adjusting and Balancing Representative

\_\_\_\_\_

Contractor's Controls Representative

\_\_\_\_\_

Resident Engineer

\_\_\_\_\_

Using Agency's Representative

\_\_\_\_\_

Functional Performance Test Checklist - Packaged Air Cooled Chiller

For Chiller: [\_\_\_\_\_]

1. Functional Performance Test: Contractor shall demonstrate operation of chilled water system as per specifications including the following: Start building air handler to provide load for chiller. Activate controls system chiller start sequence as follows.

a. Start chilled water pump and establish chilled water flow. Verify chiller-chilled water proof-of-flow switch operation. \_\_\_\_\_

b. Verify control system energizes chiller start sequence. \_\_\_\_\_

c. Verify chiller senses chilled water temperature above set point and control system activates chiller start. \_\_\_\_\_

d. Verify functioning of "soft start" sequence. \_\_\_\_\_

e. Shut off air handling equipment to remove load on chilled water system. Verify chiller shutdown sequence is initiated and accomplished after load is removed. \_\_\_\_\_

f. Restart air handling equipment one minute after chiller shut down. Verify chiller restart sequence. \_\_\_\_\_

2. Verify chiller inlet/outlet pressure reading, compare to Testing, Adjusting, and Balancing (TAB) Report, chiller design conditions, and chiller manufacturer's performance data.

	DESIGN	SYSTEM TEST	ACTUAL
Chiller inlet pressure (psig)	_____	_____	_____
Chiller outlet pressure (psig)	_____	_____	_____

3. Verify chiller amperage each phase and voltage phase-to-phase and phase-to-ground.

	PHASE 1	PHASE 2	PHASE 3
Amperage	_____	_____	_____
Voltage	_____	_____	_____
Voltage	_____	_____	_____
Voltage to ground	_____	_____	_____

4. Record the following information:

Ambient dry bulb temperature \_\_\_\_\_ degrees F  
Ambient wet bulb temperature \_\_\_\_\_ degrees F  
Entering chilled water temperature \_\_\_\_\_ degrees F  
Leaving chilled water temperature \_\_\_\_\_ degrees F



5. Unusual vibration, noise, etc.

---

---

6. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

---

Contractor's Mechanical Representative

---

Contractor's Electrical Representative

---

Contractor's Testing, Adjusting and Balancing Representative

---

Contractor's Controls Representative

---

Resident Engineer

---

Using Agency's Representative

---

Functional Performance Test Checklist - Fan Coil Units

The Contracting Officer will select fan coil units to be spot-checked during the functional performance test. The number of terminals shall not exceed 10 percent.

1. Functional Performance Test: Contractor shall demonstrate operation of selected fan coils as per specifications including the following:

a. Cooling only fan coils:

(1) Verify fan coil unit response to room temperature set point adjustment. Changes to be cooling set point to cooling set point minus 10 degrees and return to cooling set point. \_\_\_\_\_

(2) Check blower fan air flow. \_\_\_\_\_  
Check blower fan air flow. \_\_\_\_\_ cfm

(3) Check cooling coil water flow. \_\_\_\_\_  
Check cooling coil water flow. \_\_\_\_\_ gpm

(4) Verify proper operation of cooling water control valve. \_\_\_\_\_

b. Cooling/heating fan coils:

(1) Verify fan coil unit response to room temperature set point adjustment. Changes to be cooling set point to heating set point and return to cooling set point. \_\_\_\_\_

(2) Check blower fan air flow. \_\_\_\_\_  
Check blower fan air flow. \_\_\_\_\_ cfm

(3) Check cooling coil water flow. \_\_\_\_\_  
Check cooling coil water flow. \_\_\_\_\_ cfm

(4) Verify proper operation of cooling water control valve. \_\_\_\_\_

(5) Check cooling mode inlet air temperature. \_\_\_\_\_  
Check cooling mode inlet air temperature. \_\_\_\_\_ degrees F

(6) Check cooling mode outlet air temperature. \_\_\_\_\_  
Check cooling mode outlet air temperature. \_\_\_\_\_ degrees F

(7) Check heating coil power. \_\_\_\_\_  
Check heating coil capacity. \_\_\_\_\_ kw

(8) Check heating mode inlet air temperature. \_\_\_\_\_  
Check heating mode inlet air temperature. \_\_\_\_\_ degrees F

(9) Check heating mode outlet air temperature. \_\_\_\_\_  
Check heating mode outlet air temperature. \_\_\_\_\_ degrees F

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative	_____
Contractor's Mechanical Representative	_____
Contractor's Electrical Representative	_____
Contractor's Testing, Adjusting and Balancing Representative	_____
Contractor's Controls Representative	_____
Resident Engineer	_____
Using Agency's Representative	_____

Functional Performance Test Checklist - Computer Room Unit

For Computer Room Unit: [\_\_\_\_\_]

1. Functional Performance Test: Contractor shall verify operation of computer room unit as per specification including the following:

a. System safeties allow start if safety conditions are met. \_\_\_\_\_

b. Verify cooling and heating operation by varying thermostat set point from space set point to space set point plus 10 degrees, space set point minus 10 degrees, and returning to space set point. \_\_\_\_\_

c. Verify humidifier operation by varying humidistat set point from space set point to space set point plus 20 percent RH, and returning to space set point. \_\_\_\_\_

d. Verify that airflow is within +10/-0 percent of design airflow. \_\_\_\_\_

e. Verify unit shut down during fire event initiated by smoke/heat sensors. \_\_\_\_\_

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative \_\_\_\_\_

Contractor's Mechanical Representative \_\_\_\_\_

Contractor's Electrical Representative \_\_\_\_\_

Contractor's Testing, Adjusting and Balancing Representative \_\_\_\_\_

Contractor's Controls Representative \_\_\_\_\_

Resident Engineer \_\_\_\_\_

Using Agency's Representative \_\_\_\_\_

For Energy Recovery Unit: [\_\_\_\_\_]

1. Functional Performance Test: Contractor shall verify operation of Energy Recovery Unit as per specification including the following:

a. The following shall be verified when the outside air and exhaust air fans operating mode is initiated:

(1) All dampers in open position. \_\_\_\_\_

b. Verify when the outside air fan is de-energized that the minimum outside air damper closes.

(1) Outside air damper closed. \_\_\_\_\_

c. Verify when the exhaust air fan is de-energized that the exhaust air damper closes.

(1) exhaust air damper closed. \_\_\_\_\_

2. Record the following information during an approximate design cooling day condition:

Outside Air dry bulb temperature \_\_\_\_\_ degrees F  
Outside Air wet bulb temperature \_\_\_\_\_ degrees F  
Exhaust Air dry bulb temperature (before heat exchanger) \_\_\_\_\_ degrees F  
Exhaust Air wet bulb temperature (before heat exchanger) \_\_\_\_\_ degrees F  
Leaving Exhaust Air dry bulb temperature \_\_\_\_\_ degrees F  
Leaving Exhaust Air wet bulb temperature \_\_\_\_\_ degrees F  
Leaving Outside Air dry bulb temperature \_\_\_\_\_ degrees F  
Leaving Outside Air wet bulb temperature \_\_\_\_\_ degrees F

2. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative

\_\_\_\_\_

Contractor's Mechanical Representative

\_\_\_\_\_

Contractor's Electrical Representative

\_\_\_\_\_

Contractor's Testing, Adjusting and Balancing Representative

\_\_\_\_\_

Contractor's Controls Representative

\_\_\_\_\_

Resident Engineer

\_\_\_\_\_

Using Agency's Representative

\_\_\_\_\_



Functional Performance Test Checklist - HVAC Controls

For HVAC System: [\_\_\_\_\_]

The Resident Engineer will select HVAC control systems to undergo functional performance testing. The number of systems shall not exceed 6.

1. Functional Performance Test: Contractor shall verify operation of HVAC controls by performing the following tests:

a. Verify that controller is maintaining the set point by manually measuring the controlled variable with a thermometer, sling psychrometer, inclined manometer, etc.

b. Verify sensor/controller combination by manually measuring the controlled medium. Take readings from control panel display and compare readings taken manually. Record all readings.

Sensor \_\_\_\_\_  
Manual measurement \_\_\_\_\_  
Panel reading value \_\_\_\_\_

c. Verify system stability by changing the controller set point as follows:

- (1) Air temperature - 10 degrees F
- (2) Water temperature - 10 degrees F
- (3) Static pressure - 10 percent of set point
- (4) Relative humidity - percent (RH)

The control system shall be observed for 10 minutes after the change in set point. Instability or excessive hunting will be unacceptable.

d. Verify interlock with other HVAC controls.

e. Verify interlock with fire alarm control panel.

f. Verify interlock with EMCS.

[g. Change controller set point 10 percent with EMCS and verify correct response.]

2. Verify that operation of control system conforms to that specified in the sequence of operation.

3. Certification: We the undersigned have witnessed the above functional performance tests and certify that the item tested has met the performance requirements in this section of the specifications.

Signature and Date

Contractor's Chief Quality Control Representative \_\_\_\_\_

Contractor's Mechanical Representative \_\_\_\_\_

Contractor's Electrical Representative	_____
Contractor's Testing, Adjusting and Balancing Representative	_____
Contractor's Controls Representative	_____
Resident Engineer	_____
Using Agency's Representative	_____

END OF SECTION 15995