

ZHENGZHOU GREAT WALL MACHINERY MANUFACTURE CO., LTD.



ABOUT GREAT WALL

- China Well-known Trademark (the only enterprise certified with this honor in Xingyang)
- 30 Years Research and Experience
- 22 National Technical Patents
- ISO9001 CE Certified Enterprise
- President of Xingyang Construction Machinery Association
- AAA Rating Certificate of National Quality Credit
- Three Sub-factories, 280,000 Square Meters, 12 Production Lines
- 1858 Stuffs, 123 Professional Technical Engineers, 156 Sales and Service Center in China

CASE & CLIENTS

Our Case and Clients Include Those Fortune 500 Companies Like China Railway, China Sinohydro, China State Construction Engineering, CAMCE and China National Top Companies Like China South-to-North Water Project, China Mechanical Equipment Corp, China National Technology Export Corp., etc. We Have Also Established Overseas Projects in 40 Countries and Regions.

Add: No.446, Zhengshang Road, Xingyang City, Henan, China.Zip: 450199MSN;:zzgreatwall@hotmail.comTel: 0086-371-63250997Fax: 0086-371-63250887SKYPE: zzgreatwallMobil: 86-18625771286



DATE: August 31, 2013


25M³ CONCRETE BATCHING PLANT TURN-KEY PROJECT PROPOSAL


Project No. : 20130831-25

PICTURE OF HZS 25 WE BUILT IN RUSSIA









₽_% 郑州长城机器制造 WALL MACHINERY MANUFACTURE

China Well-known Trademark

	Standard Parameters for the HZS25 Concrete Mixing St	ation
	Models	HZS25
Whole Plant	Productivity (m3 /h)	25
	Standard Discharge Height(m)	1.5-3.8
	Mix Recycle Time(s)	72
	Dimension (mm)(LxWxH)	11693*13060*17245
	Total Power(KW)	50.25
	Specifications	J\$500
	Max.Aggregate Size(Cobble/Crushed Stone)(mm)	≤40/50
Mixer	Mixing Motor Model	Y180M-4
	Mixing Motor Power	18.5kw
	Mixing Blade Rotate Speed	35r/min
	Mixing Blade Number	2x7
	Model	PLD1200
	Storage Hopper Number	3
Batching Machine	Storage Hopper Volume (m ³)	(2-4)x3.5
	Weighing Hopper Volume (L)	1200
Silo	60ton Detachable Silo Number (set)	2
	Model	LSY200
Screw Conveyor	Layout (Diameter*Length)	Ф219(mm) ×6(m)
	Delivery Capacity(t/h)	35
	Air Compressor Model	1.0-7
neumatic System	Rated Discharge Capacity(m ³ /min)	1.67
neumatic system	Rated Discharge Pressure(Mpa)	0.8
	Motor Power(KW)	5.5
	Aggregate Accuracy(kg)	±2%
Neighing System	Cement Accuracy(kg)	±1%
neighnig system	Water Accuracy(kg)	±1%
	Additive Accuracy(kg)	±2%

DETAIL EQUIPMENT LIST

 No.	Equipment Name		Specifications	Q'nty(Set)	Remarks
1	Mixing	Twin Shaft Mixer	JS500	1	Great Wall
	System Discharge	Main Speed Reduce		1	Great Wall
	Height: 3.8M	Main Motor	18.5 Kw	1	Kaifeng Yuanzheng Full Copper
		Hoist Motor Speed Reducer		1	Great Wall
		Hoist Motor	5.5kw	1	Wuxing Full Copper
		Manual Oil Pump		1	Jiangsu Nanjing
		Water pump	1.1kw	1	Zhejiang Chuangmei



	Hydraulic Unit Plates and Blades		3.0Kw	1	Beijing Huade
			High Wearing Resistance Alloy for Plates and Blades	1	Great Wall
		Bracket		1	Great Wall
		Ground Platform		1	Great Wall
		Receiving Hopper		1	Great Wall
		Walking Board		3	Great Wall
		Slide Way		1	Great Wall
		Guard Rail		1	Great Wall
		Ladder		1	Great Wall
		Batch Machine 3 Bins	PLD1200	1	Great Wall Use National Standard Famous Brand Steel
		Belt System	Belt Width 600	4	Curve Type Belt Roller
	Batching	Steel Frame		1	Great Wall
2	System	Transmission Motor 4×3 Kw		4	Kaifeng Yuanzheng Full Copper
		Weighing Hopper	Volume 1.2m ³	1	Great Wall
		Discharging Bin	Volume 2.5m ³	3	Great Wall
		Ground Platform		3	Great Wall
		Weighing Sensor	1000 Kg	3	Putian
		Weighing Hopper	150Kg	1	Great Wall
	Water	Ground Platform		1	Great Wall
3	Weighing System	Sensor	500Kg	3	Putian
		Water Pump	0.75Kw	1	Zhejiang Chuangmei
		Water Pipe, Valve etc		1	
		Additive Weighing Tank	30Kg	1	Great Wall
		Additive Mixing Machine		1	Great Wall
	Additive	Sensor	50Kg	3	Putian
4	Weighing	Ground Platform		1	Great Wall
	System	Pneumatic Butterfly Valve	φ50mm	1	Zhuhai Youbang
		Additive Pump	0.55Kw	1	Shanghai
		Pipe, Valve etc		1	
5	Cement Weighing	Weighing Hopper	250Kg	1	Great Wall
	System	Ground Platform		1	Great Wall
		Sensor	500Kg	3	Putian



WALLI	MACHINERY MA	ANUFACTURE			
		Pneumatic Butterfly Valve	Φ250mm	1	Zhuhai Youbang
		Pneumatic Components		1	AirTAC
		Air Compressor 2.2Kw		1	Shanghai
		Magnetic Valve		1	
		Oil/Water Separator		1	
		Ball Valve		1	
		Pipes and Connectors		1	
		Control System Siemens	PLC Control	1	Siemens
		Industrial Control C	Computer	1	Taiwan Advantech Brand
		Computer			Lenovo
		Display		1	Samsungs
		Printer		1	Epson
		Operation Platform		1	
	Full Auto	Strong Electricity Cabinet		1	
	Centralized Control	Main Components		1	Schneider
	Unit	Cable and Wires		1	
		Button Instruction Lights		1	
		Color Camera		2	Two Way Monitor
6		Monitor System Display		3	
		Main Control Room		1	Great Wall
		Split Air Conditioner1.5P		1	
		Support Frame for Control Room		1	Great Wall
	 Equipped v Combining One Weigh Examination Siemens PI Easily External The Control Easy to Act 	l System can Control 16 Lines hieve Double Machine Double rial Control Computer is Taiwa	omputer Control To one Meter Instrume he Production Proce of Weighing Signal Control Manageme	ogether nt to Assu ess, Contro s nt	re Easy I Functions

®								
	郑州长城机	品制造 6000	Chi	na We	II-known Trademark			
REAT WALL M	ACHINERY MA	NUFACTURE						
	8) Computer I	ntegrity Control, Strong	Anti-Interference Ability,	Easy Ope	ration and Maintenance			
	9) Zero Failure, Zero Repair After Sales							
	10) Electronic Components and Intermediate Relay is of Germany Schneider Brand							
	11) Pneumatic	Butterfly Valve is of In	nported Brand or China To	p Brand				
General C	Characteristics	for HZS25 Concrete B	atching Plant					
1) All Con	nponent Equip	oments are of China Fa	mous Brand					
2) All Stee	l Materials W	e Use are of China Far	ious Brand and of Nation	al Standa	nrd			
3) Integra	ted Design, Co	ompact Structure, Spac	e Saving					
4) High Q	uality, Reliabi	lity and Safety						
5) High La	ayout Flexibili	ty, Fast and Easy Insta	llation and Remove					
6) Low Di	ıst, Low Noise	, High De-dusting Area	, High Efficiency and En	vironmen	tal			
Protect	ion with Electr	ric Pulse De-duster						
7) High A	ccuracy Digita	l Weighing System						
7	Screw Conveyor	φ219mm	P=7.5kw 6m	2				
Technical	Characters fo	r Screw Conveyor						
1) Using H	ligh Quality Ste	eel Pipes, Excellent Ense	emble Rigidity.					
2) Double	Knot Blades D	esign which Reduce the	Compressing Degree of M	aterials du	uring Conveying			
3) Using H	Heavy Duty De	esign High Performance	Speed Reducer Box which	h is Featu	ared with Large Torque and			
Low Noise	2							
4) Optiona	l Universal Ba	ll Connectors to Facilita	te the Direction Change d	uring Inst	allation and Commissioning			
Process								
5) Equipped With High Quality and Easy for Installation Middle Bearing and Rear Bearings								
6) One Time Thorough Formed Screw Leaf, Double Knot Design, No Materials Blocking								
8	Detachable	60t		2				
0	Silo	001		2				
Technical	Technical Characters of Detachable Silo System							
1) Detacha	1) Detachable Silos are Dismantled into Pieces and Easy for Delivery and Maxima Sea Freight Cost Saving							
2) Simple	Installation at S	Site, Huge Cost Saving C	Compared with the Method	of Manuf	acturing at Local Site			
3) Easy to	Move, thus ma	ximally Adapts the Proj	ect Site Changing Requirer	ment and S	Shorten Construction Period			
4) Recycla	ble, Greatly Re	educe Project Cost.						

	QUOTATION							
No	Specifications	Quantity (Set)	Unit Price USD FOB QINGDAO	Total Price USD FOB QINGDAO	Remarks			
1	HZS25 Concrete Batching Plant	1	31,090	31,090	Exclude Silo System and Screw Conveyor			
2	Fissile Silo System (60t)	2	9,600	19,200	2 Silos			
3	Screw Conveyor	2	870	1,740	Φ219(mm)×6(m)			
1. Payn	1. Payment terms is by TT.							
2. Quot	ation Validity is 60 days.							

ALL MACHINERY MANUFACTURE

3. All above quotation is on basis that 100USD=610RMB, if the value of RMB increase by more than 1%, the Buyer needs to compensate the loss thus occurred to the seller.

CERTIFICATE OF TECHNICAL UTILITY PATENT FOR CONCRETE BATCHING PLANT

- 1) Concrete Mixer With An Anti-Lock System And Climbing Hopper, No 2872459
- 2) Concrete Mixer And Its Weighing Modules, No 2887247
- 3) Water Weighing And Feeding System And The Concrete Mixer Using The System, No 2871361
- 4) Mixing Drum Device And The Concrete Mixer Using The Device, No 2887168
- 5) Mixing Shaft Device And The Concrete Mixer Using The Device, No 2964085
- 6) Concrete Mixer With The Function Of Anti-Clogging When Power Off, No 2872136
- 7) Side-Hanging Motor Bracket And The Concrete Mixer Using It, No 2885795
- 8) Water Weighing Hopper And The Concrete Mixer Using The Hopper, No 2886392
- 9) Low-Noise Double Shaft Concrete Mixer, No 2832079
- 10) Climbing Hopper Type Concrete Mixer And Its Cement Weighing Device, No 2832985
- 11) Concrete Mixer With Forced Horizontal-Shaft, No 2872654
- 12) New Type Stabilized Soil Mixer, No 2833136
- 13) A Mixing Drum and the Stabilized Soil Mixer Using It, No 2870489
- 14) A Mixing Shaft Assembly and the Stabilized Soil Mixer, No 2886802


WHY CHOOSE GREAT WALL MACHINERY MANUFACTURE COMPANY?

- China Famous Manufacturer Of Construction Machinery
- China Well-Known Trademark
- 3)30 Years Research And Project Experience
- 4)22 National Level Technical Patents
- 5)AAA Rating Enterprise Of Quality And Credit (National Level)
- 6)President Company Of Xingyang Zhengzhou Construction Machinery Association
- 7)Total Area Of 280,000 Square Meters, 12 Production Lines
- 8)Total 1858 Stuffs, 123 Professional Technical Engineers, 156 Sales And Service Center In China
- 9)Registered Capital 15Millions RMB
- 10)ISO CANS IAF Certified Enterprise



PICTURE OF MIXER







PICTURE OF SCREW CONVEYOR



PICTURE OF CONTROL SYSTEM





PICTURE OF SILOS



ASSUARANCE ON QUALITY

a) The project plan can totally satisfy your production needs at the most effective way and without wasting of resources.

- b) One year quality assurance.
- c) Abundant wearing spareparts free delivery with equipments enough for one year usage.

ON DELIVERY AND PACKAGE

- a) Delivery date: 15 days after advance payment.
- b) Standard export package for equipments and wooden box for spare parts
- c) Need 2x 40ft High Containers

ON INSTALLATION AND DEBUGGING

- a) Requires about <u>1</u> technician to the Buyer's local for installation and debugging and operation training.
- b) The Buyer needs to prepare translator and help the technician for visa, and bears all the charges for visa, traffic tickets, accommodation and salary of USD80/technician/day for the period of out and home.
- c) The user needs to make full preparation for the installation and debugging to assure fast progress of the installation and debugging work.



ON PAYMENT AND OTHER TERMS

- a) Valid: this quotation is valid within 60 days hereafter on.
- b) Payment terms: 30% TT advance rest 70% payment before shipment.

OTHERS

a) This above proposal is primary for reference. Details might be varied with the deeper communication with The Buyer

b) We reserve the right to improve our equipments and technology to be newest as the technology is development continuously.

c) The detailed mill design and other technical documentations will be provided within 15 days after contract signing.

d) A full set of documentation including will be provided as following:

General layout drawing of the workshop (drawing for approval)

General layout drawing of the mill equipments (drawing for approval)

Operating instructions & Maintenance instructions

(THANK YOU!)