

(32) TENDER SCHEDULE FOR THE WORK "CONSTRUCTION OF NEW ST GIRLS' HOSTEL COMPLEXES-I AT NISANAHANDI UNDER NANDAHANDI BLOCK".

Name _____, " _____ " **Class Contractor**

Address _____

Amount put to tender: Rs.37,87,926.00

| Sl. No. | Item | Qty. | Unit | RATE | |
|---------|---|--------|---------|-----------|----------|
| | | | | In Figure | In Words |
| 01 | Earthwork excavation of foundation in hard soil with all leads & lifts including rough dressing breaking of clods and leveling the bed and sides then depositing the excavated earth away from the work site, T & P required for the work including 1% Cess etc. complete as directed by the Engineer- in- Charge. | 205.74 | 100 Cum | | |
| 02 | Filling in foundation and plinth with sand, well watered and rammed to required thickness with all leads and lifts, cost conveyance & royalty and all taxes of materials, cost of labour, T & P required for the work including 1% Cess etc. complete in all respect as directed by the Engineer-In-Charge. | 133.80 | One Cum | | |
| 03 | Cement concrete (1: 4:8) in foundation using 40 mm size clean hard black hand broken granite metal of approved quality from approved quarry mixing with concrete mixture laying manually including hoisting, lowering and laying in layers not exceeding 15 cm thick to the required level, ramming, watering with cost conveyance, royalty and all taxes of materials, cost of labour, T &P and machineries etc curing including 1% Cess etc. complete. as directed by the Engineer-In-Charge. | 51.92 | One Cum | | |

Signature of Contractor

Project Administrator,
ITDA, Nabarangpur

| Sl. No. | Item | Qty. | Unit | RATE | |
|---------|--|-------|---------|-----------|----------|
| | | | | In Figure | In Words |
| 04 | Random Rubble Hard Granite Stone Masonry in C.M. (1:6) in foundation and plinth using hard broken granite stone of approved size and quality from approved quarry including splays cutting, corbelling, watering and curing including cost, conveyance, royalty and all taxes of materials with cost of labour T & P including 1% Cess etc. complete required for the work directed by the Engineer-In-Charge. | 72.54 | One Cum | | |
| 05 | R.C.C. in CC (1:1½:3) with clean hard broken granite chips of 12 mm size consistent with strength and strengthen cover of concrete, of approved quality and from approved quarry mixing with concrete mixture & laying manually including hoisting with and laying concrete in layer not exceeding 15cm in depth to the required thickness and compacting as per the direction of the Engineer-in-charge including rigid & smooth centering , shuttering , watering and curing for four weeks and finishing the exposed surface smooth with cost, conveyance, taxes and royalties and taxes of all materials, labour T & P, hire and running charges of machineries required for the work including 1% Cess but excluding cost, conveyance, of M.S/T.S Rods and direction of Engineer-in-charge. | | | | |
| (A) | G.FLOOR | | | | |
| (I) | Plinth Bend | 48.52 | One Cum | | |

Signature of Contractor

Project Administrator,
ITDA, Nabarangpur

| Sl. No. | Item | Qty. | Unit | RATE | |
|---------|----------------|-------|---------|-----------|----------|
| | | | | In Figure | In Words |
| (II) | Lintle Bend | 6.96 | One Cum | | |
| (III) | Columns & Beam | 32.57 | One Cum | | |
| (IV) | Slab & Chajja | 43.32 | One Cum | | |
| (B) | FIRST FLOOR | | | | |
| (I) | Lintle Bend | 6.74 | One Cum | | |
| (II) | Columns & Beam | 30.41 | One Cum | | |
| (III) | Slab & Chajja | 43.63 | One Cum | | |

Signature of Contractor

Project Administrator,
ITDA, Nabarangpur

| Sl. No. | Item | Qty. | Unit | RATE | |
|---------|--|--------|---------|-----------|----------|
| | | | | In Figure | In Words |
| 06 | Well burnt clamp brick masonry in C.M (1:6) in super structure using C.B. bricks of 10" size having a crushing strength not less than 35 Kg/sq.cm including splays cutting, circular moulding, chamfering and corbelling, and watering and curing etc. complete including cost conveyance, royalty and all taxes of materials with cost of labour, T & P including 1% Cess etc. required for the work complete in all respect. | | | | |
| (A) | G.FLOOR | 103.09 | One Cum | | |
| (B) | FIRST FLOOR | 118.56 | One Cum | | |
| 07 | Supplying straightening, Cutting, Bending, Binding, Cranking, Hooking, and jointing, (if required) the HYSD rod and tying the grills, hoisting and placing in proper position as required for R.C.C. works including cost, conveyance and all taxes of rods and binding wires of 18 to 20 gauge with cost of labour and T & P required for the work including 1% Cess etc. complete in all respect as directed by the Engineer-in- charge. | | | | |
| (A) | G.FLOOR | 131.37 | One Qtl | | |

Signature of Contractor

Project Administrator,
ITDA, Nabarangpur

| Sl. No. | Item | Qty. | Unit | RATE | |
|---------|--|--------|---------|-----------|----------|
| | | | | In Figure | In Words |
| (B) | FIRST FLOOR | 80.78 | One Qtl | | |
| 08 | 20mm thick cement grading plaster in C.M. (1:4) over roof slab to proper slope finished smooth including cost of water proof compound with watering and curing including cost, conveyance, royalty and all taxes of materials with cost of labour and T & P required for the work including 1% Cess etc. complete in all respect as per direction of Engineer-in-Charge. | 390.21 | One Sqm | | |
| 09 | 20 mm thick cement plaster in cement mortar (1:6) over stone masonry finished smooth including watering and curing, cost conveyance royalty and all taxes of materials with cost of labour and T & P, required for the work including 1% Cess etc.complete in all respect as per direction of Engineer-in-Charge. | 44.06 | One Sqm | | |
| 10 | 16 mm thick cement plaster in C.M. (1:6) over brick work (inside walls), after raking out joints finished smooth including watering and curing, cost conveyance royalty and all taxes of materials with cost of labour and T & P etc, required for the work including 1% Cess etc. complete in all respect as per direction of Engineer-in-Charge. | | | | |
| (A) | G.FLOOR | 717.50 | One Sqm | | |

Signature of Contractor

Project Administrator,
ITDA, Nabarangpur

| Sl. No. | Item | Qty. | Unit | RATE | |
|---------|--|--------|---------|-----------|----------|
| | | | | In Figure | In Words |
| (B) | FIRST FLOOR | 742.35 | One Sqm | | |
| 11 | 12 mm thick cement plaster in cement mortar (1:6) over stone masonry finished smooth including watering and curing, cost conveyance royalty and all taxes of materials with cost of labour and T & P etc, required for the work including 1% Cess etc. complete in all respect as per direction of Engineer-in-Charge. | | | | |
| (A) | G.FLOOR | 362.31 | One Sqm | | |
| (B) | FIRST FLOOR | 513.71 | One Sqm | | |

Signature of Contractor

Project Administrator,
ITDA, Nabarangpur

| Sl. No. | Item | Qty. | Unit | RATE | |
|---------|--|--------|---------|-----------|----------|
| | | | | In Figure | In Words |
| 12 | 2.5 cm thick artificial stone flooring in C.C. (1:2:4) laid to proper slopes and to a finished smooth surface by punning using 12 mm size down graded hard broken granite chips with watering and curing including cost, conveyance, royalty and all taxes of materials with cost of labour T &P etc. required for the work including 1% Cess etc. complete in all respect as per direction of Engineer-in-Charge. | | | | |
| (A) | G.FLOOR | 292.09 | One Sqm | | |
| (B) | FIRST FLOOR | 301.44 | One Sqm | | |
| 13 | Fixing of Kota stone flooring with proper slope with (1:2) cement mortar and color over 10 cm thick PCC with watering, curing for seven days with cost, conveyance, royalty, taxes of all materials labour including cutting and wax polishing etc complete | | | | |
| (A) | G.FLOOR | 59.96 | One Sqm | | |
| (B) | FIRST FLOOR | 59.96 | One Sqm | | |

Signature of Contractor

Project Administrator,
ITDA, Nabarangpur

| Sl. No. | Item | Qty. | Unit | RATE | |
|---------|---|---------|---------|-----------|----------|
| | | | | In Figure | In Words |
| 14 | Fixing of Ceramic tiles of approved shade and design over 12 mm thick cement plaster (1:1) over brickwork for dadoes, finished smooth with proper thickness, watering, curing for seven days with cost conveyance, royalty, taxes of all materials, labour including 1% Cess etc. complete in all respect as per direction of Engineer-in-Charge. | | | | |
| (A) | G.FLOOR | 72.03 | One Sqm | | |
| (B) | FIRST FLOOR | 72.03 | One Sqm | | |
| 15 | Distempering two coats over a coat of primer to walls with distemper of approved shade on new work to give on even shade including cost of distemper conveyance, taxes of all materials, labour etc complete. | | | | |
| (A) | G.FLOOR | 1069.55 | One Sqm | | |
| (B) | FIRST FLOOR | 1103.75 | One Sqm | | |

Signature of Contractor

Project Administrator,
ITDA, Nabarangpur

| Sl. No. | Item | Qty. | Unit | RATE | |
|-----------------------|--|--------|---------|-----------|----------|
| | | | | In Figure | In Words |
| 16 | Weather coating two coats to the wall with approved shade over a coat of wall primer on new work to give on even shade including cost of weather conveyance, taxes of all materials, labour including 1% Cess etc. complete in all respect as per direction of Engineer-in-Charge. | | | | |
| (A) | G.FLOOR | 344.55 | One Sqm | | |
| (B) | FIRST FLOOR | 524.15 | One Sqm | | |
| 17 | Cost of Ventilators. | 56 | Nos. | | |
| 18 | Cost for construction of display board of size 6' 0" x 4' 0" including painting and writing with enamel paint with all cost, conveyance and taxes of all materials including 1% Cess etc. complete in all respect as per direction of Engineer-in-Charge. | 1 | No. | | |
| (Eighteen items only) | | | | | |
| Total | | | | | |

Signature of Contractor

Project Administrator,
ITDA, Nabarangpur