

**(34) TENDER SCHEDULE FOR THE WORK "CONSTRUCTION OF CHECK DAM NEAR DHANSULI VILLAGE L.I. POINT UNDER PAPADAHANDI BLOCK"**

Name \_\_\_\_\_, " \_\_\_\_\_ " Class Contractor

Address \_\_\_\_\_

**Amount put to tender: Rs.21,32,820.00**

Sl. No.	Item	Qty.	Unit	RATE	
				In Figure	In Words
01	Earthwork excavation for foundation & over burden in hard soil including rough dressing the bed and slope to receive concrete including dewatering if necessary and disposing the excavated earth away from the work site and reuse if necessary and T & P required for the work etc. complete as directed by the Engineer- in- Charge.				
	(A) Foundation	658.00	100 Cum		
	(B) over burden	512.80	100 Cum		
02	Cement concrete (1:3:6) in foundation & Super structure using 40 mm size clean hard black hand broken granite metal of approved quality from approved quarry by mixing with concrete mixture machine then laying manually and curing etc. complete with cost conveyance, royalty and all taxes of materials, cost of labour, T & P and hire and running charges of all machineries etc. complete in all respect as per direction of Engineer-in-Charge.	710.99	One Cum		

Signature of Contractor

Project Administrator,  
ITDA, Nabarangpur

Sl. No.	Item	Qty.	Unit	RATE	
				In Figure	In Words
03	Cement concrete (1:2:4) using 12 mm size clean hard black crusher broken granite chips of approved quality from approved quarry including hoisting, lowering and mixing with concrete mixture machine then laying manually and curing etc. complete with cost, conveyance, royalty and all taxes of materials, cost of labour, T &P and hire and running charges of all machineries etc. complete in all respect as per direction of Engineer-in-Charge.	12.06	One Cum		
04	R.C.C (1:2:4) using 12 mm size clean hard black crusher broken granite chips of approved quality from approved quarry including hoisting, lowering and mixing with concrete mixture machine then laying manually and curing etc. complete with cost, conveyance, royalty and all taxes of materials, cost of labour, T &P and hire and running charges of all machineries but excluding cost, conveyance, royalty and all taxes of M.S.Rod etc. complete in all respect as per direction of Engineer-in-Charge.	26.88	One Cum		
05	Rough stone dry packing in aprrone & revetment with hard granite stone 0.0015 to 0.003 cum filling the interstices with small stones including cost, conveyance, royalty of stone	183.00	One Cum		

Signature of Contractor

Project Administrator,  
ITDA, Nabarangpur

Sl. No.	Item	Qty.	Unit	RATE	
				In Figure	In Words
06	Labour for straightening, Cutting, Bending, Binding, Cranking, Hooking, and jointing, (if required) the M.S. rod and tying the grills, hoisting and placing in proper position as required for R.C.C. works including cost, conveyance and all taxes of M.S. rods and binding wires of 18 to 20 gauge with cost of labour and T & P required for the work etc. complete in all respect as directed by the Engineer-in-charge.	23.44	One Cum		
07	supplyinng,fitting & fixing 1.0 mtr x1.30 mtr M.S shutter gate with 'P' type water tight rubber seal fitted with bottom & guide channel including locking arrangement etc. complete in all respect as directed by the Engineer-in-charge.	11	Each		
08	Cost for construction of display board of size 6' 0" x 4' 0" including painting and writing with enamel paint with all cost, conveyance and taxes of all materials .	1	Each		
(Eight items only)					
Total					

Signature of Contractor

Project Administrator,  
ITDA, Nabarangpur