ADDENDUM

Walton County Board of Commissioners
Office of Central Purchasing
176 Montgomery Circle
DeFuniak Springs, Fl 32435

ITB NO: 014-021

ITB TITLE: Dothan Avenue Walkover Improvements

OPENING DATE: July 9, 2014 no later than 3:00PM local time and will open immediately thereafter.

ADDENDUM NO: 1

DATE: June 30, 2014

PLEASE BE ADVISED THAT THE FOLLOWING CHANGES ARE APPLICABLE TO THE ORIGINAL SPECIFICATIONS OF THE ABOVE REFERENCED ITB.

- Clarification: Awarded contractor will warrant that areas planted with sea oats and railroad vine shall display EIGHTY PERCENT (80%) survival at the end of ONE YEAR from the date of final installation.
- Corrected Bid Schedule attached
- Clarification: The area to be planted is approximately 3200 sf
- Please see that a revised Sheet P1 is attached showing elevations and location of stairs
- Article 1 (Scope of Work), paragraph O being modified to require Contractor to rake the sand at the end of each day during turtle nesting season to remove vehicle tracks.
 See Attached paragraph.
- The sand/fill that is excavated for the installation of the 36" ADS pipe will be suitable for fill landward of the crest of the proposed dune construction or between station 1+60 and 2+00.
- "Moisture Shield" will be a suitable replacement for both decking and handrail top cap.
- Pile embedment for the pile-constructed boardwalk section will be based on the existing grade.

THIS ADDENDUM NOW BECOMES A PART OF THE ORIGINAL ITB. ACKNOWLEDGE RECEIPT OF THIS ADDENDUM. FAILURE TO DO SO MAY SUBJECT THE BIDDER DISQUALIFICATION.

| BIDDER: | BY: |
|----------------------|--------|
| ADDRESS: | PHONE: |
| CITY, STATE, | DATE: |
| EMAIL ADDRESS: | |
| | |
| Authorized Signature | |

O. County will provide limited rights of way and easements necessary for equipment access to the beach in the areas where work is to be performed by Contractor under this Contract. The Contractor shall be required to document via videotape the condition of all access locations and rights of way prior to initiating any construction activity. A copy of the videotape shall be provided to the County. The Contractor shall be responsible for any repairs required to restore equipment access locations utilized during the work, including but not necessarily limited to paving, fencing, boardwalks, dunes and vegetation. During turtle nesting season (May 1 through October 31) Contractor shall, at the end of each work day, rake the sand around the work site to eliminate tracks caused by Contractor's vehicles.

BID SCHEDULE

NOTE: BIDS shall include sales tax and all other applicable taxes and fees.

This is a LUMP SUM BID. The following Bid Schedule is intended as a general recap of the work involved, it is NOT an all inclusive detail of everything required to do this job. It is the contractor's responsibility to carefully review the plans, specifications, and project to determine what is needed to do the whole job, and to reflect this in his LUMP SUM BID. This basis of award will be the total base bid for the project. IF DURING THE BID PROCESS, THE CONTRACTOR NOTICES A DISCREPANCY BETWEEN THE WORK REQUIRED AND THIS BID SCHEDULE HE MUST BRING IT TO THE ENGINEER'S ATTENTION BEFORE THE BID DATE.

| | | | 18 | | |
|-----|---|----------|-----------|------------|-------------|
| NO. | ITEM | QUANTITY | UNITS | UNIT PRICE | TOTAL PRICE |
| 1. | 6' Wide Timber Boardwalk Installed @ Sta. 0+00 To 1+40 | 140 | LF | | |
| 2. | 6' Wide Timber Boardwalk Installed @ Sta. 1+40 To End | 150 | LF | | |
| 3. | 4" Thick 3000 PSI Concrete Landing | 20 | SY | | |
| 4. | Demolish & Remove Existing Timber Boardwalk | 1 | LS | | |
| | LIKE-I ANEOUS | | | | |
| 5. | Type "D" Inlet Box Installed | 2 | EA_ | | |
| 6. | 18" Perforated ADS Pipe Installed with Filter Sock | 16 | LF | | |
| 7. | 36" Perforated ADS Pipe Installed w/ Filter Fabric | 130 | LF | | |
| 8. | 36" ADS End Cap Installed | 1 | EA | | |
| 9. | Beach Compatible Fill As Required by FDEP Beaches and Coastal Systems to meet proposed grade as indicated on plans | 1 | LS | | |
| 10. | Sea Oats with 1" Liner & Gel Pack @ 18" O.C. Installed | 1 | LS | | |
| 11. | Earthwork (Excess Material Taken Out for Drainage Pipe Installation) | 1 | LS | | |
| 12. | Layout | 1 | LS | | |
| | | L | ap Stail | | |
| 13. | Maintenance of Traffic (to include temporary signage to close Dothan Street east access to CR 30A) | 1 | LS | | |
| 14. | Bonds (Max 2% of Bid) | 1 | LS | | |
| 15. | Mobilization (Max 5% of Bid) | 1 | LS | | |
| | | | TOTAL: | | |

| BID NAME: | DOTHAN AVENUE WALKOVER IMPROVEMENTS | | | | | |
|---|-------------------------------------|---------|--|--|--|--|
| BID NO.: | 014-021 | | | | | |
| BID AMOUNT: | \$ | | | | | |
| NOTE: The unit prices listed above will be used as the basis for computing the value of any change orders either additive or deductive. THE OWNER RESERVES THE RIGHT TO REJECT ANY OR ALL BIDS. | | | | | | |
| Respectfully subn | nitted: | | | | | |
| Signature | | Address | | | | |
| Title | | Date | | | | |
| License Number (| if applicable) | | | | | |
| (SEAL – if bid is b | y a corporation) | | | | | |
| ATTEST: | | | | | | |
| | | | | | | |

