



BEDZYK BROS., INC.

General Construction – Construction Management – Design/Build – Development

Revised Concrete Flatwork Bid Form & Scope of Work

New Goodwill Dearborn Retail Store

April 30, 2012

Bids Due:	Friday, May 4, 2012 by 12:00 pm (noon)
Project Commence with Work: *	Friday, May 11, 2012

* Construction Phase - Subject to acquisition date of permits

CONCRETE FLATWORK - SCOPE OF WORK:

1) **Base Bid:**

- a) Provide all material, labor, forms, re-bar/reinforcement, equipment, supervision, etc., necessary to complete the Interior Flatwork concrete floor infill/patching;
- b) Include all fine grading, compaction and/or minor excavation work
- c) Coordinate all soil, concrete, etc., testing with Prime and/or testing company (as directed by Prime);

2) **Alternate #EC:** (Exterior Canopy Flatwork)

- a) Provide all material, labor, forms, re-bar/reinforcement, expansion joint, equipment, supervision, etc., necessary to complete the new sidewalk - Exterior Concrete Flatwork - at new canopy island;
- b) Include all excavation, fine grading, sand backfill/compaction; legally dispose of all excess material from site upon completion;
- c) Coordinate all soil, concrete, etc., testing with Prime and/or testing company (as directed by Prime);

3) **Alternate #SD:** (Site Demo)

- a) Sawcut and remove asphalt for new foundations (overcut approx. 12") at canopy and new island; remove and stockpile stone base from foundation area for re-use; stone base in island area to remain; legally dispose of all removed/excess material

4) **Alternate #CF:** (Exterior Canopy Foundations)

- a) Provide all material, labor, forms, re-bar/reinforcement, equipment, supervision, etc., necessary to complete the Foundation work for the new canopy, per the drawings (mass pour will be acceptable, provided the top is formed, unless designed to be 8" below finish grade (asphalt);
- b) Include all excavation, fine grading, sand backfill/compaction; legally dispose of all excess material from site upon completion;
- c) Coordinate all soil, concrete, etc., testing with Prime and/or testing company (as directed by Prime);
- d) Provide installation of anchor bolts, leveling plates (w/ grout) and miscellaneous steel embedded in concrete; include dowels into existing foundations as required;
- e) Remove asphalt, including sawcutting, to accommodate the installation of the new footings and legally dispose of off-site;

=====

PLEASE FILL IN ALL THE INFORMATION BELOW COMPLETELY & RETURN TO BBI


=====

BASE BID – Total Amount:

\$ _____



RE: *Revised* CONCRETE FLATWORK – BID FORM & Scope of Work
New Goodwill Dearborn Retail Store
April 30, 2012 - Page 2 of 2



Bedzyk Bros., Inc.

- Schedule information:
 - # of work days to complete work: _____
 - Lead-time req'd for submittals: _____

Alternate #EC: (Exterior Canopy Flatwork)– Total Amount, ADD: \$ _____

- Schedule information: # of work days to complete: _____

Alternate #SD (Site Demo) – Total Amount, ADD: \$ _____

- Schedule information: # of work days to complete: _____

Alternate #CF: (Exterior Canopy Footings) – Total Amount, ADD: \$ _____

- Schedule information: # of work days to complete: _____

1.1 ADDENDA

A. Bidder acknowledges receipt of the following Addenda:

No. _____ Dated _____, 20__

No. _____ Dated _____, 20__

No. _____ Dated _____, 20__

Respectfully Submitted,

_____	_____
Firm Name	By
_____	_____
Street Address	Signature
_____	_____
City, State and Zip Code	Title
_____	_____
Telephone	Email
_____	_____
Fax	Cell Phone
_____	_____
Date	

Corporations: Affix Corporate Seal

State in which incorporated

END OF DOCUMENT

f:\bbi files\goodwill - dearborn\scopes for subs\scope for arch phase\concrete flatwork revised.doc

