

## HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation  
DT1502 10/2010 s.66.29(7) Wis. Stats.

Proposal Number:

3 Ø

COUNTY	STATE PROJECT ID	FEDERAL PROJECT ID	PROJECT DESCRIPTION	HIGHWAY
Marquette	6749-00-70		10 <sup>th</sup> Road Gale Avenue – CTH D Union Pacific RR Crossing	Town Road

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required, \$ 40,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Due Date: March 12, 2013 Time (Local Time): 9:00 AM	Firm Name, Address, City, State, Zip Code
Contract Completion Time Eighty (80) Working Days	<b>SAMPLE</b> <b>NOT FOR BIDDING PURPOSES</b>
Assigned Disadvantaged Business Enterprise Goal 0 %	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

**Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.**

Subscribed and sworn to before me this date \_\_\_\_\_

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

Notary Seal

\_\_\_\_\_  
(Bidder Signature)

\_\_\_\_\_  
(Print or Type Bidder Name)

\_\_\_\_\_  
(Bidder Title)

### For Department Use Only

Type of Work Grading, base, paving, Structure B-39-74, structure removal, signing, pavement marking and culvert pipe.	
Notice of Award Dated	Date Guaranty Returned

**PLEASE ATTACH  
PROPOSAL GUARANTY HERE**

## **Effective with November 2007 Letting**

### **PROPOSAL REQUIREMENTS AND CONDITIONS**

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

## BID PREPARATION

### Preparing the Proposal Schedule of Items

#### **A General**

- (1) Obtain bidding proposals as specified in **section 102** of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
  1. Electronic bid on the internet.
  2. Electronic bid on a printout with accompanying diskette or CD ROM.
  3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 P.M. local time on the Thursday before the letting. Check the department's web site after 5:00 P.M. local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express™ on-line bidding exchange at <http://www.bidx.com/> after 5:00 P.M. local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (\*.ebs or \*.00x) is used to submit the final bid.
- (4) Interested parties can subscribe to the Bid Express™ on-line bidding exchange by following the instructions provided at the [www.bidx.com](http://www.bidx.com) web site or by contacting:

Info Tech Inc.  
5700 SW 34th Street, Suite 1235  
Gainesville, FL 32608-5371  
email: <mailto:customer.support@bidx.com>

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm> or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, Room 601, 4802 Sheboygan Avenue, Madison, WI, during regular business hours.

#### **B Submitting Electronic Bids**

##### **B.1 On the Internet**

- (1) Do the following before submitting the bid:
  1. Have a properly executed annual bid bond on file with the department.
  2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in **102.6** and **102.9** of the standard specifications, submit the proposal on the internet as follows:

1. Download the latest schedule of items reflecting all addenda from the Bid Express™ web site.
  2. Use Expedite™ software to enter a unit price for every item in the schedule of items.
  3. Submit the bid according to the requirements of Expedite™ software and the Bid Express™ web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
  4. Submit the bid before the hour and date the Notice to Contractors designates.
  5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

## **B.2 On a Printout with Accompanying Diskette or CD ROM**

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express™ web site reflecting the latest addenda posted on the department's web site at <http://www.dot.wisconsin.gov/business/engrserv/bid-letting-information.htm>. Use Expedite™ software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express™ web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite™ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite™ generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

**Bidder Name**

**BN00**

**Proposals: 1, 12, 14, & 22**

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite™ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  1. The check code printed on the bottom of the printout of the Expedite™ generated schedule of items is not the same on each page.
  2. The check code printed on the printout of the Expedite™ generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

### **C Waiver of Electronic Submittal**

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to [section 102](#) of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in [section 102](#) of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
  2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
  3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in [section 102](#) of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.





# PROPOSAL BID BOND

DT1303 1/2006

Wisconsin Department of Transportation

Proposal Number	Project Number	Letting Date
Name of Principal		
Name of Surety	State in Which Surety is Organized	

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation **within 10 business days of demand** a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

## PRINCIPAL

\_\_\_\_\_  
(Company Name) **(Affix Corporate Seal)**

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

\_\_\_\_\_  
(Company Name)

\_\_\_\_\_  
(Signature and Title)

## NOTARY FOR PRINCIPAL

\_\_\_\_\_  
(Date)

State of Wisconsin )  
 ) ss.  
\_\_\_\_\_ County )

On the above date, this instrument was acknowledged before me by the named person(s).

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

**Notary Seal**

\_\_\_\_\_  
(Name of Surety) **(Affix Seal)**

\_\_\_\_\_  
(Signature of Attorney-in-Fact)

## NOTARY FOR SURETY

\_\_\_\_\_  
(Date)

State of Wisconsin )  
 ) ss.  
\_\_\_\_\_ County )

On the above date, this instrument was acknowledged before me by the named person(s).

\_\_\_\_\_  
(Signature, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Print or Type Name, Notary Public, State of Wisconsin)

\_\_\_\_\_  
(Date Commission Expires)

**Notary Seal**

**IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.**



# CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

Time Period Valid (From/To)	
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

**Cancellation:** Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

\_\_\_\_\_  
(Signature of Authorized Contractor Representative)

\_\_\_\_\_  
(Date)



**FEBRUARY 1999**

**LIST OF SUBCONTRACTORS**

Section 66.29(7), Wisconsin Statutes, provides that a bidder, as a part of his proposal, shall submit a list of the subcontractors he proposes to contract with and the class of work to be performed by each, provided that to qualify for such listing each subcontractor must first submit his bid in writing to the general contractor at least 48 hours prior to the time of bid closing. It further provides that a proposal of a bidder shall not be invalid if any subcontractor, and the class of work to be performed by such subcontractor, has been omitted from a proposal.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

<b>Name of Subcontractor</b>	<b>Class of Work</b>	<b>Estimated Value</b>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>
<hr/>	<hr/>	<hr/>



**DECEMBER 2000**

**CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER  
RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

Instructions for Certification

1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 - "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
  - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
  - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
  - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.



## Special Provisions

### Table of Contents

Article	Description	Page #
1.	General.....	2
2.	Scope of Work. ....	2
3.	Prosecution and Progress. ....	2
4.	Traffic. ....	3
5.	Utilities.....	3
6.	Railroad Insurance and Coordination. ....	4
7.	Union Pacific Railroad Requirements. ....	7
8.	Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found. ....	9
9.	Debris Containment Structure B-39-74, Item 203.0225.S.01.....	10
10.	QMP Base Aggregate. ....	11
11.	Temporary Sediment Trap, Item SPV.0060.01. ....	19
12.	Temporary Shoring Railroad, Item SPV.0105.01.....	20

## **SPECIAL PROVISIONS**

### **1. General.**

Perform the work under this construction contract for Project 6749-00-70, 10<sup>th</sup> Road, Union Pacific RR Crossing, Town Road, Town of Packwaukee, Marquette County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2013 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20120615)

### **2. Scope of Work.**

The work under this contract shall consist of constructing Structure B-39-0074 on a new alignment, grading, culvert pipe, base aggregate dense, erosion control, HMA pavement, removing the existing structure and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

### **3. Prosecution and Progress.**

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the time frame for construction of the project within the 2013 construction season to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Assure that the time frame is consistent with the contract completion time. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

#### **4. Traffic.**

10<sup>th</sup> Road will remain open to all traffic during the majority of the construction operations under this contract. Traffic will use the existing bridge while the new one is constructed.

Use drums, barricades, cones, flaggers or temporary fencing, in addition to the traffic control shown in the plans, to delineate and or protect the public from temporary hazards in the work zone. Protect hazards such as; exposed excavations, drop offs, construction equipment and operations and any other hazardous condition that is caused by the construction activity. All costs for the use of such devices are incidental to the operation that creates the hazard.

10<sup>th</sup> Road may be closed to traffic for a maximum period of three weeks for the purposes of tying the new roadway into the existing roadway and connecting the dead end road section of old 10<sup>th</sup> Road to the new roadway. A detour route will not be posted, alternate routes are available. Provide local access for property owners and emergency vehicles at all times.

Notify property owners within the construction limits a minimum of two days in advance of any construction operation that will limit access to the use of their driveway.

#### **5. Utilities.**

This contract does not come under the provision of Administrative Rule Trans 220. 107-065 (20080501)

**Adams-Columbia Electric Cooperative** has an overhead electric line about 30-feet east of existing 10<sup>th</sup> Road. They will remove and relocate all existing poles and lines within the construction limits. Adams-Columbia will complete all work prior to construction.

**Frontier** does not anticipate any conflicts with their underground line at the north side of Old 10<sup>th</sup> Road. No relocations are necessary.

**Level 3 Communications** has a buried fiber optic line located along the north side of the railroad tracks approximately 65-feet from the centerline. Fill and crushed aggregate slope paving for the new structure will extend over the fiber optic lines. Relocation of this facility is not anticipated.

## **6. Railroad Insurance and Coordination.**

### **A Description**

Comply with standard spec 107.17 for all work affecting Union Pacific Railroad Company property and any existing tracks.

### **A.1 Railroad Insurance Requirements**

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3. Insurance is filed in the name of Union Pacific Railroad Company.

Notify evidence of the required coverage, and duration to John Venice at Industry and Public Projects Engineering Department, 101 North Wacker Drive, Suite 1920, Chicago, IL 60606, TELEPHONE (312) 777-2043, FAX (402) 233-2769, email [jnvenice@up.com](mailto:jnvenice@up.com). Include the following information on the insurance document:

Project 6749-00-70

Route Name 10<sup>th</sup> Rd Bridge, Marquette County

### **A.2 Work by Railroad**

The railroad will perform the work described in this section, except for work described in other special provisions and will be accomplished without cost to the contractor. Pole line through the construction site will be removed prior to construction at no cost to the project.

### **A.3 Names and addresses of Railroad Representatives for Consultation and Coordination**

Contact John Venice, Manager Special Projects – Industry and Public Projects Engineering Department, 101 North Wacker Drive, Suite 1920, Chicago, IL 60606, TELEPHONE (312) 777-2043,, FAX (402) 233-2769, email [jnvenice@up.com](mailto:jnvenice@up.com), for consultation on railroad requirements during construction. To arrange for flagging, contact Daryl Clark at (708) 649-5273 at least 30 days before flaggers are needed.

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

### **A.4 Temporary Grade Crossing**

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 several weeks prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing.

### **A.5 Train Operation**

Approximately six through freight trains operate daily through the construction site. Through freight trains operate at up to 50 mph.

### **A.6 Temporary Clearances During Construction**

Replace subparagraphs (2) 4.1 and (2) 4.2 of standard spec 107.17.1 with the following:

Provide 12 feet 0 inches plus 1.5 inches per degree of track curvature, measured horizontally from the track center line.

Provide 21 feet 6 inches plus compensation for super-elevated track, measured vertically above the top of the highest rails.

### **B Railroad Flagging**

Arrange with the railroad for the flagging of trains and safety of railroad operations if clearances specified in standard spec 107.17.1 are not maintained during construction operations. The following conditions may also warrant flagging:

1. Cranes swinging or handling materials or equipment within 25 feet of the centerline of any track.
2. Construction operations that are in proximity of power lines or railroad signal and communication lines, underground cables, fuel oil facilities or pipe lines and which might result in fire or damage to such facilities, danger to railroad operations or danger to the public in the transaction of business on railroad premises.
3. Excavation, tunneling, blasting, pile driving, placing, or removing cofferdams or sheeting, or similar activities might cause the railroad's tracks or buildings to be undermined, heaved out of normal level, shifted out of alignment, or otherwise impaired.
4. Bridge painting activities including rigging of falsework, scaffolding or similar activities within 25 feet of the centerline of any track.
5. Deck removal activities within 25 feet of the centerline of any track.
6. Pouring of bridge decks in spans over an operated track.
7. At any other time in railroad representative's judgment, the contractor's work or operations constitute an intrusion into the track zone and create an extraordinary hazard to railroad traffic and at any other time when flagging protection is necessary for safety to comply with the operating rules of the railroad.

Projects with concurrent activity may require more than one flagger.

Projects with heavy contractor activity within 25 feet of the centerline of any track or unusual or heavy impact on railroad facilities will normally require a full-time flagger.

The department and railroad will monitor operations for compliance with the above flagging requirements. Violations may result in removal from railroad property until arrangements to adhere to the flagging requirements are satisfied. If the railroad imposes additional flagging requirements beyond the above flagging requirements due to the

previous violations, the contractor shall bear all costs of the additional flagging requirements.

## **C Flagging by Railroad– Railroad Does Not Pay Flagging Costs**

### **C.1 General**

*Replace paragraph (3) of standard spec 107.17.1 with the following:*

Comply with the railroad's rules and regulations regarding operations on railroad right-of-way. If the railroad's chief engineering officer requires, arrange with the railroad to obtain the services of qualified railroad employees to protect railroad traffic through the work area. Bear the cost of these services and make payment directly to the railroad. Notify the appropriate railroad representative as listed in section A.3 above, in writing, at least thirty business days before starting work near a track. Provide the specific time planned to start the operations.

### **C.2 Rates – BNSF and Union Pacific**

The following rates, reimbursement provisions, and excluded conditions will be used to determine the contractor's cost of flagging:

\$526 daily rate for an eight-hour day (including wages, labor surcharges, meals, lodging, vehicle and mileage expenses),

\$1,054 "Rest Time" or nightly rate for weekday overnight work for an eight-hour day (including wages, labor surcharges, meals, lodging, vehicle and mileage expenses),

\$760 daily rate for an eight-hour day on Saturdays, Sundays or holidays (including wages, labor surcharges, meals, lodging, vehicle and mileage expenses),

\$1,540 "Rest Time" or nightly rate for weekend overnight work for an eight-hour day (including wages, labor surcharges, meals, lodging, vehicle and mileage expenses),

\$88 per hour overtime rate for all time worked before or after the regular assigned eight hours on any day, or for a minimum three hour call on Saturdays, Sundays, or Holidays.

The flagger is required to set flags each day in advance of the contractor commencing work that will require flagging. The flagger must also remove the flags each day after the completion of work that required flagging. Any time worked before or after the minimum eight-hour flagging day to set or remove flags will be billed at the overtime rate. The contractor is responsible for knowing the requirements of the railroad for arranging and terminating flagging services and for the associated costs of those services.

### **C.3 Reimbursement Provisions**

The actual cost for flagging will be billed by the railroad. After the completion of the work requiring flagging protection as provided in section B above, the department will reimburse 50% of the cost of such services up to the rates provided above based on paid railroad invoices, except for the excluded conditions enumerated below. In the event actual flagging rates exceed the rates stated above, the department will reimburse 100% of the portion of the rate that is greater than the rates stated above.

### **C.4 Excluded Conditions**

The department will not reimburse any of the cost for additional flagging attributable to the following:

1. Additional flagging requirements imposed by the railroad beyond the flagging requirements provided in subsection B above due to violations by the contractor.
2. Temporary construction crossings arranged for by the contractor.

The contractor shall bear all costs of the additional flagging requirements for the excluded conditions.

### **C.5 Payment for Flagging**

Railroads may issue progressive bills. Notify the railroad when the work is completed and request a final bill from the railroad. The railroad will issue a final bill. Promptly pay railroad-flagging bills, less any charges that may be in dispute. The department will pay for flagging reimbursement under the Railroad Flagging Reimbursement administrative item. The department will withhold flagging reimbursement until any disputed charges are resolved and the final bill is paid. No reimbursement for flagging will be made by the department if a violation of subsection B is documented.

107-034 (20090901)

## **7. Union Pacific Railroad Requirements.**

### **A General**

In addition to requirements of the standard specifications and other articles within these special provisions, comply with the following requirements of Union Pacific Railroad Company (UPRR).

### **B Request for Information / Clarification**

All requests for information (RFI) involving work within UPRR right-of-way shall be in accordance to the procedures listed elsewhere in the special provisions. Submit all RFIs to the engineer for submittal to UPRR. Allow four weeks for UPRR's review after receipt from the engineer.

### **C Plans / Specifications**

Changes to the plans or specifications are subject to the approval of UPRR. Submit all change requests to the engineer. Allow four weeks for UPRR review time after receipt of a change request from the engineer.

#### **D Construction Submittals**

Submit six sets of the following to the engineer. All design submittals shall be stamped and signed by a professional engineer registered in the State of Wisconsin. The engineer will submit four sets of each submittal, along with any review comments to UPRR. A satisfactory submittal review does not relieve the contractor of responsibility and liability.

The engineer and UPRR may review the submittals. If the engineer or UPRR finds a submittal unsatisfactory, make all required changes and resubmit it. A satisfactory submittal review does not relieve the contractor of responsibility and liability of complying with the plans, specifications and the special provisions and for the structural integrity and proper functioning of the item that is the subject of the submittal. Allow four weeks for UPRR's review time after receipt of a submittal from the engineer.

Item	Description of Submittal Item	Notes
1	Shoring Design and Details	
2	Falsework Design and Details	
3	Drainage Design Provisions	
4	Erection Diagrams and Sequence	
5	Demolition Diagram and Sequence	
6	Shop Drawings	Steel and concrete members.

Whenever work may affect the operations or safety of trains, the method of doing such work shall first be submitted to UPRRs designated representative for review. Review by UPRR shall not relieve the contractor from liability.

#### **E Infringement on Minimum Clearances**

Submit to the engineer requests for infringement upon the minimum horizontal or vertical clearance requirements of standard spec 107.17.1 (2) 4. The engineer will submit the requests to UPRR's designated representative. Allow four weeks for UPRR's review time after receipt of a submittal from the engineer. Do not infringe upon the minimum clearances unless they are first approved in writing by UPRR.

#### **F Approval of Details**

Submit details of construction affecting UPRR tracks, structure, and right-of-way not included in the plans to the engineer for UPRR review before undertaking such work. Allow four weeks for UPRR's review after receipt from the engineer.

#### **G Site Inspections by UPRR**

UPRR may make site inspections at any time. Provide the engineer a schedule of anticipated dates for the following activities; the engineer will furnish the schedule to UPRR:



1. Shoring
2. Demolition
3. Falsework
4. Erection of superstructure
5. Completion of the bridge structure.

Update the schedule monthly, or more frequently if necessary, so that site visits may be scheduled.

### **I Construction Excavations and Demolition**

Construction excavations shall meet OSHA and American Railway Engineering and Maintenance-of-Way Association (AREMA) requirements and the UPRR “Guidelines for Temporary Shoring” (GTS).

Demolition shall be done in accordance to Union Pacific’s Guidelines for Preparation of a Bridge Demolition and Removal Plan for Structures over Railroad (GPBDRP)

The GTS and the GPBDRP are available for review from the North Central Region’s Railroad Coordinator at the department’s North Central Regional Office located at 510 N Hanson Lake Road, Rhineland, Wisconsin 54501.

## **8. Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.**

John Roelke, License Number AII-119523, inspected Structure P-39-0041 for asbestos on June 26, 2007. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: Mike Novey, Local Program Manager at DAAR Engineering, Inc., 608-334-5215.

In accordance to NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days prior to beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Mike Novey, Local Program Manager at DAAR Engineering, Inc., 608-334-5215 and DOT BTS-ESS attn: Hazardous Materials Specialist PO Box 7965, Madison, WI. 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure P-39-0041, 10<sup>th</sup> Road over Union Pacific Railroad
- Site Address: : Section 34, Town 15N., Range 09E., Town of Packwaukee
- Ownership Information: Town of Packwaukee, N2719 Lake Shore Drive, Montello, WI 5394
- Contact: Mike Novey
- Phone: (608) 334-5215
- Age: 73 years old. This structure was constructed in 1940.
- Area: 3310 SF of deck

Insert the following paragraph in Section 6.g.:

- If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response in accordance to standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

107-125 (20120615)

## **9. Debris Containment Structure B-39-74, Item 203.0225.S.01.**

### **A Description**

This special provision describes providing a containment system to prevent debris from structure removal, reconstruction, or other construction operations from falling onto facilities located under the structure. Using this containment system does not relieve the contractor of requirements under standard spec 107.17 and standard spec 107.19 or requirements under a US Army Corps of Engineers Section 404 Permit.

### **B (Vacant)**

### **C Construction**

Prior to starting work, submit a debris containment plan to the engineer for review. Incorporate engineer-requested modifications. Do not start work over over the Union Pacific Railroad until the engineer approves the debris containment plan.

Maintain adequate protection throughout construction for people and property within the potential fall zone. Ensure that a containment system capable of protecting underlying facilities from falling construction debris is in place before beginning deck repair, parapet removal, or other operations that may generate debris.

At least 15 working days before conducting potential debris generating operations, contact the following owners or lessees:

1. John Venice, 301 W. Lake Street, Northlake, IL 60164, (708) 649-5210.

### **D Measurement**

The department will measure Debris Containment Structure B-39-74 as a single lump sum unit of work for each structure, acceptably completed.

### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
203.0225.S.01	Debris Containment Structure B-39-74	LS

Payment is full compensation for furnishing, installing, maintaining, and removing a debris containment system.  
203-010 (20080902)

## **10. QMP Base Aggregate.**

### **A Description**

#### **A.1 General**

- (1) This special provision describes contractor quality control (QC) sampling and testing for base aggregates, documenting those test results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.
- (2) Conform to standard spec 301, standard spec 305, and standard spec 310 as modified here in this special provision. Apply this special provision to material placed under all of the Base Aggregate Dense and Base Aggregate Open Graded bid items, except do not apply this special provision to material classified as reclaimed asphaltic pavement placed under the Base Aggregate Dense bid items.
- (3) Do not apply this special provision to material placed under the Aggregate Detours, Salvaged Asphaltic Pavement Base, Breaker Run, Select Crushed, Pit Run, Subbase, or Riprap bid items.
- (4) Provide and maintain a quality control program, defined as all activities related to and documentation of the following:
  1. Production and placement control and inspection.
  2. Material sampling and testing.
- (5) Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes required sampling and testing procedures. The contractor may obtain the CMM from the department's web site at:

<http://roadwaystandards.dot.wi.gov/standards/cmm/index.htm>

#### **A.2 Contractor Testing for Small Quantities**

- (1) The department defines a small quantity, for each individual Base Aggregate bid item, as a plan quantity of 9000 tons or less of material as shown in the schedule of items under that bid item.
- (2) The requirements under this special provision apply equally to a small quantity for an individual bid item except as follows:
  1. The contractor need not submit a full quality control plan but shall provide an organizational chart to the engineer including names, telephone numbers, and current certifications of all persons involved in the quality control program for material under affected bid items.

2. Divide the aggregate into uniformly sized sublots for testing as follows:

<b>Plan Quantity</b>	<b>Minimum Required Testing</b>
$\leq 1500$ tons	One test from production, load-out, or placement at the contractor's option <sup>[1]</sup>
$> 1500$ tons and $\leq 6000$ tons	Two tests of the same type, either from production, load-out, or placement at the contractor's option <sup>[1]</sup>
$> 6000$ tons and $\leq 9000$ tons	Three placement tests <sup>[2][3]</sup>

<sup>[1]</sup> If using production tests for acceptance, submit test results to the engineer for review prior to incorporating the material into the work. Production test results are valid for a period of 3 years.

<sup>[2]</sup> For 3-inch material, obtain samples at load-out.

<sup>[3]</sup> If the actual quantity overruns 9000 tons, create overrun sublots to test at a rate of one additional placement test for each 3000 tons, or fraction of 3000 tons, of overrun.

3. No control charts are required. Submit aggregate load-out and placement test results to the engineer within one business day of obtaining the sample. Assure that all properties are within the limits specified for each test.

4. Department verification testing is optional for quantities of 6000 tons or less.

(3) Material represented by a subplot with any property outside the specification limits is nonconforming. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

## **B Materials**

### **B.1 Quality Control Plan**

(1) Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not place base before the engineer reviews and comments on the plan. Construct the project as that plan provides.

(2) Do not change the quality control plan without the engineer's review. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in each of the contractor's laboratories as changes are adopted. Ensure that the plan provides the following elements:

1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.
2. The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication means that will be used, and action time frames.
3. A list of source and processing locations, section and quarter descriptions, for all aggregate materials requiring QC testing.
4. Test results for wear, sodium sulfate soundness, freeze/thaw soundness, and plasticity index of all aggregates requiring QC testing. Obtain this information from the region materials unit or from the engineer.

5. Descriptions of stockpiling and hauling methods.
6. Locations of the QC laboratory, retained sample storage, and where control charts and other documentation is posted.
7. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.

## **B.2 Personnel**

- (1) Have personnel certified under the department's highway technician certification program (HTCP) perform sampling, testing, and documentation as follows:

<b>Required Certification Level:</b>	<b>Sampling or Testing Roles:</b>
Aggregate Technician IPP Aggregate Sampling Technician Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Sampling <sup>[1]</sup>
Aggregate Technician IPP Aggregate Assistant Certified Technician (ACT-AGG)	Aggregate Gradation Testing, Aggregate Fractured Particle Testing, Aggregate Liquid Limit and Plasticity Index Testing

<sup>[1]</sup> Plant personnel under the direct observation of an aggregate technician certified at level one or higher may operate equipment to obtain samples.

- (2) A certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

## **B.3 Laboratory**

- (1) Perform QC testing at a department-qualified laboratory. Obtain information on the Wisconsin laboratory qualification program from:

Materials Management Section  
3502 Kinsman Blvd.  
Madison, WI 53704  
Telephone: (608) 246-5388

<http://www.dot.state.wi.us/business/engrserv/lab-qualification.htm>

## **B.4 Quality Control Documentation**

### **B.4.1 General**

- (1) Submit base aggregate placement documentation to the engineer within 10 business days after completing base placement. Ensure that the submittal is complete, neatly organized, and includes applicable project records and control charts.

### **B.4.2 Records**

- (1) Document all placement observations, inspection records, and control adjustments daily in a permanent field record. Also include all test results in the project records. Provide test results to the engineer within 6 hours after obtaining a sample. For 3-inch

base, extend this 6-hour limit to 24 hours. Post or distribute tabulated results using a method mutually agreeable to the engineer and contractor.

#### **B.4.3 Control Charts**

- (1) Plot gradation and fracture on the appropriate control chart as soon as test results are available. Format control charts according to CMM 8.30. Include the project number on base placement control charts. Maintain separate control charts for each base aggregate size, source or classification, and type.
- (2) Provide control charts to the engineer within 6 hours after obtaining a sample. For 3-inch base, extend this 6-hour limit to 24 hours. Post or distribute charts using a method mutually agreeable to the engineer and contractor. Update control charts daily to include the following:
  1. Contractor individual QC tests.
  2. Department QV tests.
  3. Department IA tests.
  4. Four-point running average of the QC tests.
- (3) Except as specified under B.8.2.1 for nonconforming QV tests, include only QC tests in the running average. The contractor may plot process control or informational tests on control charts, but do not include these tests, conforming QV tests, or IA tests in the running average.

#### **B.5 Contractor Testing**

- (1) Test gradation, fracture, liquid limit and plasticity index during placement for each base aggregate size, source or classification, and type.
- (2) Test gradation once per 3000 tons of material placed. Determine random sample locations and provide those sample locations to the engineer. Obtain samples after the material has been bladed, mixed, and shaped but before compacting; except collect 3-inch samples from the stockpile at load-out. Do not sample from material used to maintain local traffic or from areas of temporary base that will not have an overlying pavement. On days when placing only material used to maintain local traffic or only temporary base that will not have an overlying pavement, no placement testing is required.
- (3) Split each contractor QC sample and identify it according to CMM 8.30. Retain the split for 7 calendar days in a dry, protected location. If requested for department comparison testing, deliver the split to the engineer within one business day.
- (4) The engineer may require additional sampling and testing to evaluate suspect material or the technician's sampling and testing procedures.

- (5) Test fracture for each gradation test until the fracture running average is above the lower warning limit. Subsequently, the contractor may reduce the frequency to one test per 10 gradation tests if the fracture running average remains above the warning limit.
- (6) Test the liquid limit and plasticity index for the first gradation test. Subsequently, test the liquid limit and plasticity index a minimum of once per 10 gradation tests.

## **B.6 Test Methods**

### **B.6.1 Gradation**

- (1) Test gradation using a washed analysis conforming to the following as modified in CMM 8.60:  
 Gradation..... AASHTO T 27  
 Material finer than the No. 200 sieve..... AASHTO T 11
- (2) For 3-inch base, if 3 consecutive running average points for the percent passing the No. 200 sieve are 8.5 percent or less, the contractor may use an unwashed analysis. Wash at least one sample out of 10. If a single running average for the percent passing the No. 200 sieve exceeds 8.5 percent, resume washed analyses until 3 consecutive running average points are again 8.5 percent passing or less.
- (3) Maintain a separate control chart for each sieve size specified in standard spec 305 or standard spec 310 for each base aggregate size, source or classification, and type. Set control and warning limits based on the standard specification gradation limits as follows:
  1. Control limits are at the upper and lower specification limits.
  2. There are no upper warning limits for sieves allowing 100 percent passing and no lower control limits for sieves allowing 0 percent passing.
  3. Dense graded warning limits, except for the No. 200 sieve, are 2 percent within the upper and lower control limits. Warning limits for the No. 200 sieve are set 0.5 percent within the upper and lower control limits.
  4. Open graded warning limits for the 1-inch, 3/8-inch, and No. 4 sieves are 2 percent within the upper and lower control limits. Upper warning limits for the No. 10, No. 40, and No. 200 sieves are 1 percent inside the upper control limit.

### **B.6.2 Fracture**

- (1) Test fracture conforming to CMM 8.60. The engineer will waive fractured particle testing on quarried stone.
- (2) Maintain a separate fracture control chart for each base aggregate size, source or classification, and type. Set the lower control limit at the contract specification limit, either specified in another special provision or in table 301-2 of standard spec 301.2.4.5. Set the lower warning limit 2 percent above the lower control limit. There are no upper limits.

### **B.6.3 Liquid Limit and Plasticity**

- (1) Test the liquid limit and plasticity according to AASHTO T 89 and T 90.
- (2) Ensure the material conforms to the limits specified in standard spec table 301-2.

## **B.7 Corrective Action**

### **B.7.1 General**

- (1) Consider corrective action when the running average trends toward a warning limit. Take corrective action if an individual test exceeds the contract specification limit. Document all corrective actions both in the project records and on the appropriate control chart.

### **B.7.2 Placement Corrective Action**

- (1) Do not blend additional material on the roadbed to correct gradation problems.
- (2) Notify the engineer whenever the running average exceeds a warning limit. When 2 consecutive running averages exceed a warning limit, the engineer and contractor will discuss appropriate corrective action. Perform the engineer's recommended corrective action and increase the testing frequency as follows:
  1. For gradation, increase the QC testing frequency to at least one randomly sampled test per 1000 tons placed.
  2. For fracture, increase the QC testing frequency to at least one test per gradation test.
- (3) If corrective action improves the property in question such that the running average after 4 additional tests is within the warning limits, the contractor may return to the testing frequency specified in B.5.3. If corrective action does not improve the property in question such that the running average after 4 additional individual tests is still in the warning band, repeat the steps outlined above starting with engineer notification.
- (4) If the running average exceeds a control limit, material starting from the first running average exceeding the control limit and ending at the first subsequent running average inside the control limit is nonconforming and subject to pay reduction.
- (5) For individual test results significantly outside the control limits, notify the engineer, stop placing base, and suspend other activities that may affect the area in question. The engineer and contractor will jointly review data, data reduction, and data analysis; evaluate sampling and testing procedures; and perform additional testing as required to determine the extent of potentially unacceptable material. The engineer may direct the contractor to remove and replace that material. Individual test results are significantly outside the control limits if meeting one or more of the following criteria:



1. A gradation control limit for the No. 200 sieve is exceeded by more than 3.0 percent.
2. A gradation control limit for any sieve, except the No. 200, is exceeded by more than 5.0 percent.
3. The fracture control limit is exceeded by more than 10.0 percent.

## **B.8 Department Testing**

### **B.8.1 General**

- (1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project, and provide test results to the contractor within 2 business days after the department obtains the sample.

### **B.8.2 Verification Testing**

#### **B.8.2.1 General**

- (1) The department will have an HTCP technician, or ACT working under a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in B.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests of each base aggregate size, source or classification, and type during placement conforming to the following:
  1. One non-random test on the first day of placement.
  2. At least one random test per 30,000 tons, or fraction of 30,000 tons, placed.
- (3) The department will sample randomly, at locations independent of the contractor's QC work, collecting one sample at each QV location. The department will collect QV samples after the material has been bladed, mixed, and shaped but before compacting; except, for 3-inch aggregates, the department will collect samples from the stockpile at load-out. The department will split each sample, test half for QV, and retain half.
- (4) The department will conduct QV tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing.
- (5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to the specification, the department will take no further action. If QV test results are nonconforming, add the QV to the QC test results as if it were an additional QC test.

#### **B.8.3 Independent Assurance**

- (1) Independence assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing including personnel qualifications, procedures, and equipment. The department will perform an IA review

according to the department's independent assurance program. That review may include one or more of the following:

1. Split sample testing.
  2. Proficiency sample testing.
  3. Witnessing sampling and testing.
  4. Test equipment calibration checks.
  5. Reviewing required worksheets and control charts.
  6. Requesting that testing personnel perform additional sampling and testing.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in B.9.

### **B.9 Dispute Resolution**

- (1) The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E 178 to evaluate potential statistically outlying data.
- (2) Production test results, and results from other process control testing, may be considered when resolving a dispute.
- (3) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating non-conforming product, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

### **C (Vacant)**

### **D (Vacant)**

### **E Payment**

- (1) Costs for all sampling, testing, and documentation required under this special provision are incidental to this work. If the contractor fails to perform the work required under this special provision, the department may reduce the contractor's pay. The department will administer pay reduction under the non-performance of QMP administrative item.

- (2) For material represented by a running average exceeding a control limit, the department will reduce pay by 10 percent of the contract price for the affected Base Aggregate bid items listed in subsection A. The department will administer pay reduction under the Nonconforming QMP Base Aggregate Gradation or Nonconforming QMP Base Aggregate Fracture Administrative items. The department will determine the quantity of nonconforming material as specified in B.7.2.

301-010 (20100709)

## **11. Temporary Sediment Trap, Item SPV.0060.01.**

### **A Description**

This special provision describes providing a Temporary Sediment Trap to manage sediment-laden runoff.

### **B (Vacant)**

### **C Construction**

Use the Department of Natural Resources Storm Water Management Technical Standard on Sediment Traps (Standard Number 1063) as found on their website at “[www.dnr.wi.gov/runoff/stormwater/techstds.htm](http://www.dnr.wi.gov/runoff/stormwater/techstds.htm)” for the appropriate best management practice and proper application and sizing of such practice. As part of the Erosion Control Implementation Plan (ECIP) submittal, supply all pertinent information and calculations used to determine the best management practice, including sizing calculations, for capturing sediment at each location as required. Prior to construction, obtain approval from the engineer for the proposed method of treatment including supporting calculations.

Construct a sediment trap of sufficient size to detain sediment-laden runoff from disturbed areas for sufficient time to allow the majority of sediment to settle out. Alternate methods to trap sediment from those detailed in the plans are acceptable, provided the performance of the alternative method is comparable to the detail proposed in the plan.

The dimensions, exact location and outlet configuration of the sediment trap must be approved by the engineer prior to construction. The sediment trap may be constructed with rock filter bags for the walls and type DF geotextile as the basin liner. Place a clear washed stone in the bottom of the basin to hold the geotextile liner in place.

### **D Measurement**

The department will measure Temporary Sediment Trap as each individual sediment trap, acceptably completed.

### **E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Temporary Sediment Trap	Each

Payment is full compensation for furnishing all materials including: excavation; rock bags; fabrics; filtering materials; maintenance; cleaning; disposal of surplus material; and for removal of the sediment trap after all seeded areas are established.

## **12. Temporary Shoring Railroad, Item SPV.0105.01.**

### **A Description**

This special provision describes furnishing and installing or constructing temporary shoring at locations alongside railroad tracks as shown in the plan and in accordance to the shoring design

### **B Materials**

#### **B.1 Shoring Design**

Provide an effective shoring system capable of withstanding Coopers E-80 live load surcharge, and which is in compliance with OSHA and Federal Railroad Administration (FRA) requirements. For reference, use “Guidelines For Temporary Shoring” published by Union Pacific Railroad and The Burlington Northern and Santa Fe Railway (BNSF). A copy of these guidelines may be obtained from the department at the Bureau of Railroads and Harbors, 4802 Sheboygan Avenue, Room 701, Madison, Where conflicts exist, the standard specifications, special provisions and plans shall supercede these guidelines.

Refer to standard spec 107.17(5) and (6) regarding the development and submittal of shop drawings, detailed plans, and computations for temporary construction near the BNSF’s tracks. Include in the submitted drawings and plans the proposed method of installation and removal of the shoring not included in the contract plans. In all calculations, take into consideration railroad surcharge loading and design the shoring to meet Coopers E-80 live loading.

### **C Construction**

The contractor shall coordinate construction with train operations, consistent with its operational requirements. The number and duration of work windows free of train operations available per day will vary depending on operational requirements. At the end of each window, leave the construction area in a condition that will allow for safe and normal train operations. Do not leave shoring extended above the top of rail within 12’-0” from the centerline of the nearest track. Train operations and available windows for work and hours available for work within windows are subject to change. Contact John Venice at, Union Pacific Railroad, 301 West Lake Street, Northlake, IL 60164, (708) 649-5210, at least three working days in advance of construction operations that require implementation of the temporary shoring.

Provide, install and maintain adequate protection for people within the Union Pacific right-of-way. Cover, guard, and/or protect all excavations, holes, or trenches within the Union Pacific right-of-way when they are not being worked on. When leaving work site areas at night and over weekends, secure the areas and leave them in a condition that will ensure that railroad employees and other personnel, who may be working or passing

through the area, are protected around excavations. Install handrails that are parallel to the track and not less than 9'-0" from the centerline of the nearest track. Handrails, fences, or other barrier methods must meet OSHA and FRA requirements. Backfill all excavations as soon as possible.

Upon completion of the need for the temporary shoring at the required location, remove the shoring or cut-off the shoring 4'-6" below the top of the adjacent rail. Backfill the space that is excavated but not occupied by the new permanent construction in accordance to standard spec 206.3.13.

#### **D Measurement**

The department will measure Temporary Shoring Railroad as a single complete lump sum unit of work for each structure, acceptably completed.

#### **E Payment**

The department will pay for the measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.01	Temporary Shoring Railroad	LS

Payment is full compensation for providing a verified design of the shoring; providing a copy of the design; furnishing and hauling materials to each location; installing or constructing the shoring; maintaining the shoring as needed; removing the shoring when required by the design; backfilling upon completion of the need for the shoring; and for furnishing all labor, tools, equipment, materials, and incidentals needed to complete the contract work.



#### **ADDITIONAL SPECIAL PROVISION 4**

Payment to all Subcontractors. Within 10 calendar days of receipt by a contractor of a progress payment for work performed, materials furnished, or materials stockpiled by a subcontractor, the contractor shall pay that subcontractor for all work satisfactorily performed and for all materials furnished or stockpiled.

The contractor agrees further to release retainage amounts to each subcontractor within 10 calendar days after the subcontractor's work is satisfactorily completed. In addition, whenever the Department reduces the contract retainage amount, within 10 calendar days of receipt by a contractor of a retainage payment, the contractor must reduce the total amount retained from subcontractors to no more than remains retained by the Department.

The contractor shall pay the subcontractor within the time frames described above unless the contractor complies with both of the following within 10 calendar days of receiving the Department's progress payment:

- 1) The contractor notifies the subcontractor in writing that the work is not satisfactorily completed.
- 2) The contractor requests approval from the Department to delay payment because the subcontractor has not satisfactorily completed the work.

The contractor's request for approval should include the written notification to the subcontractor and shall provide sufficient documentation of good cause to assist the engineer in making a timely decision. If the engineer does not grant approval, the contractor shall pay the subcontractor within 10 calendar days of the Department's decision.

All subcontracting agreements made by a contractor shall include the above provisions and shall be binding on all contractors and subcontractors.

The contractor certifies compliance with the requirements of this Additional Special Provision by signing the contract. This clause applies to both DBE and non-DBE subcontractors.





**ADDITIONAL SPECIAL PROVISION 6****ASP 6 - Modifications to the standard specifications**

*Make the following revisions to the 2013 edition of the standard specifications:*

---

**106.3.4.3.1 General**

*Replace paragraph two with the following effective with the November 2012 letting:*

- (2) Required sampling and testing methodologies and documentation are specified in CMM chapter 8.
  - (3) If disputed, approval of materials and components, as well as acceptance of the work incorporating those materials or components, is subject to review under the QMP dispute resolution process.
- 

**107.17.3 Railroad Insurance Requirements**

*Replace the entire text with the following effective with the August 2012 letting:*

- (1) If required by the special provisions, provide or arrange for a subcontractor to provide railroad protective liability insurance in addition to the types and limits of insurance required in 107.26. Keep railroad protective liability insurance coverage in force until completing all work, under or incidental to the contract, on the railroad right of way or premises of the railroad and until the department has accepted the work as specified in 105.11.2.4.
- (2) Provide railroad protective liability insurance coverage written as specified in 23 CFR part 646 subpart A. Provide a separate policy for each railroad owning tracks on the project. Ensure that the railroad protective liability insurance policies provide the following minimum limits of coverage:
  - 1. Coverage A, bodily injury liability and property damage liability; \$2 million per occurrence.
  - 2. Coverage B, physical damage to property liability; \$2 million per occurrence.
  - 3. An annual aggregate amount of \$6 million that shall apply separately to each policy renewal or extension.
- (3) Obtain coverage from insurance companies licensed to do business in Wisconsin that have an A.M. Best rating of A- or better. The cost of providing the required insurance coverage and limits is incidental to the contract. The department will make no additional or special payment for providing insurance.
- (4) Submit the following to each railroad owning tracks on the project as evidence of that railroad's respective coverage:
  - 1. A certificate of insurance for the types and limits of insurance specified in 107.26.
  - 2. The railroad protective liability insurance policy or other acceptable documentation to the railroad company.
- (5) Submit the following to the region as evidence of the required coverage:
  - 1. A copy of the letter to the railroad company transmitting the submittal documents specified in 107.17.3(4).
  - 2. A certificate of insurance for the required railroad protective liability coverages.
- (6) Do not begin work on the right of way or premises of the railroad company until the region receives the submittals specified in 107.17.3(5) and notification from the railroad company that the contractor has provided sufficient insurance information to begin work.
- (7) Notify the railroad and the region immediately upon cancellation or initiating cancellation, whichever is earlier, or any material change in coverage. Cease operations within 50 feet of the railroad right of way immediately if insurance is cancelled or reduced. Do not resume operations until the required coverage is in force.

**460.2.8.3.1.4 Department Verification Testing Requirements**

Replace paragraph four with the following effective with the December 2012 letting:

- (4) The department will randomly test each design mixture at the following minimum frequency:
- FOR TONNAGES TOTALING:
- Less than 501 tons ..... no tests required
- From 501 to 5,000 tons..... one test
- More than 5,000 tons..... add one test for each additional 5,000-ton increment

**501.2.1 Portland Cement**

Replace paragraph one with the following effective with the March 2013 letting:

- (1) Use cement conforming to ASTM specifications as follows:
- Type I portland cement; ASTM C150.
  - Type II portland cement; ASTM C150.
  - Type III portland cement; ASTM C50, for high early strength.
  - Type IP portland-pozzolan cement; ASTM C595, except maximum loss on ignition is 2.0 percent.
  - Type IS portland blast-furnace slag cement; ASTM C595.
  - Type IL portland-limestone cement; ASTM C595, except maximum nominal limestone content is 10 percent with no individual test result exceeding 12.0 percent.

**501.2.5.5 Sampling and Testing**

Replace the entire text with the following effective with the January 2013 letting:

- (1) Sample and test aggregates for concrete according to the following:
- |   |                           |
|---|---------------------------|
| Sampling aggregates .....   | AASHTO T2                 |
| Lightweight pieces in aggregate .....                               | AASHTO T113               |
| Material finer than No. 200 sieve .....                             | AASHTO T11                |
| Unit weight of aggregate .....                                      | AASHTO T19                |
| Organic impurities in sands .....                                   | AASHTO T21                |
| Sieve analysis of aggregates .....                                  | AASHTO T27                |
| Effect of organic impurities in fine aggregate .....                | AASHTO T71                |
| Los Angeles abrasion of coarse aggregate .....                      | AASHTO T96                |
| Freeze-thaw soundness of coarse aggregate.....                      | AASHTO T103               |
| Sodium sulfate soundness of aggregates.....                         | AASHTO T104               |
| Specific gravity and absorption of fine aggregate .....             | AASHTO T84                |
| Specific gravity and absorption of coarse aggregate .....           | AASHTO T85                |
| Flat & elongated pieces based on a 3:1 ratio.....                   | ASTM D4791 <sup>[1]</sup> |
| Sampling fresh concrete .....                                       | AASHTO R60                |
| Making and curing concrete compressive strength test specimens..... | AASHTO T23                |
| Compressive strength of molded concrete cylinders .....             | AASHTO T22                |

<sup>[1]</sup> As modified in CMM 8-60.

**501.2.6 Fly Ash**

Replace paragraph three with the following effective with the March 2013 letting:

- (3) Test fly ash using a recognized laboratory, as defined in 501.2.2(1), starting at least 30 days before its proposed use, and continuing at ASTM-required frequencies as the work progresses. The manufacturer shall test the chemical and physical properties listed in tables 1 and 2 of ASTM C618 at the frequencies and by the test methods prescribed in ASTM C311.

---

**501.3.1.1.1 Air-Entrained Concrete**

Replace paragraph one with the following effective with the March 2013 letting:

- (1) Prepare air-entrained concrete with type I, IL, II, IS, or IP portland cement and sufficient air-entraining admixture to produce concrete with the air content specified in 501.3.2.4.

---

**503.2.2 Concrete**

Replace paragraph five with the following effective with the March 2013 letting:

- (5) Furnish prestressed concrete members cast from air-entrained concrete, except I-type girders may use non-air-entrained concrete. Use type I, IL, IS, , IP, II, or III portland cement. The contractor may replace up to 30 percent of type I, IL, II, or III portland cement with an equal weight of fly ash, slag, or a combination of fly ash and slag, except for prestressed box girders and slabs, the contractor shall replace 20-30 percent of the cement with fly ash, slag, or a combination of fly ash and slag. Ensure that fly ash conforms to 501.2.6 and slag conforms to 501.2.7. Use only one source and replacement rate for work under a single bid item. Use a department-approved air-entraining admixture conforming to 501.2.2 for air-entrained concrete. Use only size No. 1 coarse aggregate conforming to 501.2.5.4.

---

**506.3.22 Shop Inspection**

Replace paragraph one with the following effective with the July 2010 letting:

- (1) The engineer or an independent inspection agency under department contract may inspect all structural steel and miscellaneous metals furnished. The department will provide the contractor with monthly consultant inspection invoices and identify any quality deficiencies at the fabrication facility.

---

**506.5 Payment**

Add paragraph nine as follows effective with the June 2010 letting:

- (9) The department will limit costs for inspections conducted under 506.3.2 to \$0.05 per pound of material and deduct costs in excess of that amount from payment due the contractor. The department will determine costs for in-house inspections based on hourly rates for department staff plus overhead and use invoiced costs for contracted-out inspections. The department will administer deductions for the contractor's share of the total inspection cost under the Excess Costs For Fabrication Shop Inspection administrative item.

---

**507.2.2.1 General**

Replace paragraph four with the following effective with the December 2012 letting:

- (4) Ensure that there are no unsound knots or knot holes. Also ensure that there are no tight knots of a diameter exceeding one-quarter of the greater dimension at the point where they occur. Measure a knot by taking its diameter at right angles to the length of the timber. Ensure that the sum of sizes of all knots in any one-foot length does not exceed 2 times the size of the largest allowed single knot. The engineer will treat cluster knots as if they were a single knot. A cluster knot is 2 or more knots grouped together, with the fibers of the wood deflected around the entire unit.

---

**512.3.1 Driving and Cutting Off**

Replace the entire text with the following effective with the December 2012 letting:

**512.3.1.1 General**

- (1) Coordinate driving operations to prevent damage or displacement of concrete in substructure units or damage to adjacent facilities due to vibrations.
- (2) Drive sheeting with a variation of 1/4 inch or less per foot from the vertical or from the batter the plans show. Ensure that the sheetpiles are within 6 inches of the plan position after driving. Do not damage sheetpiles attempting to correct for misalignment.

- (3) Remove and replace, or otherwise correct, sheetpiles the engineer deems unacceptable under 105.3. Submit details of planned corrections to the engineer for review and approval before initiating any corrective actions.
- (4) Drive sheetpiles to or beyond the required tip elevation the plans show.

#### **512.3.1.2 Driving System**

- (1) Furnish a sheetpile driving system capable of driving the sheetpiles to the required minimum tip elevation the plans show.
- (2) The engineer may order the contractor to remove a pile driving system component from service if it causes insufficient energy transfer or damages the sheetpiles. Do not return a component to service until the engineer determines that it has been satisfactorily repaired or adjusted.
- (3) Drive sheetpiles with diesel, air, steam, gravity, hydraulic, or vibratory hammers.

#### **512.3.1.3 Cut-Offs**

- (1) Cut off sheetpiles at the elevations the plans show or as the engineer directs. Pile cut-offs become the property of the contractor. Dispose of cut-offs not incorporated into the work.

### **518.2.1 General**

Replace paragraph one with the following effective with the March 2013 letting:

- (1) Furnish portland cement and water as specified in 501.2. Unless the engineer allows an alternate, use either type I, IL, IS, , or IP portland cement.

### **526.3.3 Temporary Structures**

Replace paragraphs two through four with the following effective with the January 2013 letting:

- (2) Inspect temporary structures conforming to the National Bridge Inspection Standards (NBIS) and the department's structure inspection manual before opening to traffic. Perform additional inspections, as the department's structure inspection manual requires, based on structure type and time in service. Submit inspection reports on department form DT2007 to the engineer and electronic copies to the department's bureau of structures maintenance section. Ensure that a department-certified active team leader, listed online in the department's highway structures information system (HSIS), performs the inspections.
- (3) Maintain temporary structures and approaches in place until no longer needed. Unless the engineer directs otherwise, completely remove and dispose of as specified in 203.3.4. Contractor-furnished materials remain the contractor's property upon removal.

### **614.2.5 Wood Posts and Offset Blocks**

Retitle and replace the entire text with the following effective with the July 2012 letting:

#### **614.2.5 Posts and Offset Blocks**

##### **614.2.5.1 Wood Posts and Offset Blocks**

- (1) Furnish sawed posts and offset blocks of one of the following species:
 

Douglas fir	Southern pine	Ponderosa pine	Jack pine	White pine
Red pine	Western hemlock	Western larch	Hem-fir	Oak
- (2) Ensure that posts are the size the plans show and conform to the nominal and minimum dimensions tabulated in 507.2.2.3. The contractor does not have to surface the posts. Provide posts of the net length the plans show after setting and cut off.
- (3) Use stress graded posts rated at 1200 psi  $f_b$  or higher. Determine the stress grade rating for douglas fir, western larch, and southern pine as specified in 507.2.2.4.
- (4) For hem-fir, hemlock, red pine, white pine, jack pine, ponderosa pine, and oak conform to the following:

TABLE 614-1 PROPERTIES FOR WOOD POSTS AND BLOCKS

SPECIES			WESTERN HEMLOCK, HEM-FIR, RED PINE, WHITE PINE, JACK PINE, PONDEROSA PINE		OAK	
MAXIMUM SLOPE OF GRAIN			1 in 15		1 in 12	
NOMINAL WIDTH OF FACE			6"	8"	6"	8"
SHAKES, CHECKS, AND SPLITS	GREEN		1"	1 3/8"	2 3/8"	3 1/8"
	SEASONED		1 1/2"	2"	2 5/8"	3 1/2"
MAXIMUM WANE			1"	1 3/8"	1 1/8"	1 5/8"
MAXIMUM ALLOWABLE KNOTS	NARROW FACE	MIDDLE 1/3 OF LENGTH	1 3/8"	1 5/8"	2 1/8"	2 3/8"
		END <sup>[1]</sup>	2 3/4"	3 1/4"	4 1/4"	4 3/4"
		SUM IN MIDDLE 1/2 OF LENGTH <sup>[2]</sup>	11"	13"	17"	19
	WIDE FACE	EDGE KNOT N MIDDLE 1/3 OF LENGTH	1 3/8"	1 5/8"		
		EDGE KNOT AT END <sup>[1]</sup>	2 3/4" 7	3 1/4"		
		CENTERLINE	1 3/8"	1 7/8"	2 1/4"	2 7/8"
		SUM IN MIDDLE 1/2 OF LENGTH	5 1/2"	7 1/2"	9"	11 1/2"

<sup>[1]</sup> But do not exceed the maximum allowable knot on the centerline of the wide face of the same piece.

<sup>[2]</sup> But do not exceed 4 times the maximum allowable knot on the centerline of the wide face of the same piece.

- (5) Pressure treat posts and offset blocks as specified in 507.2.2.6. Use one of the oil-soluble preservatives or chromated copper arsenate conforming to 507.2.3. Use the same material for offset blocks and posts and treat material used in each continuous installation with the same type of preservative.

#### 614.2.5.2 Steel Posts

- (1) Furnish steel posts conforming to AASHTO M270 Grade 36 and galvanized according to AASTHO M111.

#### 614.2.5.3 Plastic Offset Blocks

- (1) Furnish plastic offset blocks from the department's approved products list.

### 614.3.1 General

Replace the entire text with the following effective with the July 2012 letting:

- (1) Paint the ends of cut-off galvanized posts, rail, bolts, cut or drilled surfaces of galvanized components, and areas of damaged zinc coating with 2 coats of zinc dust/zinc oxide paint. Clean the damaged and adjacent areas thoroughly before applying paint.
- (2) Apply 2 coats of wood preservative to cut surfaces of wood components. Use the same preservative originally used to treat that component or use a 2-percent solution of copper naphthenate conforming to AWWA Standard P8 or P36.

#### 614.3.2.1 Installing Posts

Replace paragraph four with the following effective with the July 2012 letting:

- (4) Cut post tops to the finished elevation the plans show.

**628.2.13 Rock Bags**

*Replace paragraph one with the following effective with the November 2012 letting:*

- (1) Furnish rock bags made of a porous, ultraviolet resistant, high-density polyethylene or geotextile fabric that will retain 70% of its original strength after 500 hours of exposure according to ASTM D4355 and a minimum in-place filled size of 18-inches long by 12-inches wide by 6-inches high. Ensure that the fabric conforms to the following:

TEST REQUIREMENT	METHOD	VALUE
Minimum Tensile	ASTM D4632	
Machine direction		70 lb minimum
Cross direction		40 lb minimum
Elongation	ASTM D4632	
Machine direction		20% minimum
Cross direction		10 % min
Puncture	ASTM 4833	65 lbs minimum
Minimum Apparent Opening		0.0234 inches (No. 30 sieve)
Maximum Apparent Opening		0.0787 inches (No. 10 sieve)

**639.2.1 General**

*Replace paragraph two with the following effective with the March 2013 letting:*

- (2) For grout use fine aggregate conforming to 501.2.5.3 and type I, IL, IS, or IP portland cement.

**649.3.1 General**

*Replace paragraphs three and four with the following effective with the March 2013 letting:*

- (3) For pavements open to all traffic, apply centerline and no-passing barrier line markings as follows:
- On intermediate pavement layers, including milled surfaces, on the same day the pavement is placed or milled.
  - On the upper layer of pavement, on the same day the pavement is placed unless the contractor applies permanent marking on the same day the pavement is placed.

If weather conditions preclude same-day application, apply as soon as weather allows. Do not resume next-day construction operations until these markings are completed unless the engineer allows otherwise.

- (4) If required to apply no passing zone temporary pavement marking, reference the beginning and end of all existing no-passing barrier lines. Apply temporary no-passing barrier lines at those existing locations. If the contract contains the Locating No-Passing Zones bid item, relocate the no-passing zones as specified in section 648 for permanent marking.

**701.4.2 Verification Testing**

*Replace paragraph two with the following effective with the December 2012 letting:*

- (2) The department will sample randomly at locations independent of the contractor's QC tests and use separate equipment and laboratories. The department will conduct a minimum of one verification test for each 5 contractor QC tests unless specific QMP provisions specify otherwise.

**715.2.3.1 Pavements**

*Replace paragraph two with the following effective with the March 2013 letting:*

- (2) Provide a minimum cement content of 565 pounds per cubic yard, except if using type I, IL, or III portland cement in a mix where the geologic composition of the coarse aggregate is primarily igneous or metamorphic materials, provide a minimum cement content of 660 pounds per cubic yard.

---

**715.3.1.3 Department Verification Testing**

Replace paragraph one with the following effective with the December 2012 letting:

- (1) The department will perform verification testing as specified in 701.4.2 except as follows:
  - Air content, slump, and temperature: a minimum of 1 verification test per lot.
  - Compressive strength: a minimum of 1 verification test per lot.

---

**Errata**

---

Make the following corrections to the 2013 edition of the standard specifications:

---

**102.12 Public Opening of Proposals**

Correct 102.12(1) errata by changing htm to shtm in the web link.

- (1) The department will publicly open proposals at the time and place indicated in the notice to contractors. The department will post the total bid for each proposal on the Bid Express web site beginning at 9:30 AM except as specified in 102.8. If a proposal has no total bid shown, the department will not post the bid. After verification for accuracy under 103.1, the department will post bid totals on the department's HCCI web site.

<http://roadwaystandards.dot.wi.gov/hcci/bid-letting/index.shtm>

---

**107.22 Contractor's Responsibility for Utility Facilities, Property, and Services**

Correct errata by eliminating references to the department. Costs are determined by statute.

- (3) If the contractor damages or interrupts service, the contractor shall notify the utility promptly. Coordinate and cooperate with the utility in the repair of the facility. Determine who is responsible for repair costs according to Wisconsin statutes 66.0831 and 182.0175(2).
- 

**204.3.2.2 Removing Items**

Correct errata by changing the reference from 490.3.2 to 490.3.

- (5) Under the Removing Asphaltic Surface Milling bid item, remove and dispose of existing asphaltic pavement or surfacing by milling at the location and to the depth the plans show. Mill the asphaltic pavement or surfacing as specified for milling salvaged asphaltic pavement in 490.3.
- 

**501.2.9 Concrete Curing Materials.**

Correct errata by changing AASHTO M171 to ASTM C171.

- (4) Furnish polyethylene-coated burlap conforming to ASTM C171 for white burlap-polyethylene sheets.
- 

**506.2.6.5.2 Pad Construction**

Correct errata by changing ASTM A570 to ASTM A1011.

- (4) For the internal steel plates use rolled mild steel conforming to ASTM A36, or ASTM A1011 grade
- 

**512.3.3 Painting**

Correct errata by changing 511.3.5 to 550.3.11.3.

- (1) Paint permanent steel sheet piling as specified for painting steel piling in 550.3.11.3.

**513.2.2.8 Toggle Bolts**Correct errata by changing ASTM A570 to ASTM A1011.

- (1) Use toggle bolts made of steel, conforming to the plans. Make the assembly from the material specified below:

Toggle bolt and pin ..... Cold finished steel heat-treated Brinell 311-363 ASTM A354.  
 Toggle washer ..... Hot rolled steel ASTM A1011. Manufacturer's standard washer.  
 Spacer nut ..... Grade 1213, ASTM A108. Cold finished steel heat-treated ASTM A325.

**660.2.1 General**Correct errata by changing section 511 to 550.

- (1) Furnish materials conforming to the following:

Concrete ..... section 501  
 Concrete bridges ..... section 502  
 Luminaires ..... section 659  
 Steel piling ..... section 550  
 Steel reinforcement ..... section 505

**660.3.2.3 Pile Type Foundations**Correct errata by changing section 511 to 550.

- (1) Drive piles as specified in for steel piling in section 550.

**701.3 Contractor Testing**Correct errata by updating AASHTO T141 to AASHTO R60 and changing AASHTO T309 to ASTM C1064.

- (1) Perform contract required QC tests for samples randomly located according to CMM 8-30. Also perform other tests as necessary to control production and construction processes, and additional testing enumerated in the contractor's quality control plan or that the engineer directs. Use test methods as follows:

**TABLE 701-2 TESTING STANDARDS**

TEST	TEST STANDARD
Washed P 200 analysis	AASHTO T11 <sup>[1]</sup>
Sieve analysis of fine and coarse aggregate	AASHTO T27 <sup>[1]</sup>
Aggregate moisture	AASHTO T255 <sup>[1]</sup>
Sampling freshly mixed concrete	AASHTO R60
Air content of fresh concrete	AASHTO T152 <sup>[2]</sup>
Concrete slump	AASHTO T119 <sup>[2]</sup>
Concrete temperature	ASTM C1064
Concrete compressive strength	AASHTO T22
Making and curing concrete cylinders	AASHTO T23
Standard moist curing for concrete cylinders	AASHTO M201

<sup>[1]</sup> As modified in CMM 8-60.

<sup>[2]</sup> As modified in CMM 8-70.



**ADDITIONAL SPECIAL PROVISION 7**

- A. Reporting 1<sup>st</sup> Tier and DBE Payments During Construction
1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
  2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
  3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
  4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
  5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
  6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.



**ADDITIONAL SPECIAL PROVISION 9  
Electronic Certified Payroll Submittal**

(1) Use the department's Civil Rights Compliance System (CRCS) to submit certified payrolls electronically. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

<http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/index.shtm>

(2) Ensure that all tiers of subcontractors, as well as all trucking firms, submit their weekly certified payrolls electronically through CRCS. These payrolls are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin payrolls. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Tess Mulrooney at 608-267-4489 to schedule the training.

(4) The department will reject all paper submittals of forms DT-1816 and DT-1929 for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll data from their computer system into CRCS should have their payroll coordinator send several sample electronic files to Tess two months before a payroll needs to be submitted. Not every contractor's payroll system is capable of producing export files. For details, see section 3.2 of the CRCS System Background Information manual available online on the Labor, Wages, and EEO Information page at:

<http://roadwaystandards.dot.wi.gov/hcci/labor-wages-eeo/docs/crc-basic-info.pdf>



**Effective with September 2004 Letting**

**WISCONSIN DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS AND TRANSPORTATION FACILITIES**

**SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS**

- I. Wage Rates, Hours of labor and payment of Wages
- II. Payroll Requirements
- III. Postings at the Site of the Work
- IV. Affidavits
- V. Wage Rate Redistribution
- VI. Additional Classifications

**I. WAGE RATES, HOURS OF LABOR AND PAYMENT OF WAGES**

The schedule of "Minimum Wage Rates" attached hereto and made a part hereof furnishes the prevailing wage rates that have been determined pursuant to Section 103.50 of the Wisconsin Statutes. These wage rates are the minimum required to be paid to the various laborers, workers, mechanics and truck drivers employed by contractors and subcontractors on the construction work embraced by the contract and subject to prevailing hours and wages under Section 103.50, Stats. If necessary to employ laborers, workers, mechanics or truck drivers whose classification is not listed on the schedule, they shall be paid at rates conformable to those listed for similar classifications. Apprentices shall be paid at rates not less than those prescribed in their state indenture contracts.

While the wage rates shown are the minimum rates required by the contract to be paid during its life, this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price shall be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

Pursuant to Section 103.50 of the Wisconsin Statutes, the prevailing hours of labor have been determined to be up to 10 hours per day and 40 hours per calendar week Monday through Friday. If any laborer, worker, mechanic or truck driver is permitted or required to work more than the prevailing number of hours per day or per calendar week on this contract, they shall be paid for all hours in excess of the prevailing hours at a rate of at least one and one-half (1 1/2) times their hourly rate of pay. All work on Saturday, Sunday and the following holidays is to be paid at time and a half: (1) January 1, (2) the last Monday in May, (3) July 4, (4) the first Monday in September, (5) the fourth Thursday in November, (6) December 25, (7) the day before if January 1, July 4 or December 25 falls on a Saturday and (8) the day following if January 1, July 4 or December 25 falls on a Sunday.

All laborers, workers, mechanics and truck drivers shall be paid unconditionally not less often than once a week. Persons who own and operate their own trucks must receive the prevailing truck driver rate for the applicable type of truck (i.e. 2 axle, 3 or more axle, articulated, eculid or dumptor) he or she operates, plus an agreed upon amount for the use of his or her truck. Every owner-operator MUST be paid separately for their driving and for the use of their truck.

For those projects subject to the requirements of the Davis-Bacon Act, the Secretary of Labor will also have determined "Minimum Wage Rates" for work to be performed under the contract. These rates are, for all or most of the labor, worker, mechanic or truck driver classifications, identical to those established under Section 103.50 of the Wisconsin Statutes. In the event the rates are not identical, the higher of the two rates will govern.

## **II. PAYROLL REQUIREMENTS**

All contractors and subcontractors must submit weekly Certified Payrolls and Compliance Statement verifying that all laborers, workers, mechanics and truck drivers working on the project have been paid the prevailing wage rates for all work performed under the contract required by Section 103.50 of the Wisconsin Statutes.

## **III. POSTINGS AT THE SITE OF THE WORK**

In addition to the required postings furnished by the Department, the contractor shall post the following in at least one conspicuous place at the site of work:

- a. "NOTICE TO EMPLOYEES," which provides information required to be posted by the provisions of Section 103.50 of the Wisconsin Statutes.
- b. A copy of the State of Wisconsin Minimum Wages Rates. (Four pages.)
- c. A copy of the contractor's Equal Employment Opportunity Policy.
- d. On any project involving federal aid, in addition to the furnished postings, the contractor shall post a copy of the "Davis-Bacon Act, Minimum Wage Rates". (Three pages.)

## **IV. WAGE RATE REDISTRIBUTION**

The amount specified as the hourly basic rate of pay and the amount(s) specified as the fringe benefit contribution(s), for all classes of laborers, workers, mechanics or truck drivers may be redistributed, when necessary, to conform to those specified in any applicable collective bargaining agreement, provided that both parties to such agreement

request and receive the approval for any such redistribution from both the Department of Transportation and the Department of Workforce Development prior to the implementation of such redistribution.

## **V. ADDITIONAL CLASSIFICATIONS**

Any unlisted laborer or mechanic classification that is needed to perform work on this project, and is not included within the scope of any of the classifications listed in the application prevailing wage rate determination, may be added after award only if all of the following criteria have been met:

1. The affected employer(s) must make a written request to WisDOT Central Office to utilize the unlisted classification on this project.
2. The request must indicate the scope of the work to be performed by the unlisted classification and must indicate the proposed wage/fringe benefit package that the unlisted classification is to receive.
3. The work to be performed by the unlisted classification must not be performed by a classification that is included in the applicable prevailing wage rate determination.
4. The unlisted classification must be commonly employed in the area where the project is located.
5. The proposed wage/fringe benefit package must bear a reasonable relationship to those set forth in the applicable prevailing wage rate determination.
6. The request should be made prior to the actual performance of the work by the unlisted classification.
7. DWD must approve the use of the unlisted classification and the proposed wage/fringe benefit package. USDOL also must approve the use of the unlisted classification and the proposed wage/fringe benefit package on federal aid projects.
8. WisDOT and DWD may amend the proposed wage/fringe benefit package, as deemed necessary, and may set forth specific employment ratios and scope of work requirements in the approval document.

The approved wage/fringe benefit package shall be paid to all laborers, workers, mechanics or truck drivers performing work within the scope of that performed by the unlisted classification, from the first day on which such work is performed. In the event that work is performed by the unlisted classification prior to approval, the wage/fringe benefit package to be paid for such work must be in conformance with the wage/fringe

benefit package approved for such work. Under this arrangement a retroactive adjustment in wages and/or fringe benefits may be required to be made to the affected laborers, workers, mechanics or truck drivers by the affected employer(s).



**ANNUAL PREVAILING WAGE RATE DETERMINATION  
FOR ALL STATE HIGHWAY PROJECTS  
MARQUETTE COUNTY**

Compiled by the State of Wisconsin - Department of Workforce Development  
for the Department of Transportation  
Pursuant to s. 103.50, Stats.  
Issued on April 1, 2012

**CLASSIFICATION:** Contractors are required to call the Department of Workforce Development if there are any questions regarding the proper trade or classification to be used for any worker on a public works project.

**OVERTIME:** Time and one-half must be paid for all hours worked over 10 hours per day and 40 hours per calendar week and for all hours worked on Saturday, Sunday and the following six (6) holidays: January 1; the last Monday in May; July 4; the 1st Monday in September; the 4th Thursday in November; December 25; the day before if January 1, July 4 or December 25 falls on a Saturday; the day following if January 1, July 4 or December 25 falls on a Sunday.

**FUTURE INCREASE:** If indicated for a specific trade or occupation, the full amount of such increase MUST be added to the "TOTAL" indicated for such trade or occupation on the date(s) such increase(s) becomes effective.

**PREMIUM PAY:** If indicated for a specific trade or occupation, the full amount of such pay MUST be added to the "HOURLY BASIC RATE OF PAY" indicated for such trade or occupation, whenever such pay is applicable.

**SUBJOURNEY:** Wage rates may be available for some of the classifications indicated below. Any employer that desires to use any subjourney classification on a project MUST request the applicable wage rate from the Department of Workforce Development PRIOR to the date such classification is used on such project. Form ERD-10880 is available for this purpose and can be obtained by writing to the Department of Workforce Development, Equal Rights Division, P.O. Box 8928, Madison, WI 53708.

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Bricklayer, Blocklayer or Stonemason	32.66	15.92	48.58
Carpenter	29.06	15.16	44.22
Cement Finisher	29.35	15.15	44.50
Electrician	27.40	16.54	43.94
Future Increase(s): Add \$.50/hr. on 06/04/2012			
Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Fence Erector	35.62	0.00	35.62
Ironworker	30.90	19.11	50.01
Line Constructor (Electrical)	35.97	18.08	54.05
Painter	21.87	10.07	31.94
Pavement Marking Operator	26.52	16.09	42.61
Piledriver	29.56	15.16	44.72
Roofer or Waterproofor	18.00	4.58	22.58
Teledata Technician or Installer	21.26	11.75	33.01
Tuckpointer, Caulker or Cleaner	30.65	13.08	43.73
Underwater Diver (Except on Great Lakes)	36.20	18.81	55.01
Heavy Equipment Operator - ELECTRICAL LINE CONSTRUCTION ONLY	35.42	12.90	48.32
Light Equipment Operator -ELECTRICAL LINE CONSTRUCTION ONLY	35.50	14.27	49.77
Heavy Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	25.18	13.07	38.25
Light Truck Driver - ELECTRICAL LINE CONSTRUCTION ONLY	23.38	12.48	35.86
Groundman - ELECTRICAL LINE CONSTRUCTION ONLY	21.30	10.97	32.27

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
<b>TRUCK DRIVERS</b>			
Single Axle or Two Axle	22.35	16.19	38.54
Future Increase(s): Add \$1.75/hr on 6/1/2012; Add \$1.85/hr on 6/1/2013.			
Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Three or More Axle	22.50	16.19	38.69
Future Increase(s): Add \$1.75/hr on 6/1/2012; Add \$1.85/hr on 6/1/2013.			
Premium Pay: DOT PREMIUM: Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day.			
Articulated, Euclid, Dumptror, Off Road Material Hauler	26.77	18.90	45.67
Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14.			
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Pavement Marking Vehicle	23.99	14.64	38.63
Shadow or Pilot Vehicle	24.76	15.35	40.11
Truck Mechanic	24.91	15.35	40.26

**LABORERS**

General Laborer	26.92	13.45	40.37
Future Increase(s): Add \$1.60/hr on 6/1/2012; Add \$1.70/hr on 6/1/2013; Add \$1.60/hr on 6/1/2014.			
Premium Pay: Add \$.10/hr for topman, air tool operator, vibrator or tamper operator (mechanical hand operated), chain saw operator and demolition burning torch laborer; Add \$.15/hr for bituminous worker (raker and luteman), formsetter (curb, sidewalk and pavement) and strike off man; Add \$.20/hr for blaster and powderman; Add \$.25/hr for bottomman; Add \$.35/hr for line and grade specialist; Add \$.45/hr for pipelayer.			
DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Asbestos Abatement Worker	23.96	12.88	36.84
Landscaoper	26.92	13.45	40.37
Future Increase(s): Add \$1.60/hr on 6/1/12; Add \$1.70/hr on 6/1/13; Add \$1.60/hr on 6/1/14.			
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Flagperson or Traffic Control Person	23.55	13.45	37.00
Future Increase(s): Add \$1.60/hr on 6/1/2012; Add \$1.70/hr on 6/1/2013; Add \$1.60/hr on 6/1/2014.			
Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr when the Wisconsin Department of Transportation or responsible governing agency requires that work be performed at night under artificial illumination with traffic control and the work is completed after sunset and before sunrise.			
Fiber Optic Laborer (Outside, Other Than Concrete Encased)	17.50	0.82	18.32

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Railroad Track Laborer	23.96	12.88	36.84

### HEAVY EQUIPMENT OPERATORS

Crane, Tower Crane, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 176 Ft or Over; Crane, Tower Crane, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of Over 100 Tons, Self-Erecting Tower Crane With a Lifting Capacity Of Over 4,000 Lbs., Crane With Boom Dollies; Traveling Crane (Bridge Type).	34.22	18.90	53.12
--	-------	-------	-------

Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14.

Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).

Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of 130,000 Lbs. or Over; Caisson Rig; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With Boom, Leads &/or Jib Lengths Measuring 175 Ft or Under; Crane, Tower Crane, Portable Tower, Pedestal Tower or Derrick, With or Without Attachments, With a Lifting Capacity of 100 Tons or Under, Self-Erecting Tower Crane With A Lifting Capacity Of 4,000 Lbs., & Under; Dredge (NOT Performing Work on the Great Lakes); Licensed Boat Pilot (NOT Performing Work on the Great Lakes); Pile Driver.	33.72	18.90	52.62
--	-------	-------	-------

Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14.

Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).

Air Track, Rotary or Percussion Drilling Machine &/or Hammers, Blaster; Asphalt Heater, Planer & Scarifier; Asphalt Milling Machine; Asphalt Screed; Automatic Subgrader (Concrete); Backhoe (Track Type) Having a Mfgr.'s Rated Capacity of Under 130,000 Lbs., Backhoe (Mini, 15,000 Lbs. & Under); Bituminous (Asphalt) Plant & Paver, Screed; Boatmen (NOT Performing Work on the Great Lakes); Boring Machine (Directional, Horizontal or Vertical); Bridge (Bidwell) Paver; Bulldozer or Endloader; Concrete Batch Plant, Batch Hopper; Concrete Breaker (Large, Auto, Vibratory/Sonic, Manual or Remote); Concrete Bump Cutter, Grinder, Planing or Grooving Machine; Concrete Conveyor System; Concrete Laser/Screed; Concrete Paver (Slipform); Concrete Pump, Concrete Conveyor (Rotec or Bidwell Type); Concrete Slipform Placer Curb & Gutter Machine; Concrete Spreader & Distributor; Crane (Carry Deck, Mini) or Truck Mounted Hydraulic Crane (10 Tons or Under); Crane With a Lifting Capacity of 25 Tons or Under; Forestry Equipment, Timbco, Tree Shear, Tub Grinder, Processor; Gradall (Cruz-Aire Type); Grader or Motor Patrol; Grout Pump; Hydro-Blaster (10,000 PSI or Over); Loading Machine (Conveyor); Material or Stack Hoist; Mechanic or Welder; Milling Machine; Post Hole Digger or Driver; Roller (Over 5 Ton); Scraper (Self Propelled or Tractor Drawn) 5 cu yds or More Capacity; Shoulder Widener; Sideboom; Skid Rig; Stabilizing or Concrete Mixer (Self-Propelled or 14S or Over); Straddle Carrier or Travel Lift; Tractor (Scraper, Dozer, Pusher, Loader); Tractor or	33.22	18.90	52.12
---	-------	-------	-------

<u>TRADE OR OCCUPATION</u>	<u>HOURLY BASIC RATE OF PAY</u>	<u>HOURLY FRINGE BENEFITS</u>	<u>TOTAL</u>
	\$	\$	\$
Truck Mounted Hydraulic Backhoe; Trencher (Wheel Type or Chain Type); Tube Finisher; Tugger (NOT Performing Work on the Great Lakes); Winches & A- Frames. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).			
Belting, Burlap, Texturing Machine; Broom or Sweeper; Compactor (Self-Propelled or Tractor Mounted, Towed & Light Equipment); Concrete Finishing Machine (Road Type); Environmental Burner; Farm or Industrial Type Tractor; Fireman (Asphalt Plant, Pile Driver & Derrick NOT Performing Work on the Great Lakes); Forklift; Greaser; Hoist (Tugger, Automatic); Jeep Digger; Joint Sawyer (Multiple Blade); Launch (NOT Performing Work on the Great Lakes); Lift Slab Machine; Mechanical Float; Mulcher; Power Subgrader; Robotic Tool Carrier (With or Without Attachments); Roller (Rubber Tire, 5 Ton or Under); Self Propelled Chip Spreader; Shouldering Machine; Skid Steer Loader (With or Without Attachments); Telehandler; Tining or Curing Machine. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).	32.96	18.90	51.86
Air Compressor (&/or 400 CFM or Over); Air, Electric or Hydraulic Jacking System; Augers (Vertical & Horizontal); Automatic Belt Conveyor & Surge Bin; Boiler (Temporary Heat); Concrete Proportioning Plant; Crusher, Screening or Wash Plant; Generator (&/or 150 KW or Over); Heaters (Mechanical); High Pressure Utility Locating Machine (Daylighting Machine); Mudjack; Oiler; Prestress Machine; Pug Mill; Pump (3 Inch or Over) or Well Points; Rock, Stone Breaker; Screed (Milling Machine); Stump Chipper; Tank Car Heaters; Vibratory Hammer or Extractor, Power Pack. Future Increase(s): Add \$2/hr on 6/1/12; Add \$2/hr on 6/1/13; Add \$1.75/hr on 6/1/14. Premium Pay: DOT PREMIUMS: 1) Pay two times the hourly basic rate on Sunday, New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day & Christmas Day. 2) Add \$1.25/hr for work on projects involving temporary traffic control setup, for lane and shoulder closures, when work under artificial illumination conditions is necessary as required by the project provisions (including prep time prior to and/or cleanup after such time period).	33.22	18.90	52.12
Fiber Optic Cable Equipment.	26.00	0.90	26.90

## Wisconsin Department of Transportation

PAGE: 1

DATE: 01/15/13

REVISED:

## SCHEDULE OF ITEMS

CONTRACT:  
20130312030PROJECT(S):  
6749-00-70FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

## SECTION 0001 ROADWAY

0010	201.0105 CLEARING	9.000				
	STA		.		.	
0020	201.0205 GRUBBING	9.000				
	STA		.		.	
0030	203.0200 REMOVING OLD STRUCTURE (STATION) 01. 50+00	LUMP	LUMP			.
0040	203.0225.S DEBRIS CONTAINMENT (STRUCTURE) 01. B-39-74	LUMP	LUMP			.
0050	204.0165 REMOVING GUARDRAIL	200.000				
	LF		.		.	
0060	205.0100 EXCAVATION COMMON **P**	3,800.000				
	CY		.		.	
0070	206.1000 EXCAVATION FOR STRUCTURES BRIDGES (STRUCTURE) 01. B-39-74	LUMP	LUMP			.
0080	208.0100 BORROW	28,580.000				
	CY		.		.	
0090	210.0100 BACKFILL STRUCTURE	200.000				
	CY		.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20130312030PROJECT(S):  
6749-00-70FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0100	213.0100 FINISHING ROADWAY (PROJECT) 01. 6749-00-70	1.000 EACH	.		.	
0110	305.0110 BASE AGGREGATE DENSE 3/4-INCH	230.000 TON	.		.	
0120	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH	1,970.000 TON	.		.	
0130	416.1010 CONCRETE SURFACE DRAINS	2.500 CY	.		.	
0140	455.0105 ASPHALTIC MATERIAL PG58-28	40.000 TON	.		.	
0150	455.0605 TACK COAT	70.000 GAL	.		.	
0160	460.1100 HMA PAVEMENT TYPE E-0.3	650.000 TON	.		.	
0170	460.2000 INCENTIVE DENSITY HMA PAVEMENT	500.000 DOL	1.00000		500.00	
0180	502.0100 CONCRETE MASONRY BRIDGES **P**	377.000 CY	.		.	
0190	502.3200 PROTECTIVE SURFACE TREATMENT **P**	580.000 SY	.		.	
0200	503.0136 PRESTRESSED GIRDER TYPE I 36-INCH	634.000 LF	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20130312030PROJECT(S):  
6749-00-70FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	505.0405 BAR STEEL REINFORCEMENT HS BRIDGES **P**	8,190.000 LB	.		.	
0220	505.0605 BAR STEEL REINFORCEMENT HS COATED BRIDGES **P**	68,840.000 LB	.		.	
0230	506.2605 BEARING PADS ELASTOMERIC NON-LAMINATED	24.000 EACH	.		.	
0240	506.4000 STEEL DIAPHRAGMS (STRUCTURE) 01. B-39-74	9.000 EACH	.		.	
0250	516.0500 RUBBERIZED MEMBRANE WATERPROOFING	20.000 SY	.		.	
0260	520.0124 CULVERT PIPE CLASS III 24-INCH	40.000 LF	.		.	
0270	520.1024 APRON ENDWALLS FOR CULVERT PIPE 24-INCH	2.000 EACH	.		.	
0280	550.2126 PILING CIP CONCRETE 12 3/4 X 0. 375-INCH	2,450.000 LF	.		.	
0290	604.0500 SLOPE PAVING CRUSHED AGGREGATE	391.000 SY	.		.	
0300	606.0200 RIPRAP MEDIUM	11.000 CY	.		.	
0310	614.0150 ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	4.000 EACH	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20130312030PROJECT(S):  
6749-00-70FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	619.1000 MOBILIZATION	1.000				
	EACH		.		.	
0330	624.0100 WATER	11.000				
	MGAL		.		.	
0340	625.0500 SALVAGED TOPSOIL	10,950.000				
	SY		.		.	
0350	627.0200 MULCHING	11,100.000				
	SY		.		.	
0360	628.1504 SILT FENCE	2,780.000				
	LF		.		.	
0370	628.1520 SILT FENCE MAINTENANCE	2,780.000				
	LF		.		.	
0380	628.1905 MOBILIZATIONS EROSION CONTROL	3.000				
	EACH		.		.	
0390	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL	3.000				
	EACH		.		.	
0400	628.2004 EROSION MAT CLASS I TYPE B	8,300.000				
	SY		.		.	
0410	628.6505 SOIL STABILIZER TYPE A	1.730				
	ACRE		.		.	
0420	628.7504 TEMPORARY DITCH CHECKS	224.000				
	LF		.		.	



## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20130312030PROJECT(S):  
6749-00-70FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	629.0210 FERTILIZER TYPE B	13.000 CWT	.		.	
0440	630.0120 SEEDING MIXTURE NO. 20	180.000 LB	.		.	
0450	630.0200 SEEDING TEMPORARY	20.000 LB	.		.	
0460	633.5100 MARKERS ROW	17.000 EACH	.		.	
0470	634.0612 POSTS WOOD 4X6-INCH X 12-FT	9.000 EACH	.		.	
0480	637.0202 SIGNS REFLECTIVE TYPE II	48.250 SF	.		.	
0490	638.2602 REMOVING SIGNS TYPE II	7.000 EACH	.		.	
0500	638.3000 REMOVING SMALL SIGN SUPPORTS	5.000 EACH	.		.	
0510	642.5201 FIELD OFFICE TYPE C 01. 6749-00-70	1.000 EACH	.		.	
0520	643.0100 TRAFFIC CONTROL (PROJECT) 01. 6749-00-70	1.000 EACH	.		.	
0530	643.0300 TRAFFIC CONTROL DRUMS	1,680.000 DAY	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20130312030PROJECT(S):  
6749-00-70FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	643.0420 TRAFFIC CONTROL BARRICADES TYPE III	392.000 DAY	.		.	
0550	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A	560.000 DAY	.		.	
0560	643.0900 TRAFFIC CONTROL SIGNS	964.000 DAY	.		.	
0570	645.0130 GEOTEXTILE FABRIC TYPE R	45.000 SY	.		.	
0580	646.0106 PAVEMENT MARKING EPOXY 4-INCH	4,800.000 LF	.		.	
0590	650.4500 CONSTRUCTION STAKING SUBGRADE	1,285.000 LF	.		.	
0600	650.5000 CONSTRUCTION STAKING BASE	1,285.000 LF	.		.	
0610	650.6000 CONSTRUCTION STAKING PIPE CULVERTS	1.000 EACH	.		.	
0620	650.6500 CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE) 01. B-39-74	LUMP	LUMP		.	
0630	650.9910 CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) 01. 6749-00-70	LUMP	LUMP		.	

## Wisconsin Department of Transportation

PAGE: 7

DATE: 01/15/13

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20130312030PROJECT(S):  
6749-00-70FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0640	650.9920 CONSTRUCTION STAKING SLOPE STAKES	1,285.000 LF	.		.	
0650	690.0150 SAWING ASPHALT	40.000 LF	.		.	
0660	715.0502 INCENTIVE STRENGTH CONCRETE STRUCTURES	1,537.000 DOL	1.00000		1537.00	
0670	SPV.0060 SPECIAL 01. TEMPORARY SEDIMENT TRAP	5.000 EACH	.		.	
0680	SPV.0105 SPECIAL 01. TEMPORARY SHORING RAILROAD	LUMP	LUMP		.	
	SECTION 0001 TOTAL				.	
	TOTAL BID				.	



**PLEASE ATTACH SCHEDULE OF ITEMS HERE**